RICHARD V. HOLLYER<sup>\*\*</sup> ROBERT T. MORGENSTERN▲ ROGER W. THOMAS<sup>•</sup> WILLIAM T. HAGGERTY EILEEN McCARTHY BORN<sup>\*\*\*</sup> CHARLES J. BRAND<sup>•</sup> CATHERINE ANNE GACQUIN<sup>\*\*+</sup>

+

▲ CERTIFIED CIVIL TRIAL ATTORNEY \*\*\* ALSO MEMBER NY BAR \*\*\*\* ALSO MEMBER PA BAR \*\*\*\* ALSO MEMBER NY, CA BARS • CERTIFIED WORKERS COMPENSATION ATTORNEY ◆ CPA, L.L.M. (TAXATION)

+ APPROVED BY THE SUPREME COURT OF NEW JERSEY AS A FAMILY LAW MEDIATOR

William T. Haggerty, Esq. whaggerty@dolanlaw.com (973) 383-1600 ext. 105

## **DOLAN AND DOLAN**

A PROFESSIONAL CORPORATION ATTORNEYS AT LAW WILLIAM A. DOLAN (1905-1952) LEWIS P. DOLAN (1921-1974)

ONE LEGAL LANE (AT FIFTY-THREE SPRING STREET) P.O. BOX D NEWTON, N.J. 07860-0106

(973) 383-1600 FAX (973) 383-7823 E-mail: dolananddolan@dolanlaw.com http://www.dolanlaw.com MICHELLE M. CORBETT-RIVIELLE \*\*\*\* KAREN GRECO-BUTA

#### OF COUNSEL

F. CLIFFORD GIBBONS KATHLEEN M. McNAMARA

> WILLIAM M. COX (1950 - 2011)

April 5, 2021

## Via Electronic Mail Only

cstoner@hpellow.com Cory Stoner, P.E. Harold E. Pellow & Associates, Inc. 17 Plains Road Augusta, NJ 07822

#### **RE:** <u>BHT Properties</u>

Andover Township Land Use Board 248 Stickles Pond Road Block 151, Lot 21

Dear Mr. Stoner:

I received your report dated March 31, 2021. Attached hereto please find the following:

- 1. Traffic Impact Study for Proposed Construction Equipment & Material Storage Facility prepared by Dynamic Traffic, revised February 4, 2021.
- 2. Document entitled "Construction Business Office and Construction Equipment and Material Storage" providing property information. Description of construction materials/equipment and site operations.
- 3. Building Floorplan prepared by The Hill Architect Firm, revised February 5, 2021.
- 4. Updated Environmental Impact Study bearing most recent revision date January 26, 2021.

A description of the nature of the proposed use is set forth therein as follows:

The proposed project consists of the construction of a construction office with construction equipment and material storage areas on the property located on 248 Stickles Pond Road, on Lot 151, Block 21 in Andover Township, Sussex County, New Jersey. The 100-acre subject property currently consists of a former airport. The proposed project consists of the demolition of hangars, paved drives, concrete pads, three dwellings, two garages, and three sheds. The existing 112,050 square foot asphalt runway is to remain. The proposed construction consists of a 12,860 square foot building, 2,883 square feet of concrete sidewalk and curbing, lighting and landscape improvements, 35,235 square feet to be paved with asphalt for parking and circulation and 1,822,812 square feet to be paved with asphalt millings and used as construction equipment and material storage area. The materials to be stored in site are stone, aggregate, precast concrete structures and other typical natural construction materials.

I am responding to certain paragraphs of your report as indicated.

## 3. Completeness Comments

- a. <u>Updated Environmental Impact Statement</u>. Enclosed herewith.
- b. <u>Updated Traffic Impact Study</u>. Enclosed herewith.
- c. <u>Project Narrative</u>. See above.
- d. <u>Updated Architectural Drawings</u>. Floor Plans/Construction Document attached.

## 4. Zoning Comments.

b. The existing home on the site will be removed.

## 5. Site Plan Layout & Parking.

- b. The proposed building is the same building as submitted for the prior proposed use.
- c. A waiver is requested for parking lot spaces to permit 9 x 18 ft. spaces.
- d. A design waiver is requested for the absence of a loading space.
- e. A design waiver is requested for the fence height. The extra fence height is to provide additional visual screening. The fence type as previously proposed is now proposed.
- f. A waiver is requested for not paving all parking areas.
- g. A waiver request is made for absence of curbing for proposed parking areas.
- 6. <u>Stormwater Management</u>. The Applicant's Engineer will address the concerns as set forth.
- 7. <u>Architectural Plans</u>. See attached Floor Plans/Construction Document.

#### 9. Signage.

a. The proposed signage will be redesigned to comply with the ordinance requirements.

#### 10. Environmental Comments & Permits.

- a. Environmental Impact Statement. Enclosed herewith.
- b. Freshwater Wetlands.

Very truly yours,

DOLAN & DOLAN, PA

WilliamTHOR

William T. Haggerty

WTH:jm Enclosures

cc: Ram Adar (via email: ram@bhtpropertiesgroup.com) Lula Elharar (via email: <u>PM18@bhtpropertiesgroup.com</u>) Alex Tukh (via email: alext@bhtpropertiesgroup.com) Wayne J. Ingram, PE (via email: Wayne@elp-inc.com) Corey Chase (via email: cchase@dynamictraffic.com) Stephanie Pizzulo, Administrator (via email: spizzulo@andovertwp.org) Thomas J. Molica Jr., Esq.(via email: tmolica@vccslaw.com) Liz Durkin, Esq. (via email: ldurkin@durkinfirm.com)

## **TRAFFIC IMPACT STUDY**

For

BHT Properties Group, LLC Proposed Construction Equipment & Materials Storage Facility

**Property Located at:** 

248 Stickles Pond Road Block 151 – Lot 21 Township of Andover, Sussex County, NJ



 1904 Main Street
 245 Main Street, Suite #110

 Lake Como, NJ 07719
 Chester, NJ 07930

 (732) 681-0760

Corey Chase, PE NJ PE License #47470

Craig Peregoy, PE NJ PE License #45880

August 6, 2020 Revised: February 4, 2021

3527-99-001TE

NED



### INTRODUCTION

It is proposed to construct a construction equipment and materials storage facility on a parcel of land currently occupied by a former airport runway, located along the westbound side of Stickles Pond Road east of US Route 206 in Andover Township, Sussex County, New Jersey, see Figure 1 in Appendix A. The site is designated as Block 151 – Lot 21 on the Township of Andover Tax Maps. It is proposed to develop the site with a construction materials and equipment storage facility, including the construction of a 12,860 SF office (The Project). The site will serve as an outdoor storage facility for special order construction materials and equipment with a construction business office and receiving area. The site is located within the C/I – Commercial Industrial District. Access to the site is proposed to be provided via a left/right turn in/right turn out driveway along Stickles Pond Road.

Dynamic Traffic LLC has been retained to prepare this study to assess the traffic impact associated with the construction of The Project on the adjacent roadway network. This study documents the methodology, analyses, findings and conclusions of our study and includes:

- A detailed field inspection was conducted to obtain an inventory of existing roadway geometry, traffic control, and location and geometry of existing driveways and intersections.
- Existing traffic data was collected via manual turning movement (MTM) counts during the weekday AM and weekday PM peak periods at the intersection of:
  - US Route 206 and Greendale Road (CR 611)/Stickles Pond Road
- Existing traffic volumes were normalized based on historical data to account for impacts caused by COVID-19.
- Projections of traffic to be generated by the proposed development were prepared based upon the operational characteristics of the facility as provided by the client. Site traffic was then assigned to the adjacent street system based upon the anticipated directional distribution.
- Capacity analyses were conducted for the Existing, No Build, and Build conditions for the study intersections.
- The proposed point of ingress and egress was inspected for adequacy of geometric design, spacing and/or alignment to streets and driveways on the opposite side of the street, relationship to other driveways adjacent to the development, and conformance with accepted design standards.
- The site plan as designed was reviewed for sufficiency in accommodating large wheel base vehicles such as delivery trucks, refuse trucks, and emergency vehicles.
- The parking layout and supply was assessed based on accepted design standards, local requirements, and operational characteristics.



### **EXISTING CONDITIONS**

A review of the existing roadway conditions near the proposed site was conducted to provide the basis for assessing the traffic impact of the development. This included field investigations of the surrounding roadways and intersections, collection of traffic volume data, and extensive analyses.

#### **Existing Roadway Conditions**

The following are descriptions of the roadways in the study area:

<u>US Route 206</u> is a Rural Principal Arterial roadway under New Jersey Department of Transportation (NJDOT) jurisdiction with a general north/south orientation. In the vicinity of the site the posted speed limit is 50 MPH and the roadway provides one travel lane in each direction. On-street parking is not permitted. Curbing is provided along the frontage of certain developments, while sidewalk is not provided along either side of the roadway. US Route 206 provides a slightly curved horizontal alignment and a rolling vertical alignment. The land uses along US Route 206 in the vicinity of The Project are primarily commercial.

<u>Greendale Road (CR 611)</u> is a Rural Minor Collector under Sussex County jurisdiction with a general east/west orientation. In the vicinity of the site the posted speed limit is 40 MPH and the roadway provides one travel lane in each direction. On-street parking is not permitted, and curb and sidewalk are not provided along either side of the roadway. Greendale Road provides a curved horizontal alignment and a downgrade from east to west. The land uses along Greendale Road in the vicinity of The Project are primarily residential.

<u>Stickles Pond Road</u> is an Urban Local roadway under Andover Township jurisdiction with a general east/west orientation. In the vicinity of the site the posted speed limit is 35 MPH and the roadway provides on travel lane in each direction. On-street parking is not permitted, and curb and sidewalk are not provided along either side of the roadway. Stickles Pond Road provides a curved horizontal and a downgrade from east to west. The land uses along Stickles Pond Road in the vicinity of The Project are a mixture of industrial and residential.

#### **Existing Traffic Volumes**

Manual turning movement (MTM) counts were conducted on Thursday, July 30, 2020 from 7:00 to 9:00 AM and from 4:30 to 6:30 PM at the intersection of US Route 206 and Greendale Road (CR 611)/Stickles Pond Road. Review of the collected traffic data reveals that the weekday morning peak street hour (PSH) occurs between 7:30 - 8:30 AM and the weekday evening PSH occurs between 4:30 - 5:30 PM. Note that the 2020 counts were increased to better represent existing 2021 traffic volumes by applying a growth rate of 1.75% per year obtained from the NJDOT Annual Background Growth Rate Table for a period of one year. Figure 2, located in the Appendix, shows the existing peak hour traffic volumes at the study intersections. All traffic counts are contained in Appendix B.

It should be noted that various protocols associated with the COVID-19 pandemic were in effect as of the time of the traffic counts. As a result, current traffic volumes on the surrounding roadways are atypically low at this time and would not be representative of "existing" traffic conditions. Therefore, historical traffic volume data has been reviewed and compared with current traffic conditions. The following Automatic Traffic Recorder (ATR) counts have been obtained from the NJDOT count database:



- US Route 206 north of Stickles Pond Road Tuesday, April 18, 2017
- Stickles Pond Road east of US Route 206 Wednesday, August 15, 2018
- Greendale Road west of US Route 206 Wednesday, August 15, 2018

In order to better represent 2021 traffic volumes, each NJDOT ATR count was grown utilizing its respective annual growth rate contained within the NJDOT Annual Background Growth Rate Table for the appropriate number of years. The historical traffic volumes representative of "existing" conditions were then compared to the MTM counts. The volumes along Route 206 were found to be higher than or representative of typical existing conditions, while the volumes along both Stickles Pond Road and Greendale Road were both found to be lower than the historical volumes representative of "existing" conditions. Adjustment factors of 1.51 and 1.17 were then applied to the eastbound approach weekday morning and weekday evening peak hour volumes, respectively. Additionally, the movements that were still less than the highest peak hour volumes of the historical volumes representative of "existing" conditions were also factored to develop traffic volumes that best represent typical "existing" conditions. Located in Appendix A, Figure 3 shows the adjusted existing peak hour traffic volumes at the study intersections.

#### **Existing Capacity Analysis**

The methodology utilized in the capacity analyses is described in the *Highway Capacity Manual*, published by the Transportation Research Board. In general, the term Level of Service (LOS) is used to provide a "qualitative" evaluation of capacity based upon certain "quantitative" calculations related to empirical values, such as traffic volume and intersection control.

At signalized intersections, factors that affect the various approach capacities include width of approach, number of lanes, signal "green time", turning percentages, truck volumes, etc. However, delays cannot be related to capacity in a simple one-to-one fashion. For example, it is possible to have delays in the Level of Service "F" range without exceeding roadway capacity. Substantial delays can exist without exceeding capacity if one or more of the following conditions exist: long signal cycle lengths; a particular traffic movement experiences a long red time; or progressive movement for a particular lane group is poor. Table I describes the level of service ranges for signalized intersections.

An unsignalized (STOP sign controlled) driveway or side street along a through route is seldom critical from an overall capacity standpoint, however, it may be of great significance to the capacity of the minor cross-route, and it may influence the quality of traffic flow on both. When analyzing an unsignalized intersection, it is assumed that both the major street through and right turn movements are unimpeded and have the right-of-way over all side street traffic and left turns from the major street. All other turning movements in the intersection cross, merge with, or are otherwise impeded by major street movements. Traffic delays at unsignalized intersections are determined by sequentially processing these impeded movements. Table II describes the level of service ranges for unsignalized (stop controlled) intersections.



Table ILevel of Service Criteriafor Signalized Intersections

Level of Service	Average Control Delay (seconds per vehicle)
А	0.0 to 10.0
В	10.1 to 20.0
С	20.1 to 35.0
D	35.1 to 55.0
E	55.1 to 80.0
F	greater than 80.0

	Ta	able II			
Leve	l of S	ervice (	Crite	eria	
for Uns	ignali	ized Int	erse	ctions	S
1 0		0		1 D	

Level of	Average Control Delay								
Service	(seconds per vehicle)								
а	0.0 to 10.0								
b	10.1 to 15.0								
С	15.1 to 25.0								
d	25.1 to 35.0								
e	35.1 to 50.0								
f	greater than 50.0								

It should be noted that the analyses within the *Highway Capacity Manual* assume a random arrival for all the movements, which may not be the case if an adjacent traffic signal is present that platoons vehicles, such as the signalized intersection of Route 206 and Greendale Road (CR 611)/Stickles Pond Road.

All capacity analyses were performed utilizing Synchro 11 software. Table III summarizes the existing levels of service (LOS) and delays. All capacity analysis calculation worksheets are contained in Appendix C.

Table III       Existing Length of Counting											
Existing Levels of Service											
Intersection		ction/ ement	AM PSH	PM PSH							
	БD	LT	D (47)	D (47)							
	EB	R	A (0)	A (2)							
Route 206 & Greendale Road/	WB	LTR	C (30)	C (32)							
Stickles Pond Road	NB	LTR	A (9)	B (13)							
	SB	LTR	B (13)	B (12)							
	Ov	erall	B (17)	B (18)							

A (#) - Signalized Intersection Level of Service (seconds of delay per vehicle)

The following are discussions pertaining to each of the existing intersections analyzed. It should be noted that the existing percentage of trucks and peak hour factors were used in the existing analysis.

#### Route 206 and Greendale Road/Stickles Pond Road

Greendale Road and Stickles Pond Road both intersect Route 206 to form a four-leg intersection controlled by a traffic signal. The signal timing directive was obtained from the New Jersey Department of Transportation which indicates that a two-phase variable background cycle is utilized (the traffic signal timing directive is included in Appendix B).

The eastbound approach of Greendale Road provides a shared left turn/through lane and a dedicated right turn lane, while the westbound approach of Stickles Pond Road provides a shared left turn/through/right turn lane. The northbound and southbound approaches of Route 206 both provide a shared left turn/through/right turn lane.



A review of the existing analysis reveals that the intersection operates at overall levels of service "B" and all movements operate at levels of service "D" or better during the analyzed peak periods. See Table III for the individual movement levels of service and delays.



#### **FUTURE CONDITIONS**

Traffic volumes and operational analyses were developed for both the 2023 No Build and Build conditions. The No Build conditions provide a baseline for assessing the impact of the site development traffic on the roadway system. The process of developing the No Build and Build traffic volumes and the subsequent analyses is outlined below.

Regardless of whether the subject site is developed or not, traffic volumes on the surrounding roadways are expected to increase as a result of developments throughout the region. A growth rate for roadways within the study area was obtained from the NJDOT Annual Background Growth Rate Table, which indicates a growth rate of 1.75% per year.

Through consultation with the Andover Township Planning Board staff, there are no other developments in the vicinity of the site that have been approved but not yet constructed that are identified as significant traffic generators. It was assumed that the background growth rate was adequate to account for the traffic associated with all developments not listed.

Future 2023 No Build traffic volumes were developed by applying the background growth rate of 1.75% for two (2) years to the study area roadways existing traffic volumes. Figure 4, in Appendix A, shows the 2023 No Build traffic volumes.

#### **Traffic Generation**

There is presently no data published for construction equipment and material storage facilities or uses of similar operation within the Institute of Transportation Engineers' (ITE) publication, *Trip Generation*,  $10^{th}$  *Edition*. Therefore, in order to provide the most accurate estimates for the use, trip generation for The Project was based upon operational characteristics as provided by the client. It is our understanding that the proposed facility will operate with a maximum of 20 full time employees and there will be approximately 150 trips per day associated with the pick-up and delivery of the equipment and materials. Conservatively, it was assumed that all employees enter and exit the site during the same peak hour. It should be noted that the hours of operation will be from 8:00 AM – 5:00 PM, which was considered when calculating the number of peak hour deliveries. The following table details the proposed trip generation for The Project.

	Trip Generation											
Tribe Tr		Daily AM PSH PM PSH										
Trip T	In	Out	Total	In	Out	Total	In	Out	Total			
Construction	Cars (Employees)	20	20	40	20	0	20	0	20	20		
Equipment & Materials	Trucks (Deliveries)	75	75	150	9	8	17	8	9	17		
Storage Facility	Total	95	95	190	29	8	37	8	29	37		

Table IV	
<b>Frin Generation</b>	

As seen above, The Project is anticipated to generate a maximum of 37 new peak hour trips, which is below the industry accepted standard of a significant increase in traffic of 100 trips. Based on *Transportation Impact Analysis for Site Development*, published by the ITE "it is suggested that a transportation impact study be conducted whenever a proposed development will generate 100 or more added (new) trips during the adjacent roadways' peak hour or the development's peak hour." Additionally, NJDOT has determined that the same 100 vehicle threshold is considered a "significant increase in traffic," hence, it is not anticipated that The Project will have any perceptible impact on the traffic operation of the adjacent roadway network.



Once the magnitude of traffic to be generated by the site is known, it is necessary to assign that traffic to the adjacent street system. The distribution of new traffic to the surrounding roadways is based on the location of primary arterial roadways, major signalized intersections and existing traffic patterns. Table V below summarizes the anticipated trip distribution for The Project.

Trip Distribution										
To/From	Percentage									
10/ FIOM	In	Out								
Greendale Road – East	10%	-								
Greendale Road – West	10%	10%								
Route 206 – North	40%	50%								
Route 206 – South	40%	40%								
Total	100%	100%								

Table V	
Trip Distribu	tion

Located in Appendix A, Figure 5 illustrates the total site generated volumes assigned to the study area network. The site generated volumes were added to the No Build traffic volumes to generate the Build traffic volumes, which are shown in Figure 6.

#### **Future Capacity Analysis**

Operational conditions at the study intersections were analyzed under the No Build and Build conditions and are summarized in Table VI below.

Future Levels of Service												
	Dira	tion /	AM	PSH	PM PSH							
Intersection	Direction/ Movement		No Build	Build	No Build	Build	Build w/ Mit.					
	EB	LT	D (49)	D (49)	D (48)	D (51)	D (43)					
Devite 206 & Green dela	ED	R	A (0)	A (0)	A (2)	A (2)	A (2)					
Route 206 & Greendale Road/Stickles Pond	WB	LTR	C (31)	C (34)	C (32)	D (40)	C (35)					
Road	NB	LTR	A (9)	A (10)	B (14)	B (14)	B (16)					
Koad	SB	LTR	B (14)	B (15)	B (14)	B (15)	B (16)					
	Ove	erall	B (18)	B (19)	B (19)	C (21)	C (21)					
Stickles Pond Road	EB	L	-	a (8)	-	a (9)	-					
& Site Driveway	SB	R	-	b (11)	-	b (10)	-					

# Table VI

a (#) - Unsignalized Intersection Level of Service (seconds of delay per vehicle) A (#) - Signalized Intersection Level of Service (seconds of delay per vehicle)

#### Route 206 and Greendale Road/Stickles Pond Road

With the addition of site generated traffic, the intersection is anticipated to operate at overall intersection levels of service "C" or better during the analyzed peak hours. It should be noted that the westbound left turn/through/right turn movement is anticipated to degrade from No Build level of service "C" to Build level of service "D" during the weekday evening peak hour. However, with the reallocation of 3 seconds of green time from the Route 206 phase to the Greendale Road/Stickles Pond Road phase during the weekday evening peak hour, the No Build level of service can be maintained. See Table VI for the individual movement levels of service and delays.



#### Stickles Pond Road and Site Driveway

The site driveway is proposed to intersect Stickles Pond Road to form an unsignalized T-intersection with the southbound approach of the site driveway operating under stop control. The eastbound approach of Stickles Pond Road is proposed to provide a shared left turn/through lane, while the westbound approach is proposed to provide a shared through/right turn lane. The southbound approach of the site driveway is proposed to provide a right turn lane.

As designed, the driveway is anticipated to operate at levels of service "B" or better during the studied peak hours. See Table VI for the individual movement levels of service and delays.



### SITE PLAN

#### Site Access and Circulation

The site plan was reviewed with respect to the site access and on-site circulation design. As noted previously, access to The Project will be provided via a left/right turn in/right turn out driveway along Stickles Pond Road.

The parking lot will be serviced by parking aisles with widths of 24', which does not meet the Ordinance's minimum requirement of 25'. These aisles will safely and efficiently allow for two-way circulation and 90 degree parking and are consistent with accepted engineering design standards. Review of the site plan design indicates that the site can sufficiently accommodate, within paved areas, a large wheel base vehicle, such as a single unit truck (SU), or a tractor with a 53' trailer, along with the automobile traffic anticipated.

#### Parking

The site as proposed provides 62 parking spaces. As previously mentioned, the site will operate with a maximum of 20 employees, and all other trip generation will consist of deliveries and pick-ups. Therefore, the 62 parking spaces will be more than sufficient to support the demand of The Project. Additionally, ITE sets forth a peak parking demand of 2.51 parking spaces per 1,000 SF for general office buildings. This equates to a parking demand of 33 parking spaces for the 12,860 SF construction office, which is met as designed.

It is proposed to provide parking stalls with dimensions of 9'x18'. It should be noted that industry standards recommend stall widths of 9' and a length of 18' for low to moderate turnover parking stalls, which is met as designed.



### FINDINGS & CONCLUSIONS

#### Findings


Based upon the detailed analyses as documented herein, the following findings are noted:


- The proposed construction equipment and materials storage facility will generate 29 entering trips and 8 exiting trips during the weekday morning peak hour and 8 entering trips and 29 exiting trips during the evening peak hour that are "new" to the adjacent roadway network.
- Access to the site is proposed to be provided via a left/right turn in/right turn out driveway along Stickles Pond Road.
- With the addition of site generated traffic, the intersection is anticipated to operate at overall intersection levels of service "C" or better during the analyzed peak hours. It should be noted that the westbound left turn/through/right turn movement is anticipated to degrade from No Build level of service "C" to Build level of service "D" during the weekday evening peak hour. However, with the reallocation of 3 seconds of green time from the Route 206 phase to the Greendale Road/Stickles Pond Road phase during the weekday evening peak hour, the No Build level of service can be maintained.
- As designed, the intersection of Stickles Pond Road and the site driveway is anticipated to operate at acceptable levels of service "B" or better during the peak hours studied.
- As proposed, The Project's site driveways and internal circulation have been designed to provide for safe and efficient movement of automobiles and large wheel base vehicles.
- The proposed parking supply and design is sufficient to support the projected demand and exceeds ITE peak parking demand.


#### Conclusions


Based upon our Traffic Impact Study as detailed in the body of this report, it is the professional opinion of Dynamic Traffic LLC that the adjacent street system of the New Jersey Department of Transportation, Sussex County, and Andover Township will not experience any significant degradation in operating conditions with the construction of The Project. The site driveway is located to provide safe and efficient access to the adjacent roadway system. The site plan as proposed provides for good circulation throughout the site and provides adequate parking to accommodate The Project's needs.


Appendix A Traffic Volume Figures














Appendix B Project Information

## Dynamic Traffic, LLC 1904 Main Street, Lake Como, NJ 07719

1904 Main Street, Lake Como, NJ 07719 245 Main Street - Suite 110, Chester, NJ 07930 732-681-0760

E/W: Stickles Pond Rd N/S: Rt 206 Town/County: Andover/Sussex Job #: 3527-99-001TE File Name : Rt 206 and Stickles Pond Rd - AMPM Site Code : 00000000 Start Date : 7/30/2020 Page No : 1

										ars - Tr	ucks	(SU) ·	Truc	ks (TT	)	1					1
	Sti	ckles		Road	(CR	Sti	ckles		Road	(CR		R	oute	206			R	oute	206		
		E	(611 astbou				w	611) estbo			Northbound				Southbound						
Start Time	Left	Thru	Right	Peds	App. Total	Left	Thru	Right	Peds	App. Total	Left	Thru	Right	Peds	App. Total	Left	Thru	Right	Peds	App. Total	Int. Total
07:00 AM	10	5	3	0	18	2	6	5	0	13	2	65	10	0	77	7	116	6	1	130	238
07:15 AM	14	6	5	0	25	13	4	4	0	21	0	44	6	0	50	14	94	6	0	114	210
07:30 AM	17	12	3	0	32	4	5	9	0	18	3	104	14	0	121	16	137	10	0	163	334
07:45 AM	16	8	1	0	25	10	5	16	0	31	0	99	13	0	112	17	131	10	0	158	326
Total	57	31	12	0	100	29	20	34	0	83	5	312	43	0	360	54	478	32	1	565	1108
08:00 AM	11	12	3	0	26	4	7	8	0	19	5	115	6	0	126	23	118	11	0	152	323
08:15 AM	16	9	1	0	26	8	6	7	0	21	1	113	9	0	123	16	144	5	0	165	335
08:30 AM	13	12	3	0	28	7	3	8	1	19	1	92	5	0	98	21	126	13	0	160	305
08:45 AM	15	15	1	0	31	4	10	9	0	23	1	114	5	0	120	13	107	9	0	129	303
Total	55	48	8	0	111	23	26	32	1	82	8	434	25	0	467	73	495	38	0	606	1266
*** BREAK '	***																				
04:30 PM	25	14	5	0	44	8	11	18	0	37	4	150	14	0	168	24	107	15	1	147	396
04:45 PM	18	13	7	0	38	12	10	7	0	29	6	164	10	0	180	9	112	12	0	133	380
Total	43	27	12	0	82	20	21	25	0	66	10	314	24	0	348	33	219	27	1	280	776
05:00 PM	16	8	2	0	26	11	8	13	0	32	9	143	10	0	162	10	96	14	0	120	340
05:15 PM	21	9	5	0	35	8	10	14	0	32	8	131	16	0	155	16	116	21	0	153	375
05:30 PM	12	12	5	0	29	14	5	6	0	25	4	112	10	0	126	6	83	16	0	105	285
05:45 PM	17	13	0	0	30	7	9	13	0	29	1	98	8	0	107	4	63		0	78	244
Total	66	42	12	0	120	40	32	46	0	118	22	484	44	0	550	36	358	62	0	456	1244
06:00 PM	10	5	0	0	15	11	6	10	0	27	2	83	7	0	92	7	70	12	0	89	223
06:15 PM	24	10	3	0	37	4	7	18	0	29	4	89	9	0	102	7	54	13	0	74	242
Grand Total	255	163	47	0	465	127	112	165	1	405	51	1716	152	0	1919	210	1674	184	2	2070	4859
Apprch %	54.8	35.1	10.1	0		31.4	27.7	40.7	0.2		2.7	89.4	7.9	0		10.1	80.9	8.9	0.1		
Total %	5.2	3.4	1	0	9.6	2.6	2.3	3.4	0	8.3	1	35.3	3.1	0	39.5	4.3	34.5	3.8	0	42.6	
Cars	251	159	45	0	455	124	110	161	1	396	47	1681	146	0	1874	205	1637	182	2	2026	4751
% Cars	98.4	97.5	95.7	0	97.8	97.6	98.2	97.6	100	97.8	92.2	98	96.1	0	97.7	97.6	97.8	98.9	100	97.9	97.8
Trucks (SU)	4	4	1	0	9	3	2	4	0	9	3	33	6	0	42	5	37	2	0	44	104
% Trucks (SU)	1.6	2.5	2.1	0	1.9	2.4	1.8	2.4	0	2.2	5.9	1.9	3.9	0	2.2	2.4	2.2	1.1	0	2.1	2.1
Trucks (TT)	0	0	1	0	1	0	0	0	0	0	1	2	0	0	3	0	0	0	0	0	4
% Trucks (TT)	0	0	2.1	0	0.2	0	0	0	0	0	2	0.1	0	0	0.2	0	0	0	0	0	0.1

## VARIABLE CYCLES

<u>Movement</u>	<u>Signal</u>	Faces	<u>Tin</u>	<u>ne</u>
	<u>1-5</u>	<u>6-10</u>	Ī	Ш
A. Route US 206 Change Clearance	G Y R	R R R	45 Min. 5 2	30 Min. 5 2
<ul> <li>B. County Route 611 - Relocated Stickles Pond Road Change Clearance</li> </ul>	R R R	G Y R	7-17 4 2	7-15 4 2
Emergency Flash	Y	R	-	-

The vehicular memory is to be disconnected and the vehicle extension set at 2.0 seconds for Movement B.

Actuation of pedestrian push button is to provide a minimum green time of 15 seconds to Movement B.

The manual control is to be disconnected.

A detector call delay of 8 seconds is to be employed prior to placing a call for Movement B.

Hours of Operation: Time I: 7 – 9 A.M., 3:30 – 6:30 P.M., Monday – Friday

Time II: All Other Times

Appendix C Capacity Analysis

Existing - AM 10: Route 206 & Greendale Road/Stickles Pond Road

	۶	-	$\mathbf{r}$	4	+	•	•	t	1	1	ŧ	~
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations		<del>ب</del> ا ا	1		\$			\$			\$	
Traffic Volume (vph)	92	63	12	54	48	87	15	439	43	73	539	60
Future Volume (vph)	92	63	12	54	48	87	15	439	43	73	539	60
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Lane Width (ft)	12	12	14	12	12	12	12	12	12	12	12	12
Grade (%)		-4%			-2%			4%			4%	
Storage Length (ft)	0		30	0		0	0		0	0		0
Storage Lanes	0		1	0		0	0		0	0		0
Taper Length (ft)	25			25			25			25		
Lane Util. Factor	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Frt			0.850		0.938			0.988			0.988	
Flt Protected		0.971			0.986			0.999			0.995	
Satd. Flow (prot)	0	1813	1757	0	1699	0	0	1754	0	0	1780	0
Flt Permitted		0.668			0.849			0.976			0.898	
Satd. Flow (perm)	0	1247	1757	0	1463	0	0	1713	0	0	1606	0
Right Turn on Red			Yes			Yes			No			Yes
Satd. Flow (RTOR)			58		53						12	
Link Speed (mph)		40			35			50			50	
Link Distance (ft)		457			494			688			731	
Travel Time (s)		7.8			9.6			9.4			10.0	
Peak Hour Factor	0.98	0.98	0.98	0.98	0.98	0.98	0.98	0.98	0.98	0.98	0.98	0.98
Heavy Vehicles (%)	3%	5%	0%	4%	4%	5%	22%	4%	7%	4%	3%	0%
Shared Lane Traffic (%)												
Lane Group Flow (vph)	0	158	12	0	193	0	0	507	0	0	685	0
Turn Type	Perm	NA	Perm	Perm	NA		Perm	NA		Perm	NA	
Protected Phases		4			8			2			6	
Permitted Phases	4		4	8			2			6		
Detector Phase	4	4	4	8	8		2	2		6	6	
Switch Phase												
Minimum Initial (s)	7.0	7.0	7.0	7.0	7.0		45.0	45.0		45.0	45.0	
Minimum Split (s)	13.0	13.0	13.0	13.0	13.0		52.0	52.0		52.0	52.0	
Total Split (s)	23.0	23.0	23.0	23.0	23.0		52.0	52.0		52.0	52.0	
Total Split (%)	30.7%	30.7%	30.7%	30.7%	30.7%		69.3%	69.3%		69.3%	69.3%	
Yellow Time (s)	4.0	4.0	4.0	4.0	4.0		5.0	5.0		5.0	5.0	
All-Red Time (s)	2.0	2.0	2.0	2.0	2.0		2.0	2.0		2.0	2.0	
Lost Time Adjust (s)		0.0	0.0		0.0			0.0			0.0	
Total Lost Time (s)		6.0	6.0		6.0			7.0			7.0	
Lead/Lag												
Lead-Lag Optimize?												
Recall Mode	None	None	None	None	None		Max	Max		Max	Max	
Act Effct Green (s)		12.5	12.5		12.5			46.6			46.6	
Actuated g/C Ratio		0.17	0.17		0.17			0.65			0.65	
v/c Ratio		0.73	0.03		0.65			0.46			0.66	
Control Delay		47.3	0.2		29.9			8.8			12.5	
Queue Delay		0.0	0.0		0.0			0.0			0.0	
Total Delay		47.3	0.2		29.9			8.8			12.5	
LOS		D	Α		С			А			В	
Approach Delay		44.0			29.9			8.8			12.5	
Approach LOS		D			С			А			В	

NED 02/04/2021

Existing - AM 10: Route 206 & Greendale Road/Stickles Pond Road

	۶	-	$\mathbf{F}$	∢	←	•	1	Ť	1	5	Ļ	~
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Queue Length 50th (ft)		65	0		56			99			162	
Queue Length 95th (ft)		125	0		118			192			324	
Internal Link Dist (ft)		377			414			608			651	
Turn Bay Length (ft)			30									
Base Capacity (vph)		293	458		385			1106			1041	
Starvation Cap Reductn		0	0		0			0			0	
Spillback Cap Reductn		0	0		0			0			0	
Storage Cap Reductn		0	0		0			0			0	
Reduced v/c Ratio		0.54	0.03		0.50			0.46			0.66	
Intersection Summary												
Area Type: Ot	her											
Cycle Length: 75												
Actuated Cycle Length: 72.2												
Natural Cycle: 65												
Control Type: Actuated-Uncoo	rdinated											
Maximum v/c Ratio: 0.73												
Intersection Signal Delay: 16.9				In	tersection	LOS: B						
Intersection Capacity Utilization	n 94.5%			IC	CU Level c	of Service	F					
Analysis Period (min) 15												
Splits and Phases: 10: Rout	- <u>-</u>	roondol	Deed/Ci	iaklaa Da	nd Dood							

#### Splits and Phases: 10: Route 206 & Greendale Road/Stickles Pond Road



Existing - PM 10: Route 206 & Greendale Road/Stickles Pond Road

	٨	-	7	4	ł	•	•	1	1	*	ţ	~
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations		र्स	1		\$			\$			\$	
Traffic Volume (vph)	95	53	22	54	54	71	38	598	64	74	440	89
Future Volume (vph)	95	53	22	54	54	71	38	598	64	74	440	89
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Lane Width (ft)	12	12	14	12	12	12	12	12	12	12	12	12
Grade (%)		-4%			-2%			4%			4%	
Storage Length (ft)	0		30	0		0	0		0	0		0
Storage Lanes	0		1	0		0	0		0	0		0
Taper Length (ft)	25			25			25			25		
Lane Util. Factor	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Frt			0.850		0.946			0.988			0.980	
Flt Protected		0.969			0.985			0.997			0.994	
Satd. Flow (prot)	0	1866	1757	0	1774	0	0	1815	0	0	1783	0
Flt Permitted		0.657			0.842			0.945			0.841	-
Satd. Flow (perm)	0	1265	1757	0	1516	0	0	1721	0	0	1509	0
Right Turn on Red			Yes			Yes			No			Yes
Satd. Flow (RTOR)			58		41						21	
Link Speed (mph)		40			35			50			50	
Link Distance (ft)		457			494			688			731	
Travel Time (s)		7.8			9.6			9.4			10.0	
Peak Hour Factor	0.94	0.94	0.94	0.94	0.94	0.94	0.94	0.94	0.94	0.94	0.94	0.94
Heavy Vehicles (%)	1%	0%	0%	0%	0%	2%	0%	1%	2%	2%	2%	0%
Shared Lane Traffic (%)				- , -					_,,	_/*		- / -
Lane Group Flow (vph)	0	157	23	0	190	0	0	744	0	0	642	0
Turn Type	Perm	NA	Perm	Perm	NA		Perm	NA		Perm	NA	
Protected Phases		4			8			2			6	
Permitted Phases	4		4	8			2			6		
Detector Phase	4	4	4	8	8		2	2		6	6	
Switch Phase												
Minimum Initial (s)	7.0	7.0	7.0	7.0	7.0		45.0	45.0		45.0	45.0	
Minimum Split (s)	13.0	13.0	13.0	13.0	13.0		52.0	52.0		52.0	52.0	
Total Split (s)	23.0	23.0	23.0	23.0	23.0		52.0	52.0		52.0	52.0	
Total Split (%)	30.7%	30.7%	30.7%	30.7%	30.7%		69.3%	69.3%		69.3%	69.3%	
Yellow Time (s)	4.0	4.0	4.0	4.0	4.0		5.0	5.0		5.0	5.0	
All-Red Time (s)	2.0	2.0	2.0	2.0	2.0		2.0	2.0		2.0	2.0	
Lost Time Adjust (s)		0.0	0.0		0.0			0.0			0.0	
Total Lost Time (s)		6.0	6.0		6.0			7.0			7.0	
Lead/Lag												
Lead-Lag Optimize?												
Recall Mode	None	None	None	None	None		Max	Max		Max	Max	
Act Effct Green (s)		12.4	12.4		12.4			46.7			46.7	
Actuated g/C Ratio		0.17	0.17		0.17			0.65			0.65	
v/c Ratio		0.72	0.07		0.64			0.67			0.65	
Control Delay		46.5	1.7		31.5			12.6			12.4	
Queue Delay		0.0	0.0		0.0			0.0			0.0	
Total Delay		46.5	1.7		31.5			12.6			12.4	
LOS		D	А		С			В			В	
Approach Delay		40.7			31.5			12.6			12.4	
Approach LOS		D			С			В			В	

NED 02/04/2021

Existing - PM 10: Route 206 & Greendale Road/Stickles Pond Road

	۶	-	$\mathbf{F}$	∢	-	*	1	1	1	5	Ļ	~
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Queue Length 50th (ft)		65	0		60			180			147	
Queue Length 95th (ft)		124	4		121			354			305	
Internal Link Dist (ft)		377			414			608			651	
Turn Bay Length (ft)			30									
Base Capacity (vph)		298	458		388			1114			984	
Starvation Cap Reductn		0	0		0			0			0	
Spillback Cap Reductn		0	0		0			0			0	
Storage Cap Reductn		0	0		0			0			0	
Reduced v/c Ratio		0.53	0.05		0.49			0.67			0.65	
Intersection Summary												
Area Type: Oth	ner											
Cycle Length: 75												
Actuated Cycle Length: 72.2												
Natural Cycle: 65												
Control Type: Actuated-Uncoor	dinated											
Maximum v/c Ratio: 0.72												
Intersection Signal Delay: 17.5				In	tersection	LOS: B						
Intersection Capacity Utilization	า 82.3%			IC	U Level c	of Service	E					
Analysis Period (min) 15												
Splits and Phases: 10: Route	- 206 9 (	roondole	Dood/Ci	iaklaa Da	nd Dood							

#### Splits and Phases: 10: Route 206 & Greendale Road/Stickles Pond Road



No Build - AM 10: Route 206 & Greendale Road/Stickles Pond Road

	≯	+	*	4	ł	•	<	1	1	×	Ŧ	~
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations		र्स	1		4			<b>4</b>			4	
Traffic Volume (vph)	95	65	12	56	50	90	16	454	45	76	558	62
Future Volume (vph)	95	65	12	56	50	90	16	454	45	76	558	62
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Lane Width (ft)	12	12	14	12	12	12	12	12	12	12	12	12
Grade (%)		-4%			-2%			4%			4%	
Storage Length (ft)	0		30	0		0	0		0	0		0
Storage Lanes	0		1	0		0	0		0	0		0
Taper Length (ft)	25			25			25			25		
Lane Util. Factor	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Frt			0.850		0.938			0.988			0.988	
Flt Protected		0.971			0.986			0.998			0.995	
Satd. Flow (prot)	0	1813	1757	0	1699	0	0	1752	0	0	1780	0
Flt Permitted	Ţ	0.659		•	0.847	•	•	0.974	•	•	0.892	, in the second s
Satd. Flow (perm)	0	1230	1757	0	1460	0	0	1710	0	0	1596	0
Right Turn on Red	Ű	1200	Yes	Ű	1100	Yes	Ű		No	Ŭ	1000	Yes
Satd. Flow (RTOR)			58		53	100					12	100
Link Speed (mph)		40	00		35			50			50	
Link Distance (ft)		457			494			688			731	
Travel Time (s)		7.8			9.6			9.4			10.0	
Peak Hour Factor	0.98	0.98	0.98	0.98	0.98	0.98	0.98	0.98	0.98	0.98	0.98	0.98
Heavy Vehicles (%)	3%	5%	0%	4%	4%	5%	22%	4%	7%	4%	3%	0.50
Shared Lane Traffic (%)	0 /0	070	070	- 70	- <del>7</del> 70	070	22/0	770	170	- 70	0 /0	070
Lane Group Flow (vph)	0	163	12	0	200	0	0	525	0	0	710	0
Turn Type	Perm	NA	Perm	Perm	NA		Perm	NA		Perm	NA	
Protected Phases		4			8			2			6	
Permitted Phases	4		4	8			2			6		
Detector Phase	4	4	4	8	8		2	2		6	6	
Switch Phase												
Minimum Initial (s)	7.0	7.0	7.0	7.0	7.0		45.0	45.0		45.0	45.0	
Minimum Split (s)	13.0	13.0	13.0	13.0	13.0		52.0	52.0		52.0	52.0	
Total Split (s)	23.0	23.0	23.0	23.0	23.0		52.0	52.0		52.0	52.0	
Total Split (%)	30.7%	30.7%	30.7%	30.7%	30.7%		69.3%	69.3%		69.3%	69.3%	
Yellow Time (s)	4.0	4.0	4.0	4.0	4.0		5.0	5.0		5.0	5.0	
All-Red Time (s)	2.0	2.0	2.0	2.0	2.0		2.0	2.0		2.0	2.0	
Lost Time Adjust (s)		0.0	0.0		0.0			0.0			0.0	
Total Lost Time (s)		6.0	6.0		6.0			7.0			7.0	
Lead/Lag												
Lead-Lag Optimize?												
Recall Mode	None	None	None	None	None		Max	Max		Max	Max	
Act Effct Green (s)		12.9	12.9		12.9			46.4			46.4	
Actuated g/C Ratio		0.18	0.18		0.18			0.64			0.64	
v/c Ratio		0.75	0.03		0.66			0.48			0.69	
Control Delay		48.5	0.2		30.6			9.2			13.6	
Queue Delay		0.0	0.0		0.0			0.0			0.0	
Total Delay		48.5	0.2		30.6			9.2			13.6	
LOS		40.0 D	A		C			A			B	
Approach Delay		45.2			30.6			9.2			13.6	
Approach LOS		4J.2 D			00.0 C			A			10.0 B	
		U			U			Л			U	

NED 02/04/2021

No Build - AM 10: Route 206 & Greendale Road/Stickles Pond Road

	≯	-	$\mathbf{F}$	∢	+	*	1	1	1	1	ţ	~
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Queue Length 50th (ft)		68	0		59			107			178	
Queue Length 95th (ft)		130	0		123			201			350	
Internal Link Dist (ft)		377			414			608			651	
Turn Bay Length (ft)			30									
Base Capacity (vph)		289	458		384			1098			1029	
Starvation Cap Reductn		0	0		0			0			0	
Spillback Cap Reductn		0	0		0			0			0	
Storage Cap Reductn		0	0		0			0			0	
Reduced v/c Ratio		0.56	0.03		0.52			0.48			0.69	
Intersection Summary												
Area Type: O	other											
Cycle Length: 75												
Actuated Cycle Length: 72.3												
Natural Cycle: 65												
Control Type: Actuated-Uncod	ordinated											
Maximum v/c Ratio: 0.75												
Intersection Signal Delay: 17.	7			In	tersection	LOS: B						
Intersection Capacity Utilization	on 97.0%			IC	U Level c	of Service	F					
Analysis Period (min) 15												
Solits and Phases: 10: Rou	ite 206 & (	Freendal	Road/St	ickles Po	nd Road							

#### Splits and Phases: 10: Route 206 & Greendale Road/Stickles Pond Road



No Build - PM 10: Route 206 & Greendale Road/Stickles Pond Road

	٦	-	7	4	+	•	•	1	1	*	Ŧ	~
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations		र्स	1		\$			\$			\$	
Traffic Volume (vph)	98	55	23	56	56	74	39	619	66	77	456	92
Future Volume (vph)	98	55	23	56	56	74	39	619	66	77	456	92
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Lane Width (ft)	12	12	14	12	12	12	12	12	12	12	12	12
Grade (%)		-4%			-2%			4%			4%	
Storage Length (ft)	0		30	0		0	0		0	0		0
Storage Lanes	0		1	0		0	0		0	0		0
Taper Length (ft)	25			25			25			25		
Lane Util. Factor	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Frt			0.850		0.946			0.988			0.980	
Flt Protected		0.969			0.985			0.997			0.994	
Satd. Flow (prot)	0	1866	1757	0	1774	0	0	1815	0	0	1783	0
Flt Permitted		0.648			0.839			0.943			0.834	
Satd. Flow (perm)	0	1248	1757	0	1511	0	0	1717	0	0	1496	0
Right Turn on Red			Yes			Yes			No			Yes
Satd. Flow (RTOR)			58		41						21	
Link Speed (mph)		40			35			50			50	
Link Distance (ft)		457			494			688			731	
Travel Time (s)		7.8			9.6			9.4			10.0	
Peak Hour Factor	0.94	0.94	0.94	0.94	0.94	0.94	0.94	0.94	0.94	0.94	0.94	0.94
Heavy Vehicles (%)	1%	0%	0%	0%	0%	2%	0%	1%	2%	2%	2%	0%
Shared Lane Traffic (%)												
Lane Group Flow (vph)	0	163	24	0	199	0	0	770	0	0	665	0
Turn Type	Perm	NA	Perm	Perm	NA		Perm	NA		Perm	NA	
Protected Phases		4			8			2			6	
Permitted Phases	4		4	8			2			6		
Detector Phase	4	4	4	8	8		2	2		6	6	
Switch Phase												
Minimum Initial (s)	7.0	7.0	7.0	7.0	7.0		45.0	45.0		45.0	45.0	
Minimum Split (s)	13.0	13.0	13.0	13.0	13.0		52.0	52.0		52.0	52.0	
Total Split (s)	23.0	23.0	23.0	23.0	23.0		52.0	52.0		52.0	52.0	
Total Split (%)	30.7%	30.7%	30.7%	30.7%	30.7%		69.3%	69.3%		69.3%	69.3%	
Yellow Time (s)	4.0	4.0	4.0	4.0	4.0		5.0	5.0		5.0	5.0	
All-Red Time (s)	2.0	2.0	2.0	2.0	2.0		2.0	2.0		2.0	2.0	
Lost Time Adjust (s)		0.0	0.0		0.0			0.0			0.0	
Total Lost Time (s)		6.0	6.0		6.0			7.0			7.0	
Lead/Lag												
Lead-Lag Optimize?												
Recall Mode	None	None	None	None	None		Max	Max		Max	Max	
Act Effct Green (s)		12.8	12.8		12.8			46.4			46.4	
Actuated g/C Ratio		0.18	0.18		0.18			0.64			0.64	
v/c Ratio		0.74	0.07		0.66			0.70			0.69	
Control Delay		47.9	2.0		32.4			13.6			13.6	
Queue Delay		0.0	0.0		0.0			0.0			0.0	
Total Delay		47.9	2.0		32.4			13.6			13.6	
LOS		D	А		С			В			В	
Approach Delay		42.0			32.4			13.6			13.6	
Approach LOS		D			С			В			В	

NED 02/04/2021

No Build - PM 10: Route 206 & Greendale Road/Stickles Pond Road

	۶	-	$\mathbf{F}$	∢	-	*	1	1	1	5	Ļ	~
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Queue Length 50th (ft)		68	0		64			197			162	
Queue Length 95th (ft)		129	5		128			379			330	
Internal Link Dist (ft)		377			414			608			651	
Turn Bay Length (ft)			30									
Base Capacity (vph)		293	458		387			1104			969	
Starvation Cap Reductn		0	0		0			0			0	
Spillback Cap Reductn		0	0		0			0			0	
Storage Cap Reductn		0	0		0			0			0	
Reduced v/c Ratio		0.56	0.05		0.51			0.70			0.69	
Intersection Summary												
Area Type: Ot	her											
Cycle Length: 75												
Actuated Cycle Length: 72.2												
Natural Cycle: 65												
Control Type: Actuated-Uncoo	rdinated											
Maximum v/c Ratio: 0.74												
Intersection Signal Delay: 18.6	;			In	tersection	LOS: B						
Intersection Capacity Utilization	n 84.9%			IC	U Level c	of Service	E					
Analysis Period (min) 15												
Calita and Dhasaay 10, Dout	- 000 0 0			Salata Da								

## Splits and Phases: 10: Route 206 & Greendale Road/Stickles Pond Road



Build - AM 10: Route 206 & Greendale Road/Stickles Pond Road

	٦	<b>→</b>	*	4	Ļ	•	•	1	1	*	ţ	~
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations		र्स	1		\$			\$			\$	
Traffic Volume (vph)	95	67	12	60	50	94	16	454	57	89	558	62
Future Volume (vph)	95	67	12	60	50	94	16	454	57	89	558	62
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Lane Width (ft)	12	12	14	12	12	12	12	12	12	12	12	12
Grade (%)		-4%			-2%			4%			4%	
Storage Length (ft)	0		30	0		0	0		0	0		0
Storage Lanes	0		1	0		0	0		0	0		0
Taper Length (ft)	25			25			25			25		
Lane Util. Factor	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Frt			0.850		0.938			0.985			0.988	
Flt Protected		0.971			0.986			0.999			0.994	
Satd. Flow (prot)	0	1820	1757	0	1635	0	0	1738	0	0	1767	0
Flt Permitted		0.653			0.842			0.974			0.871	-
Satd. Flow (perm)	0	1224	1757	0	1397	0	0	1695	0	0	1548	0
Right Turn on Red			Yes			Yes			No			Yes
Satd. Flow (RTOR)			58		53						11	
Link Speed (mph)		40			35			50			50	
Link Distance (ft)		457			494			688			731	
Travel Time (s)		7.8			9.6			9.4			10.0	
Peak Hour Factor	0.98	0.98	0.98	0.98	0.98	0.98	0.98	0.98	0.98	0.98	0.98	0.98
Heavy Vehicles (%)	3%	4%	0%	10%	4%	10%	22%	4%	12%	9%	3%	0%
Shared Lane Traffic (%)	•,•	. / 0	• / •		.,.		/	. / 0	/.	• / •	• / •	•,•
Lane Group Flow (vph)	0	165	12	0	208	0	0	537	0	0	723	0
Turn Type	Perm	NA	Perm	Perm	NA		Perm	NA		Perm	NA	-
Protected Phases		4			8			2			6	
Permitted Phases	4		4	8			2			6		
Detector Phase	4	4	4	8	8		2	2		6	6	
Switch Phase												
Minimum Initial (s)	7.0	7.0	7.0	7.0	7.0		45.0	45.0		45.0	45.0	
Minimum Split (s)	13.0	13.0	13.0	13.0	13.0		52.0	52.0		52.0	52.0	
Total Split (s)	23.0	23.0	23.0	23.0	23.0		52.0	52.0		52.0	52.0	
Total Split (%)	30.7%	30.7%	30.7%	30.7%	30.7%		69.3%	69.3%		69.3%	69.3%	
Yellow Time (s)	4.0	4.0	4.0	4.0	4.0		5.0	5.0		5.0	5.0	
All-Red Time (s)	2.0	2.0	2.0	2.0	2.0		2.0	2.0		2.0	2.0	
Lost Time Adjust (s)		0.0	0.0		0.0			0.0			0.0	
Total Lost Time (s)		6.0	6.0		6.0			7.0			7.0	
Lead/Lag												
Lead-Lag Optimize?												
Recall Mode	None	None	None	None	None		Max	Max		Max	Max	
Act Effct Green (s)		13.0	13.0		13.0			46.2			46.2	
Actuated g/C Ratio		0.18	0.18		0.18			0.64			0.64	
v/c Ratio		0.75	0.03		0.71			0.49			0.73	
Control Delay		49.0	0.2		33.8			9.6			15.3	
Queue Delay		0.0	0.0		0.0			0.0			0.0	
Total Delay		49.0	0.2		33.8			9.6			15.3	
LOS		D	А		С			А			В	
Approach Delay		45.7			33.8			9.6			15.3	
Approach LOS		D			С			А			В	

NED 02/04/2021

Build - AM 10: Route 206 & Greendale Road/Stickles Pond Road

	٦	<b>→</b>	$\mathbf{F}$	4	+	*	•	1	1	1	ŧ	~
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Queue Length 50th (ft)		69	0		63			113			191	
Queue Length 95th (ft)		#133	0		131			210			379	
Internal Link Dist (ft)		377			414			608			651	
Turn Bay Length (ft)			30									
Base Capacity (vph)		288	458		369			1085			994	
Starvation Cap Reductn		0	0		0			0			0	
Spillback Cap Reductn		0	0		0			0			0	
Storage Cap Reductn		0	0		0			0			0	
Reduced v/c Ratio		0.57	0.03		0.56			0.49			0.73	
Intersection Summary												
Area Type:	Other											
Cycle Length: 75												
Actuated Cycle Length: 72	.2											
Natural Cycle: 65												
Control Type: Actuated-Un	coordinated											
Maximum v/c Ratio: 0.75												
Intersection Signal Delay:				In	itersectior	LOS: B						
Intersection Capacity Utiliz	ation 104.4%	0		IC	CU Level o	of Service	G					
Analysis Period (min) 15												
# 95th percentile volume			eue may l	be longer	•							
Queue shown is maxim	um after two	cycles.										
Splits and Phases: 10: F	Route 206 &	Greendal	Doad/Q	lickles De	nd Pood							
		Gieenuale										

<b>↑</b> <sub>Ø2</sub>	<i>↓</i> Ø4	
52 s	23 s	
<b>↓</b> Ø6	<b>₩</b> Ø8	
52 s	23 s	

Build - PM 10: Route 206 & Greendale Road/Stickles Pond Road

	≯	-	$\mathbf{r}$	4	+	•	•	t	1	1	ţ	~
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations		<del>ب</del> ا ا	1		\$			\$			\$	
Traffic Volume (vph)	98	55	23	69	58	88	39	619	70	81	456	92
Future Volume (vph)	98	55	23	69	58	88	39	619	70	81	456	92
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Lane Width (ft)	12	12	14	12	12	12	12	12	12	12	12	12
Grade (%)		-4%			-2%			4%			4%	
Storage Length (ft)	0		30	0		0	0		0	0		0
Storage Lanes	0		1	0		0	0		0	0		0
Taper Length (ft)	25			25			25			25		
Lane Util. Factor	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Frt			0.850		0.945			0.987			0.980	
Flt Protected		0.969			0.984			0.997			0.994	
Satd. Flow (prot)	0	1866	1757	0	1704	0	0	1805	0	0	1772	0
Flt Permitted		0.612			0.832			0.943			0.825	
Satd. Flow (perm)	0	1179	1757	0	1441	0	0	1707	0	0	1471	0
Right Turn on Red			Yes			Yes			No			Yes
Satd. Flow (RTOR)			58		43						21	
Link Speed (mph)		40			35			50			50	
Link Distance (ft)		457			494			688			731	
Travel Time (s)		7.8			9.6			9.4			10.0	
Peak Hour Factor	0.94	0.94	0.94	0.94	0.94	0.94	0.94	0.94	0.94	0.94	0.94	0.94
Heavy Vehicles (%)	1%	0%	0%	7%	0%	6%	0%	1%	7%	7%	2%	0%
Shared Lane Traffic (%)												
Lane Group Flow (vph)	0	163	24	0	229	0	0	774	0	0	669	0
Turn Type	Perm	NA	Perm	Perm	NA		Perm	NA		Perm	NA	
Protected Phases		4			8			2			6	
Permitted Phases	4		4	8			2			6		
Detector Phase	4	4	4	8	8		2	2		6	6	
Switch Phase												
Minimum Initial (s)	7.0	7.0	7.0	7.0	7.0		45.0	45.0		45.0	45.0	
Minimum Split (s)	13.0	13.0	13.0	13.0	13.0		52.0	52.0		52.0	52.0	
Total Split (s)	23.0	23.0	23.0	23.0	23.0		52.0	52.0		52.0	52.0	
Total Split (%)	30.7%	30.7%	30.7%	30.7%	30.7%		69.3%	69.3%		69.3%	69.3%	
Yellow Time (s)	4.0	4.0	4.0	4.0	4.0		5.0	5.0		5.0	5.0	
All-Red Time (s)	2.0	2.0	2.0	2.0	2.0		2.0	2.0		2.0	2.0	
Lost Time Adjust (s)		0.0	0.0		0.0			0.0			0.0	
Total Lost Time (s)		6.0	6.0		6.0			7.0			7.0	
Lead/Lag												
Lead-Lag Optimize?												
Recall Mode	None	None	None	None	None		Max	Max		Max	Max	
Act Effct Green (s)		13.1	13.1		13.1			45.9			45.9	
Actuated g/C Ratio		0.18	0.18		0.18			0.64			0.64	
v/c Ratio		0.76	0.07		0.77			0.71			0.71	
Control Delay		50.5	2.0		40.2			14.3			14.6	
Queue Delay		0.0	0.0		0.0			0.0			0.0	
Total Delay		50.5	2.0		40.2			14.3			14.6	
LOS		D	А		D			В			В	
Approach Delay		44.3			40.2			14.3			14.6	

NED 02/04/2021

#### 3527-99-001TE

Build - PM 10: Route 206 & Greendale Road/Stickles Pond Road

	٦	<b>→</b>	$\mathbf{F}$	4	+	*	•	1	1	1	Ļ	~
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Queue Length 50th (ft)		68	0		78			206			171	
Queue Length 95th (ft)		#142	5		#152			386			343	
Internal Link Dist (ft)		377			414			608			651	
Turn Bay Length (ft)			30									
Base Capacity (vph)		278	459		373			1087			945	
Starvation Cap Reductn		0	0		0			0			0	
Spillback Cap Reductn		0	0		0			0			0	
Storage Cap Reductn		0	0		0			0			0	
Reduced v/c Ratio		0.59	0.05		0.61			0.71			0.71	
Intersection Summary												
Area Type:	Other											
Cycle Length: 75												
Actuated Cycle Length: 72												
Natural Cycle: 65												
Control Type: Actuated-Un	coordinated											
Maximum v/c Ratio: 0.77												
Intersection Signal Delay: 2				In	tersectior	LOS: C						
Intersection Capacity Utilization	ation 88.2%			IC	U Level o	of Service	E					
Analysis Period (min) 15												
# 95th percentile volume	exceeds cap	pacity, que	eue may l	be longer	•							
Queue shown is maxim	um after two	cycles.										
Splits and Phases: 10: R	oute 206 & 0	Greendel	Doad/Q4	ickles Po	nd Dood							

<b>▲</b> ¶ <sub>Ø2</sub>	<b>₩</b> Ø4	
52 s	23 s	
	<b>₩</b> Ø8	
52 s	23 s	

#### 3527-99-001TE

Build with Mit. - PM 10: Route 206 & Greendale Road/Stickles Pond Road

	٠	-	$\mathbf{r}$	4	Ŧ	•	•	1	1	*	ţ	~
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations		र्स	1		\$			\$			\$	
Traffic Volume (vph)	98	55	23	69	58	88	39	619	70	81	456	92
Future Volume (vph)	98	55	23	69	58	88	39	619	70	81	456	92
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Lane Width (ft)	12	12	14	12	12	12	12	12	12	12	12	12
Grade (%)		-4%			-2%			4%			4%	
Storage Length (ft)	0		30	0		0	0		0	0		0
Storage Lanes	0		1	0		0	0		0	0		0
Taper Length (ft)	25			25			25			25		
Lane Util. Factor	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Frt			0.850		0.945			0.987			0.980	
Flt Protected		0.969			0.984			0.997			0.994	
Satd. Flow (prot)	0	1866	1757	0	1704	0	0	1805	0	0	1772	0
Flt Permitted		0.626			0.832			0.943			0.829	
Satd. Flow (perm)	0	1205	1757	0	1441	0	0	1707	0	0	1478	0
Right Turn on Red			Yes			Yes			No			Yes
Satd. Flow (RTOR)			58		46						19	
Link Speed (mph)		40			35			50			50	
Link Distance (ft)		457			494			688			731	
Travel Time (s)		7.8			9.6			9.4			10.0	
Peak Hour Factor	0.94	0.94	0.94	0.94	0.94	0.94	0.94	0.94	0.94	0.94	0.94	0.94
Heavy Vehicles (%)	1%	0%	0%	7%	0%	6%	0%	1%	7%	7%	2%	0%
Shared Lane Traffic (%)												
Lane Group Flow (vph)	0	163	24	0	229	0	0	774	0	0	669	0
Turn Type	Perm	NA	Perm	Perm	NA		Perm	NA		Perm	NA	
Protected Phases		4			8			2			6	
Permitted Phases	4		4	8			2			6		
Detector Phase	4	4	4	8	8		2	2		6	6	
Switch Phase												
Minimum Initial (s)	7.0	7.0	7.0	7.0	7.0		42.0	42.0		42.0	42.0	
Minimum Split (s)	13.0	13.0	13.0	13.0	13.0		49.0	49.0		49.0	49.0	
Total Split (s)	26.0	26.0	26.0	26.0	26.0		49.0	49.0		49.0	49.0	
Total Split (%)	34.7%	34.7%	34.7%	34.7%	34.7%		65.3%	65.3%		65.3%	65.3%	
Yellow Time (s)	4.0	4.0	4.0	4.0	4.0		5.0	5.0		5.0	5.0	
All-Red Time (s)	2.0	2.0	2.0	2.0	2.0		2.0	2.0		2.0	2.0	
Lost Time Adjust (s)		0.0	0.0		0.0			0.0			0.0	
Total Lost Time (s)		6.0	6.0		6.0			7.0			7.0	
Lead/Lag												
Lead-Lag Optimize?												
Recall Mode	None	None	None	None	None		Max	Max		Max	Max	
Act Effct Green (s)		13.2	13.2		13.2			43.0			43.0	
Actuated g/C Ratio		0.19	0.19		0.19			0.62			0.62	
v/c Ratio		0.71	0.06		0.73			0.73			0.72	
Control Delay		42.9	1.8		34.8			16.0			16.2	
Queue Delay		0.0	0.0		0.0			0.0			0.0	
Total Delay		42.9	1.8		34.8			16.0			16.2	
LOS		D	А		С			В			В	
Approach Delay		37.6			34.8			16.0			16.2	
Approach LOS		D			С			В			В	

NED 02/04/2021 Synchro 11 Report Lanes, Volumes, Timings

#### 3527-99-001TE

Build with Mit. - PM 10: Route 206 & Greendale Road/Stickles Pond Road

	٦	-	$\mathbf{F}$	•	-	۰.	1	1	1	5	Ļ	~
Lane Group	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Queue Length 50th (ft)		64	0		72			199			165	
Queue Length 95th (ft)		123	5		141			#462			#441	
Internal Link Dist (ft)		377			414			608			651	
Turn Bay Length (ft)			30									
Base Capacity (vph)		349	550		450			1059			924	
Starvation Cap Reductn		0	0		0			0			0	
Spillback Cap Reductn		0	0		0			0			0	
Storage Cap Reductn		0	0		0			0			0	
Reduced v/c Ratio		0.47	0.04		0.51			0.73			0.72	
Intersection Summary												
Area Type:	Other											
Cycle Length: 75												
Actuated Cycle Length: 69	.2											
Natural Cycle: 65												
Control Type: Actuated-Un	coordinated											
Maximum v/c Ratio: 0.73												
Intersection Signal Delay: 2				In	tersectior	LOS: C						
Intersection Capacity Utiliz	ation 88.2%			IC	U Level o	of Service	E					
Analysis Period (min) 15												
# 95th percentile volume	exceeds cap	acity, que	eue may l	be longer	•							
Queue shown is maximum after two cycles.												
Splits and Phases: 10: Route 206 & Greendale Road/Stickles Pond Road												
Splits and Phases: 10: F		SIGGUIABLE	Ruau/SI									

≪¶ø2	<b>₽</b> 04	
49 s	26 s	
▼ Ø6	<b>₩</b> Ø8	
49 s	26 s	


Intersection						
Int Delay, s/veh	0.7					
Movement	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations		ŧ	et 👘			1
Traffic Vol, veh/h	27	186	196	2	0	8
Future Vol, veh/h	27	186	196	2	0	8
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Free	Free	Free	Free	Stop	Stop
RT Channelized	-	None	-	None	-	None
Storage Length	-	-	-	-	-	0
Veh in Median Storage,	# -	0	0	-	0	-
Grade, %	-	4	-4	-	0	-
Peak Hour Factor	88	88	88	88	88	88
Heavy Vehicles, %	33	4	2	0	2	100
Mvmt Flow	31	211	223	2	0	9


Major/Minor	Major1	Ν	/lajor2	ľ	Minor2	
Conflicting Flow All	225	0	-	0	-	224
Stage 1	-	-	-	-	-	-
Stage 2	-	-	-	-	-	-
Critical Hdwy	4.43	-	-	-	-	7.2
Critical Hdwy Stg 1	-	-	-	-	-	-
Critical Hdwy Stg 2	-	-	-	-	-	-
Follow-up Hdwy	2.497	-	-	-	-	4.2
Pot Cap-1 Maneuver	1181	-	-	-	0	622
Stage 1	-	-	-	-	0	-
Stage 2	-	-	-	-	0	-
Platoon blocked, %		-	-	-		
Mov Cap-1 Maneuver	1181	-	-	-	-	622
Mov Cap-2 Maneuver	-	-	-	-	-	-
Stage 1	-	-	-	-	-	-
Stage 2	-	-	-	-	-	-
Approach	EB		WB		SB	
HCM Control Delay, s	1		0		10.9	
HCM LOS					В	
Minor Lane/Major Mvm	nt	EBL	EBT	WBT	WBR S	SBLn1
Capacity (veh/h)		1181	-	-	-	622
HCM Lane V/C Ratio		0.026	-	-	-	0.015
HCM Control Delay (s)	)	8.1	0	-	-	10.9
HCM Lane LOS		А	А	-	-	В
HCM 95th %tile Q(veh	)	0.1	-	-	-	0
	,					

Intersection						
Int Delay, s/veh	0.8					
Movement	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations		र्भ	4Î			1
Traffic Vol, veh/h	8	198	186	0	0	29
Future Vol, veh/h	8	198	186	0	0	29
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Free	Free	Free	Free	Stop	Stop
RT Channelized	-	None	-	None	-	None
Storage Length	-	-	-	-	-	0
Veh in Median Storage,	, # -	0	0	-	0	-
Grade, %	-	4	-4	-	0	-
Peak Hour Factor	79	79	79	79	79	79
Heavy Vehicles, %	100	1	1	0	2	31
Mvmt Flow	10	251	235	0	0	37

Major/Minor	Major1	Ν	/lajor2	ľ	Minor2	
Conflicting Flow All	235	0	-	0	-	235
Stage 1	-	-	-	-	-	-
Stage 2	-	-	-	-	-	-
Critical Hdwy	5.1	-	-	-	-	6.51
Critical Hdwy Stg 1	-	-	-	-	-	-
Critical Hdwy Stg 2	-	-	-	-	-	-
Follow-up Hdwy	3.1	-	-	-	-	3.579
Pot Cap-1 Maneuver	920	-	-	-	0	737
Stage 1	-	-	-	-	0	-
Stage 2	-	-	-	-	0	-
Platoon blocked, %		-	-	-		
Mov Cap-1 Maneuver		-	-	-	-	737
Mov Cap-2 Maneuver	-	-	-	-	-	-
Stage 1	-	-	-	-	-	-
Stage 2	-	-	-	-	-	-
Approach	EB		WB		SB	
HCM Control Delay, s	0.3		0		10.1	
HCM LOS					В	
Minor Lane/Major Mvr	nt	EBL	EBT	WBT	WBR	SBLn1
Capacity (veh/h)		920	-	_	_	737
HCM Lane V/C Ratio		0.011	-	-	-	0.05
HCM Control Delay (s	)	9	0	-	-	10.1
HCM Lane LOS	/	A	Ă	-	-	В
HCM 95th %tile Q(veh	ı)	0	-	-	-	0.2
	/					

# Construction Business Office and Construction Equipment and Material Storage Andover Township, NJ PARCELS: Lot: 21 Tax Block: 151





roperty Information	т
te Plan	4
onstruction Materials	Ś
onstruction Equipment	9
te Operations	7




52 Stickles Pond Road, Newton NJ, 07860

Sussex County Parcel ID Lot: 21 Tax Block: 151 Acres 97 Acres Usable Acres: 48 Acres


## Proposed Use:

Outdoor storage facility of special order and ordinary construction materials and equipment like; bulldozer, earthmovers, asphalt millings, crushed stone, piping, etc., will be stored onsite. A construction business office and receiving area and staff parking will be included.




က

















Business Hours of Operation: Monday through Friday, 8am to 5pm. Trip Generation: We estimate roughly 150 trips a day


**Career and Employment Opportunities:** We estimate 10 - 20 full-time employees, salaried management position and standard hourly wages.



2

## **INSURANCE AUTO AUCTIONS** 430 TWO NOTCH RD. LEXINGTON, SC 29073

## **NEW CONSTRUCTION**



## **PROJECT DATA**

## **BUILDING CODE SUMMARY**

LEXINGTON, SOUTH CAROLINA

TYPE OF CONSTRUCTION: TYPE II-B / NON SPRINKLED (NS)

OCCUPANCY:

#### APPLICABLE CODES

**BUILDING CODE:** FUEL AND GAS CODE: MECHANICAL CODE PLUMBING CODE: ACCESSIBILITY CODE: **ENERGY CODE:** ELECTRICAL CODE: FIRE CODE: LIFE SAFETY CODE:

APPLICABLE:

ZONING:

TBD

## FIRE-RESISTANCE RATINGS NOTE(S)

**GROUP B (BUSINESS)** 

2017 ICC A117.1

2018 INTERNATIONAL BUILDING CODE (IBC) 2018 INTERNATIONAL FIRE AND GAS CODE

2018 INTERNATIONAL MECHANICAL CODE (IMC)

2009 INTERNATIONAL ENERGY CONSERVATION CODE

CITY OF LEXINGTON ADOPTED CODE(S) & ORDINANCES(S)

2018 INTERNATIONAL PLUMBING CODE (IPC)

2017 NATIONAL ELECTRIC CODE (NFPA-70)

AND ALL LOCAL AMENDMENTS AND CITATION

2018 INTERNATIONAL FIRE CODE(IFC)

2018 NFPA 101 LIFE SAFETY CODE

#### BUILDING ELEMENT PRIMARY STRUCTURAL FRAME HOURS 0 **BEARING WALLS** EXTERIOR INTERIOR NONBEARING WALLS EXTERIOR INTERIOR CORRIDOR FLOOR CONSTRUCTION ROOF CONSTRUCTION

AMERICANS WITH DISABILITIES ACT ACCESSIBILITY GUIDELINES (ADAAG)

- CORRIDOR WIDTH: NOT LESS THAN 44" (60" CLR. PROVIDED) - PORTABLE FIRE EXTINGUSHERS ARE SHOWN ON PLANS

1 STORY / PRE-ENGINEERED METAL BUILDING (PEMB

BUILDING HEIGHT: 18'-10" (1 STORY) / 2 STORIES ALLOWABLE

AREA: 8,259 S.F. (GROSS) / 17,500 ALLOWABLE

- MINIMUM NO. OF EXITS 2 (5 PROVIDED)
- MAXIMUM EXIT ACCESS TRAVEL DISTANCE = 200 FT. / NS - MAXIMUM COMMON PATH OF EGRESS TRAVEL = >30 / 75 FT.
- PLUMBING: WATER CLOSETS 83 OCC. / 1 PER 100 = 1 LAVATORIES 83 OCC. / 1 PER 100 = 1 **DRINKING FOUNTAINS** 83 OCC. / 1 PER 400 = 1 SERVICE SINK

**1 SERVICE SINK** 


## **OCCUPANT LOADS**

OCCUPANCY CLASSIFICATION AND OCCUPANCY LOADS CHAPTER 3 - SECTION 302 & 304 / SECTION 1004.1 - TABLE 1004.1.2

TOTAL OCCUPANCY: 83 OCCUPANTS (OCC.)

GROUP B - BUSINESS (OFFICE / MOTOR VEHICLE SHOW ROOM) = 100 GROSS 8,259 SF / 100 = 83 OCC.

: IMAGE SHOWN FOR REPRESENTATIONAL PURPOSES ONLY



### CIV

CO\

A1.0 A1.1 A2.1 A2.2 A3.1 A3.2 A4.1 A4.2 A5.0 A5.1

S1.0 S1.1 S2.1 S4.1

P.E.


P1.0 P2.1 P2.2

M1.0 M2.1 M2.2

E0.1 E1.0 E1.2 E2.1 E2.2 E2.3

## THF PROJECT #2019-25

INDEX OF DRAWINGS											
SHEET #	SHEET TITLE	ISSUED	REV. DATE								
VER	PROJECT DATA / INFORMATION	05/13/20	02/05/21								
/IL	AREA & GRADING PLAN - LAND DISTURBANCE	04/10/20	08/11/20								
0	FLOOR PLAN & REFLECTED CEILING PLAN	05/13/20	02/05/21								
1	NOTED / FINISH FLOOR PLAN	05/13/20	02/05/21								
1	EXTERIOR ELEVATIONS & DETAILS	05/13/20	02/05/21								
2	VIC FLOOR PLAN, SECTION & DETAILS	05/13/20	11/04/20								
 1	OVERALL BUILDING SECTIONS & DETAILS	05/13/20									
2	STEEL FRAMING DETAILS	05/13/20									
1	SCHEDULES & DETAILS	05/13/20	02/05/21								
2	SECTIONS, ELEVATIONS & DETAILS	05/13/20									
0	TYPICAL FENCE DETAILS	05/13/20									
1	TYPICAL PENETRATION DETAILS	05/13/20									
		· · ·									
0	REQUIRED IBC SPECIAL INSPECTIONS	05/13/20									
1	FOUNDATION GENERAL NOTES & TYP. DETAILS	05/13/20									
1	FOUNDATION PLAN	05/13/20									
1	FOUNDATION DETAILS	05/13/20									
.M.B.		XX/XX/XX									
	P.E.M.B. (DEFERRED SUBMITTAL)										
0	PLUMBING PLANS	05/13/20	11/04/20								
0 1	PLUMBING SCHEDULES AND DETAILS	05/13/20	11/04/20								
2	PLUMBING DETAILS	05/13/20	11/04/20								
.0	MECHANICAL PLAN	05/13/20	02/05/21								
.1	MECHANICAL NOTES AND DETAILS	05/13/20									
.2	MECHANICAL SCHEDULES	05/13/20									
1	ELECTRICAL SITE PLAN	05/13/20	09/02/20								
0	ELECTRICAL PLANS	05/13/20	02/05/22								
2	V.I.C. & M/C ELECTRICAL PLANS	05/13/20									
1	ELECTRICAL SCHEDULES AND NOTES	05/13/20									
2	ELECTRICAL LIGHTING SCHEDULES AND DETAILS	05/13/20									
3	ELECTRICAL PANEL SCHEDULES	05/13/20	09/02/20								







3100 S Market Street, Suite 202 Rogers, Arkansas 72758 (479) 621-6128 rmw@tatumsmith.com

**GREG ANDERSON** 9 West 26th Circle Fayetteville, AR 72701 P:(479)601-3331 / ga@gaengr.com SOUTH


THE HILL FIRM


INC.


Fort Smith, AR

No. 101657

 $\mathbf{C}$ 









2020 THE HILL FIRM - ARCHITECT. ALL RIGHTS RESERVED

RIGINAL SHEET SIZE 36 x 24 / DO NOT SCALE DRAWING





FLOOR FINISH		WALL FIN
CARPET 1: MNFR: STYLE STYLE #: COLOR: COLOR #:	Shaw Space 50911 Steeling Beauty 11500	PAINT 1: MNFR: STYLE: COLOR: COLOR #
LVT: MNFR: TYPE: COLOR: COLOR #:	Armstrong Vivero Best - Kingsville Oak Gate House Gray U1081	PAINT 2: MNFR: STYLE: COLOR: COLOR #
<u>S. CONC.:</u> (sea MNFR: TYPE:	CONCRETÉ SEALERS USA SILICONATE MULTI- SURFACE	PAINT 3: MNFR: STYLE: COLOR: COLOR #
ITEM# NOTE: PER AP DOORS	PS1015G PROVED SUBMITTAL	<u>PAINT 4:</u> MNFR: COLOR: COLOR #
INTERIOR: (cod MNFR: TYPE: FINISH: EXTERIOR: (se	ordinate w/ schedule) Marshfield / Masonite Flush Solid Core Red Oak Natural/Clear ee schedule)	<u>NOTE:</u> Re <u>PAINT 5:</u> MNFR: STYLE: COLOR: COLOR #
		<u>Paint 6:</u> MNFR: Color: Color #
		<u>PAINT 7:</u> MNFR: COLOR: COLOR #

1 <u>FLOOR PLAN - F.F.L. (NOTED / FINISH)</u> 1/8" = 1'-0"

### FINISH LEGEND

#### VALL FINISH

AINT 1: (interior walls - Light Gray) INFR: TYLE: S/B Sherwin Williams Satin OLOR: Site White OLOR #: SW 7070

AINT 2: (interior walls - Gray) S/B Sherwin Williams Satin COLOR: Software

AINT 3: (interior walls - White) INFR: TYLE: S/B Sherwin Williams Satin OLOR: Extra White OLOR # SW 7006

AINT 4: (Dry Erase Paint) NFR: Sherwin Williams OLOR: Clear Gloss Coating OLOR #: KB65C200 Kit

<u>OTE:</u> Requires Paint 3 - SW 7006 Base Coat

AINT 5: (door frames) NFR: Sherwin Williams TYLE: COLOR: Semi gloss Black OLOR #: SW6993

P<mark>AINT 6:</mark> (exterior wall) /INFR: Sherwin V Sherwin Williams OLOR: Extra White OLOR #: SW7006

AINT 7: (exterior accent / band at top of building) Sherwin Williams NFR: COLOR: Safety Rec COLOR #: SW4081 Safety Red

CEILING FINISH LAY-IN:

MNFR: Armstrong SIZE: 24 in. x 48 in. STYLE: Optima Lay-in & Tegular STYLE #: 3151 COLOR: White

GYPSUM BOARD: (Paint) MNFR: American G American Gypsum or Equal TYPE: USG 5/8" Tapered Edge

Match Adjacent Walls

#### FRP FINISH

COLOR:

FIBER REINFORECED PLASTIC (FRP):MNFR:Marlite Marlite STYLE: Standard COLOR #: P 100 White TEXTURE: Pebbled

#### BASE FINISH

VINYL: MNFR: Roppe STYLE: SIZE: Vinyl Base 4 inch COLOR: Black COLOR # 100

#### LAMINATE FINISH

LAMINATE: (millwork) MNFR: Wilsonart International STYLE: Standard Laminate PATTERN #: 4622-60 COLOR: Grey Nebula

LAMINATE: (ADA Flip up countertop) MNFR: Wilsonart International STYLE: Standard Laminate PATTERN #: 4623-60 COLOR: Graphite Nebula

#### STONE VENEER

SYNTHETIC STONE:(buyer counter front)MNFR:Tritan BP STYLE: Lighting Ridge Panel COLOR #: Gray Fox – LR-4824-GFX

#### <u>QUARTZ</u>


QUARTZ COUNTERTOP:MNFR:Wilsonart STYLE: Vesuvius COLOR #: Q1017 EDGE PROFILE:1/4 Round

#### FREESTANDING OPEN METAL SHELVING: MNFR: Grainger BRAND: Edsal STYLE: Freestanding Open

Metal Shelving (5 Shelves) SIZE: 36"W x 18"D x 72" H COLOR: Gray


### FINISH SCHEDULE FLOOR BASE A LVT 1 VINYL (4") CARPET / CPT-1 2 NONE SEALED CONCRETE NOT USED NONE SEE PLAN FOR ACCENT WALL LOCATIONS


FLOOR A 1 A 1 A BASE WALLS CEILING HEIGHT								
	WA	LLS	CEILING			ILING HEIGHT		
")	Α	GYP. BOARD (PAINT 1)	1	A.C.T.	Α	SEE R.C.P.		
	в	GYP. BOARD (PAINT 2)	2	GYP. BOARD (PAINT 3)	В	NONE		
	С	GYP. BOARD (PAINT 3)	3	NONE				
	D	GYP. BOARD (PAINT 4)						
	Е	FRP (FULL HEIGHT)						
	F	METAL WALL PANEL						
NS AND SPECIFIC	FIN	ISH NOTES						




SOUTH


INC. Fort Smith, AR No. 101657

















 $6 \frac{\text{BOLT THROUGH COLUMN DETAIL}}{3/4" = 1'-0"}$ 

















2 MOTORCYCLE SHED (MC) - ROOF PLAN 1/8" = 1'-0"

F.F.<u>L.</u>

25' - 0"

### **GENERAL NOTES:**

- 1. COORD. NUMBER OF BAYS W/ OWNER
- 2. COLUMNS, & BEAMS MUST BE PAINTED WITH PRIMED RED OXIDE


SOUTH


- 3. PLACE CONCRETE AGAINST UNDISTURBED EARTH
- 4. ALL COLD FORMED MATERIAL DESIGNED IN ACCORDANCE WITH 2007 EDITION OF AISI


3/4" DIA. X 10" LONG THREADED ROD. W/ NUTS & WASHERS THROUGH COLUMN.

TYP. COLUMN


- REINFORCED CONC. FOOTING








 $4 \frac{\text{TYP. WALL SECTION @ SALES BAY}}{3/4" = 1'-0"}$ 




							DOOR SCH	IEDULE			
DOOR				DOOR			FRAME	FRAME			HARDWARE
MARK	W	Н	Т	MAT.	TYPE	GLASS	MAT.	TYPE	Fire Rating	SET	COMMENTS/ HARDWARE
							· · · · · · · · · · · · · · · · · · ·				
100A	3' - 0"	7' - 0"	0' - 1 3/4"	Alum. & Glass	10" Bottom Rai		Alum./Black	Exterior		Entry	Push Bar / Closer / M.T.
100B	3' - 0"	7' - 0"	0' - 1 3/4"	Alum. & Glass	10" Bottom Rai		Alum./Black	Exterior		Entry	Push Bar / Closer / M.T.
100C	3' - 0"	7' - 0"	0' - 1 3/4"	Alum. & Glass	10" Bottom Rai		Alum./Black	Exterior		Entry	Push Bar / Closer / M.T.
100D	3' - 0"	7' - 0"	0' - 1 3/4"	Alum. & Glass	10" Bottom Rai		Alum./Black	Exterior		Entry	Push Bar / Closer / M.T.
101	3' - 0"	7' - 0"	0' - 1 3/4"	Wood	3'-0" x 7'-0"	N/A	H.M			Storeroom	
102	3' - 0"	7' - 0"	0' - 1 3/4"	Wood	3'-0" x 7'-0"	N/A	H.M			Privacy	Closer
103A	3' - 0"	7' - 0"	0' - 1 3/4"	Wood	3'-0" x 7'-0"	N/A	H.M			Privacy	Closer
104	3' - 0"	7' - 0"	0' - 1 3/4"	Wood	3'-0" x 7'-0"	N/A	H.M			Privacy	Closer / Kick Plate(s)
105	3' - 0"	7' - 0"	0' - 1 3/4"	Wood	3'-0" x 7'-0"	N/A	H.M			Push Button	Closer / KickPlate(s) / Key Pad to Lobby
106	3' - 0"	7' - 0"	0' - 1 3/4"	Wood	3'-0" x 7'-0"	N/A	H.M			Classroom	
107	3' - 0"	7' - 0"	0' - 1 3/4"	Wood	3'-0" x 7'-0"	N/A	H.M		20 MIN.	Classroom	
108A	3' - 0"	7' - 0"	0' - 1 3/4"	Metal	3'-0" x 7'-0"	N/A	P.E.M.B.	Exterior		Entry	Closer / M.T.
108D	3' - 0"	7' - 0"	0' - 1 3/4"	Wood	3'-0" x 7'-0"	N/A	H.M		20 MIN.	Push Button	Closer / KickPlate(s) / Key Pad to Corridor
109	3' - 0"	7' - 0"	0' - 1 3/4"	Wood	3'-0" x 7'-0"	N/A	H.M		20 MIN.	Passage	KickPlate(s)
110	3' - 0"	7' - 0"	0' - 1 3/4"	Wood	3'-0" x 7'-0"	N/A	H.M		20 MIN.	Passage	Closer
111	3' - 0"	7' - 0"	0' - 1 3/4"	Wood	3'-0" x 7'-0"	N/A	H.M		20 MIN.	Passage	Closer
112	3' - 0"	7' - 0"	0' - 1 3/4"	Wood	3'-0" x 7'-0"	N/A	H.M		20 MIN.	Storeroom	Vent Louver in lower portion of Door
113	3' - 0"	7' - 0"	0' - 1 3/4"	Wood	3'-0" x 7'-0"	N/A	H.M		20 MIN.	Push Button	Key Pad to Corridor
114	3' - 0"	7' - 0"	0' - 1 3/4"	Wood	3'-0" x 7'-0"	N/A	H.M		20 MIN.	Push Button	Key Pad to Corridor
115	3' - 0"	7' - 0"	0' - 1 3/4"	Wood	3'-0" x 7'-0"	N/A	H.M		20 MIN.	Push Button	Key Pad to Corridor
	3' - 0"		0' - 1 3/4"	Wood	3'-0" x 7'-0"	N/A	H.M		20 MIN.	Classroom	
118A	3' - 0"	7' - 0"	0' - 1 3/4"	Metal	3'-0" x 7'-0"	1/2 Glass	P.E.M.B.	Exterior	20 10111	Entry	Closer / Kick Plate(s) / M.T.
118B	3' - 0"	7' - 0"	0' - 1 3/4"	Metal	3'-0" x 7'-0"	N/A	H.M	LACHO	3/4 HR.	Push Button	Closer / Kick Plate(s) / M.T. / Key Pad to Lobby
118C	3' - 0"	7' - 0"	0' - 1 3/4"	Metal	3'-0" x 7'-0"	N/A	H.M		3/4 HR.	Push Button	Closer / KickPlate(s) / M.T. / Key Pad to Sales Ba
118D	3' - 0"	7' - 0"	0' - 1 3/4"	Metal	3'-0" x 7'-0"	1/2 Glass	P.E.M.B.	Exterior	5/41111.	Entry	Closer / Kick Plate(s) / M.T.
118E	3' - 0"	7' - 0"	0' - 1 3/4"	Metal	3'-0" x 7'-0"	1/2 Glass	P.E.M.B.	Exterior		,	Closer / Kick Plate(s) / M.T.
	<u> </u>	6' - 0"	0 - 1 3/4					EXIGNO		Entry	
118F	-			Chain-Link	Gate	N/A	CHAIN-LINK			Fork Latch	Hinges (x3) / Lockable Latch / Privacy Slats
	4' - 0"	6' - 0"	0' 0"	Chain-Link	Gate	N/A	CHAIN-LINK			Fork Latch	Hinges (x3) / Lockable Latch / Privacy Slats
	12' - 0"	14' - 0"	0' - 2"	Metal	12' x 14'	N/A	P.E.M.B.			N/A	Insulated / Sectional / Automatic
	12' - 0"	14' - 0"	0' - 2"	Metal	12' x 14'	N/A	P.E.M.B.			N/A	Insulated / Sectional / Automatic
	12' - 0"	14' - 0"	0' - 2"	Metal	12' x 14'	N/A	P.E.M.B.			N/A	Insulated / Sectional / Automatic
	12' - 0"	14' - 0"	0' - 2"	Metal	12' x 14'	N/A	P.E.M.B.			N/A	Insulated / Sectional / Automatic
HARDWA	RE LEGEN	<u>D:</u>	I								
<u>KNOBS</u> : BRAND: MODEL: TYPE:	S SE	ILAGE ERIES 'TUNE (NEP	B	<u>OCKS</u> : RAND: SCHLA IODEL: FE595 YPE: CAMEL	GE		E ) SERIES )R CLOSER				





NOTES:

STANDARD CYLINDERS



W2





FLOOR LINE

Ŵ3

<u>SLIDING GLASS</u> TOP TRACK (ALUM.) BOTTOM

GUIDE(S) & GLASS LOCKS

WINDOW ELEVATIONS ─ 1/4" = 1'-0"

EXTERIOR H.M. - SOLID INSULATED


10.00-11.00 R-VALUE (CALCULATED)

(POLYURETHANE INSUL.) / 083 U-FACTOR

W1


HOLLOW METAL METAL W/ THERMAL BREAK

(DBL. PANE GLAZING) 0.50 U-FACTOR (MIN.) / 0.25 SHGC





ALUM. FRAME & GLASS. W/ THERMAL BREAK (DBL. PANE GLAZING) 0.83 U-FACTOR (MIN.) / 0.25 SHGC


3 OVERHEAD DOOR 1/4" = 1'-0" GARAGE DOORS (NON-SWINGING) 4.75 R-VALUE





(A) FRAME TYPES 1/4" = 1'-0"













## 16 ELEV. @ BUYERS COUNTER 3/8" = 1'-0"


## 8 FOLDING COUNTER DETAIL 3/4" = 1'-0"





흔희


13 1/2" MIN.-













1' - 0 1/2"






SOUTH

THE HILL FIRM

REDAF

INC. Fort Smith, AR No. 101657




6" MAX.


1' - 6 1/4"

WALL HUNG LAVATORY PER SPECS

8" MIN.










BLOCKING AS NEEDED

INSUL. PIPES -







#### FENCING GUIDELINES

#### 32.1 GENERAL DESCRIPTION

THE PERIMETER AND INTERIOR STANDARD FENCING APPROACH FOR IAA GENERALLY CONSISTS OF CHAIN LINK FENCING AND SWING GATES, 6' IN HEIGHT, WITH 3 STRANDS OF BARBED WIRE ANGLED TOWARD THE EXTERIOR OF THE YARD, A TOP RAIL, NO MID RAIL, AND TENSION WIRE ON BOTTOM OF THE FABRIC. IN ADDITION TO THIS GUIDELINE, LOCAL AND MUNICIPAL REGULATIONS AND STANDARDS SHALL BE IMPLEMENTED. SPECIFICALLY LOCAL ORDINANCES, REQUIREMENTS, OR ZONING SHOULD BE REVIEWED AND CONSIDERED. TYPICALLY THESE ADDITIONAL GOVERNMENTAL REQUIREMENTS, IF FOUND, WILL CHANGE THIS STANDARD IN THE FOLLOWING WAYS: 6' HEIGHT TO 8' HEIGHT, VINYL COVERED CHAIN LINK INSTEAD OF GALVANIZED, SLATS OR SOLID PANEL FENCING INSTEAD OF STANDARD CHAIN LINK. IAA WILL CONSIDER ALL COST SAVINGS DUE TO A POSSIBLE DESIGN CHANGE IN THE FOLLOWING SPECIFICATION.

#### 32.2 PURPOSE

TO PROVIDE THE CIVIL ENGINEER OF RECORD (EOR) GUIDANCE ON INSURANCE AUTO AUCTIONS' (IAA) FENCING EXPECTATIONS. THIS DOCUMENT IS INTENDED TO COMPLEMENT THE EOR'S ENGINEERING EXPERTISE AND LOCAL KNOWLEDGE TO PRODUCE THE MOST COST EFFECTIVE PAVEMENT DESIGN WHICH MEETS IAA'S MINIMUM CRITERIA SET BELOW.

#### 32.3 PRODUCTS

A. FABRIC FOR THE 2-INCH MESH SHALL BE 9-GAUGE, ZINC-COATED STEEL (ASTM A-392, CLASS 2.2.0 OUNCE PER SQUARE FOOT) HOT DIPPED GALVANIZED. TOP AND BOTTOM SELVAGE TO BE BARBED. B. BARBED WIRE SHALL BE 3 LINES OF 2 STRANDS TWISTED 12-1/2 GAUGE, ZINC-COATED WIRE WITH 4-POINT (14-GAUGE ROUND STEEL) BARBS AT 5-INCH INTERVALS COMPLYING WITH ASTM A-585, TYPE II, BARBED WIRE WITH CLASS II COATING. PROVIDE ADDITIONAL STRANDS OF BARBED WIRE WHERE REQUIRED TO MAINTAIN 4-INCH SPACING BETWEEN WIRES FOR TOP OF FENCE FABRIC.

- C. FENCE POSTS, RAILS AND BRACING ASSEMBLIES: a. ALL TUBING AND BRACES SHALL BE GIVEN AN OUTSIDE DIAMETER CORROSION PROTECTION OF 1.0+0.1 OUNCE OF ZINC PER SQUARE FOOT OF SURFACE.
  - b. LINE POSTS SHALL BE 2.0-INCH O.D. ROUND, SCHEDULE 40
- END, CORNER, PULL AND GATE POSTS SHALL BE 4.0-INCH O.D. ROUND, SCHEDULE 40. THESE LOCATIONS SHALL ALSO INCLUDE TOP RAIL ASSEMBLY TO THE NEXT POST IN LINE. TENSION WIRE SHALL BE METALLIC-COATED STEEL WIRE: 0.177" DIAMETER.
- LINE POST CAPS FOR 4-INCH AND 2-INCH FENCE POSTS SHALL INCORPORATE AN EXTENSION ARM FOR 3 STRANDS OF BARBED WIRE SET AT 45 DEGREES. ARMS SHALL BE OF SAME MATERIAL AS END RAILS AND OTHER ACCESSORIES.

ACCESSORIES: PROVIDE ALL POST TOPS, CLIPS, TIES, BANDS, STRETCHER BARS AND MISCELLANEOUS FASTENERS FOR THE COMPLETE INSTALLATION. a. STRETCHER BARS SHALL BE 3/16-INCH BARS OF LENGTH 1-INCH LESS THAN FABRIC HEIGHT. PROVIDE

ONE STRETCHED BAR FOR EACH GATE AND TERMINAL POST AND TWO FOR EACH CORNER AND PULL POST. PROVIDE TWO STRETCHER BARS FOR EACH GATE FRAME STRETCHER BAR BANDS SHALL BE HEAVY STEEL FOR SECURING STRETCHER BARS TO POSTS. FABRIC TIES SHALL BE 6-GAUGE ALUMINUM OR 9-GAUGE STEEL, WRAPPED TWICE. ALL FITTINGS AND

ACCESSORIES SHALL BE COATED IN ACCORDANCE WITH ASTM A153. CONCRETE FOR PLACING FENCE POSTS SHALL BE 3,000 PSI OR BETTER AT A MINIMUM DEPTH OF 40". WITH PROPER REVIEW AND IAA APPROVAL IF CONCRETE IS TO BE PLACED NEAR OR OUT OF MANUFACTURER'S RECOMMENDED CONSTRAINTS.

- PEDESTRIAN SINGLE AND DOUBLE SWING GATES a. FABRICATE PERIMETER FRAMES OF GATES FROM SAME MATERIAL AND FINISH AS FENCE FRAMEWORK. ASSEMBLE GATE FRAMES BY WELDING. WELD AREAS REPAIRED WITH ZINC-RICH COATING APPLIED PER MANUFACTURER'S DIRECTIONS. FABRIC TO MATCH FENCE. PROVIDE HORIZONTAL AND VERTICAL MEMBERS TO ENSURE PROPER GATE OPERATION AND ATTACHMENT
- OF FABRIC, HARDWARE, AND ACCESSORIES. FABRIC: SAME AS FOR FENCE UNLESS OTHERWISE INDICATED. SECURE FABRIC AT VERTICAL EDGES WITH TENSION BARS AND BANDS AND TO TOP AND BOTTOM OF FRAME WITH TIE WIRES.
- STORAGE: STORE GATE FRAMES ON BUILDING SITE, IN AN UPRIGHT POSITION, UNDER COVER, ON WOOD SILLS OR FLOORS, AND IN A MANNER THAT PREVENTS RUST OR DAMAGE. VENTILATE CANVAS OR PLASTIC COVERS TO PREVENT MOISTURE TRAPS. DIMENSIONS: GATE OPENING HEIGHTS AND WIDTHS SHALL BE AS SHOWN ON THE DETAIL DRAWINGS
- VEHICULAR DOUBLE SWING GATES a. FABRICATE PERIMETER FRAMES OF GATES FROM SAME MATERIAL AND FINISH AS FENCE FRAMEWORK. ASSEMBLE GATE FRAMES BY WELDING. WELD AREAS REPAIRED WITH ZINC-RICH COATING APPLIED PER MANUFACTURER'S DIRECTIONS. FABRIC TO MATCH FENCE. PROVIDE HORIZONTAL AND VERTICAL MEMBERS TO ENSURE PROPER GATE OPERATION AND ATTACHMENT
- OF FABRIC, HARDWARE, AND ACCESSORIES. b. FABRIC: SAME AS FOR FENCE UNLESS OTHERWISE INDICATED. SECURE FABRIC AT VERTICAL EDGES WITH TENSION BARS AND BANDS AND TO TOP AND BOTTOM OF FRAME WITH TIE WIRES. STORAGE: STORE GATE FRAMES ON BUILDING SITE, IN AN UPRIGHT POSITION, UNDER COVER, ON
- WOOD SILLS OR FLOORS, AND IN A MANNER THAT PREVENTS RUST OR DAMAGE. VENTILATE CANVAS OR PLASTIC COVERS TO PREVENT MOISTURE TRAPS. d. DIMENSIONS: MINIMUM TWO 10' GATES FOR A TOTAL OF 20' WIDE

#### 32.4 DIRECTIONS TO CONTRACTOR

A. CHAIN LINK FENCING INSTALLATION

- a. GENERAL: INSTALL FENCE TO COMPLY WITH ASTM F 567. DO NOT BEGIN INSTALLATION AND ERECTION BEFORE FINAL GRADING IS COMPLETED, UNLESS OTHERWISE PERMITTED. COORDINATE FENCE POST LOCATIONS WITH OTHER TRADES PRIOR TO INSTALLATION.\
- b. STAKE LOCATIONS OF FENCE LINES, GATES, AND TERMINAL POSTS. DO NOT EXCEED INTERVALS OF 500 FEET OR LINE OF SIGHT BETWEEN STAKES. INDICATE LOCATIONS OF UTILITIES, LAWN SPRINKLER SYSTEM, UNDERGROUND STRUCTURES, BENCHMARKS, AND PROPERTY MONUMENTS. EXCAVATION: DRILL OR HAND-EXCAVATE (USING POST-HOLE DIGGER) HOLES FOR POSTS TO
- DIAMETERS AND SPACINGS INDICATED, IN FIRM, UNDISTURBED OR COMPACTED SOIL. i. IF NOT INDICATED ON DRAWINGS, EXCAVATE HOLES FOR EACH POST TO MINIMUM DIAMETER RECOMMENDED BY FENCE MANUFACTURER, BUT NOT LESS THAN FOUR TIMES THE LARGEST
- CROSS SECTION OF POST. ii. UNLESS OTHERWISE INDICATED, EXCAVATE HOLE DEPTHS APPROXIMATELY 4" LOWER THAN POST BOTTOM, WITH BOTTOM OF POSTS SET NOT LESS THAN 36" BELOW FINISH GRADE
- SURFACE d. SETTING POSTS: CENTER AND ALIGN POSTS IN HOLES 4" ABOVE BOTTOM OF EXCAVATION, UNLESS
- OTHERWISE INDICATED. SPACE A MAXIMUM OF 10' O.C., UNLESS OTHERWISE INDICATED. PROTECT PORTION OF POSTS ABOVE GROUND FROM CONCRETE SPLATTER. PLACE CONCRETE AROUND POSTS AND VIBRATE OR TAMP FOR CONSOLIDATION. CHECK EACH
  - POST FOR VERTICAL AND TOP ALIGNMENT, AND HOLD IN POSITION DURING PLACEMENT AND FINISHING OPERATIONS. UNLESS OTHERWISE INDICATED, EXTEND CONCRETE FOOTINGS 1" ABOVE GRADE AND TROWEL TO A CROWN TO SHED WATER.
- e. INSTALL PIPE POST BRACE AT TERMINAL, CORNER, PULL AND GATE POSTS AND EXTENDING TO ADJACENT LINE POST WITH DIAGONAL TRUSS ROD.
  - TERMINAL POSTS: INSTALL AT CHANGES IN HORIZONTAL OR VERTICAL ALIGNMENT OF 15 DEGREES OR MORE, AT ANY ABRUPT CHANGE IN GRADE, AND AT INTERVALS NOT GREATER THAN 500 FEET. FOR RUNS EXCEEDING 500 FEET, SPACE PULL POSTS AN EQUAL DISTANCE BETWEEN CORNER OR END POSTS.
- f. BRACE ASSEMBLIES: INSTALL BRACES AT END AND GATE POSTS AND AT BOTH SIDES OF CORNER AND PULL POSTS. LOCATE HORIZONTAL BRACES AT MIDHEIGHT OF FABRIC ON FENCES WITH TOP RAIL AND AT TWO THIRDS FABRIC HEIGHT ON FENCES WITHOUT TOP RAIL. INSTALL SO POSTS ARE PLUMB WHEN DIAGONAL ROD IS UNDER PROPER TENSION. g. BARBED WIRE ARMS: BOLT OR RIVET TO TOP OF POST. ANGLE SINGLE ARMS TOWARD APPROACH
- SIDE OF FENCE. h. FABRIC: LEAVE APPROXIMATELY 2" BETWEEN FINISH GRADE AND BOTTOM SELVAGE UNLESS
- OTHERWISE INDICATED. PULL FABRIC TAUT AND TIE TO POSTS, RAILS, AND TENSION WIRES. INSTALL FABRIC ON SECURITY SIDE OF FENCE, AND ANCHOR TO FRAMEWORK SO THAT FABRIC REMAINS UNDER TENSION AFTER PULLING FORCE IS RELEASED. TENSION OR STRETCHER BARS: THREAD THROUGH FABRIC AND SECURE TO END, CORNER, PULL,
- AND GATE POSTS WITH TENSION BANDS SPACED NOT OVER 24" O.C. FASTEN FABRIC TO TENSION WIRE WITH HOG RINGS OF SAME MATERIAL AND FINISH AS FABRIC WIRE. EXTENDED ALONG TOP AND BOTTOM OF FENCE FABRIC. INSTALL TOP TENSION WIRE
- THROUGH POST CAP LOOPS. INSTALL BOTTOM TENSION WIRE WITHIN 6 INCHES OF BOTTOM OF FABRIC AND TIE TO EACH POST WITH NOT LESS THAN SAME DIAMETER AND TYPE OF WIRE. MAXIMUM SPACING: TIE FABRIC TO LINE POSTS 12" O.C. AND TO RAILS AND BRACES 24" O.C. FASTENERS: INSTALL NUTS FOR TENSION BANDS AND CARRIAGE BOLTS ON THE SIDE OF THE FENCE OPPOSITE THE FABRIC SIDE. PEEN ENDS OF BOLTS OR SCORE THREADS TO PREVENT REMOVAL OF NUTS FOR ADDED SECURITY.


SOUTH

INC.


Fort Smith, AR

No. 101657

- B. GATE INSTALLATION a. INSTALL GATES PLUMB, LEVEL, AND SECURE FOR FULL OPENING WITHOUT INTERFERENCE. INSTALL GROUND-SET ITEMS IN CONCRETE FOR ANCHORAGE. ADJUST HARDWARE FOR SMOOTH OPERATION AND LUBRICATE WHERE NECESSARY. INSTALL GATES ACCORDING TO MANUFACTURER'S INSTRUCTIONS, PLUMB, LEVEL, AND SECURE
- FIFTEEN FEET CONSTRUCTION ACCESS OPENINGS IN PERIMETER FENCE MAY BE USED AT THE CONTRACTOR'S DISCRETION. NUMBER AND LOCATION SHALL BE APPROVED, IN WRITING, BY THE ARCHITECT/ENGINEER. FINAL INSTALLATION OF PORTIONS OF THE FENCING SHALL BE DONE WHEN CONSTRUCTION OF ALL INTERIOR WORK IS SUBSTANTIALLY COMPLETE. D. CLEAN UP AND ADJUSTING
  - a. UPON COMPLETION OF THE WORK, INSPECT THE ENTIRE INSTALLATION. CORRECT ALL DEFECTIVE WORK. REPLACE ALL DAMAGED AND DEFECTIVE
  - PARTS WITH NEW MATERIALS. b. GATES: AFTER REPEATED OPERATION OF COMPLETED INSTALLATION EQUIVALENT TO 3 DAYS' USE BY NORMAL TRAFFIC. READJUST GATES FOR OPTIMUM OPERATING CONDITION AND SAFETY. LUBRICATE OPERATING EQUIPMENT AND CLEAN EXPOSED SURFACES.



shall include the following construction features: beyond each surface of the wall. types and sizes of cables may be used: chloride (PVC) insulation and jacketing material. linked polyethylene (XLPE) jacket. cables with PVC insulation and jacket. aluminum clad or steel clad TEK cable. (Romex) with PVC insulation and jacket. Hylar jacket and insulation.





TYPICAL PENETRATION

DATE: JOB NO. 05/13/2020 2020-09

A5.1


DETAILS


SHEET:

			INSPECTIONS		(IBC 170	05
be employed to provide Spec	cial Inspections	s during cons	vith Section 1705 of 2018 IBC. An independent testing agency shall struction on the types of work listed under Section 1705. The	NONDESTRUCTIVE	TESTING	(9
following areas of work requ 2. Refer to project specification	ion for addition	nal quality co	accordance with 2018 IBC. ontrol/quality assurance requirements. additional Special Inspection requirements with the Owner and	Verification & Inspection	Continuous	
<ul> <li>applicable building authoritie</li> <li>Special Inspections are not t</li> </ul>	s.	-		CJP welds (Risk Cat. II)		
	ions Réports s	shall be emai	led to the SEOR Richard M. Welcher, P.E., (rmw@tswstructural.com)			
	STf	RUCTI	JRAL STEEL	CJP welds (Risk Cat. III or IV)	×	
			705.12.1 \$ 1705.13.1)	Access holes (flange >2" for	~	
PRIOR TO WELDIN	Continuous		, AISC 360-16; TABLE J6.1, AISC 341-16) Detailed Instructions	rolled shapes, web >2" for built-up shapes)	×	
Verify welding procedures (WPS) and manufacturer certifications	×			Welded joints subject to fatigue Document all nondestructive testing	× ×	-
for welding consumable available Verify type and grade of material.		×	For components of seismic force resisting system, perform on a random, daily basis per AISC 341-14 Section J5.1.	k-area		
Welder identification		×	A system shall be maintained by which a welder who has welded a joint or member can be identified. For components of seismic force resisting system, perform on a random, daily basis per AISC		×	
Fit-up groove welds		×	341-14 Section J5.1. Verify joint preparation, dimensions, cleanliness, tacking, and backing. For components of seismic force resisting system,	CJP groove welds (all components of seismic force		
Access holes			perform on a random, daily basis per AISC 341-14 Section J5.1. Verify configuration and finish. For components of seismic force	resisting system)	×	
Fit-up of fillet welds		×	resisting system, perform on a random, daily basis per AISC 341-14 Section J5.1. Verify dimensions, cleanliness, and tacking. For components of			
-ic-up of filler weids		×	seismic force resisting system, perform on a random, daily basis per AISC 341-14 Section J5.1.	Base metal (>1 1/2")		
Check welding equipment		×	 AISC 360-16; TABLE J6.2, AISC 314-16)		×	
Verification & Inspection	Continuous	Periodic	Detailed Instructions			
Use of qualified welders Control and handling of welding		×	Verify that welders are appropriately qualified. For components of seismic force resisting system, perform on a random, daily basis per AISC 341-14 Section J5.1. Verify packaging and exposure control. For components of	Beam Cope and Access Holes (flange >1 1/2" for rolled shapes, web thickness >1 1/2" for built-up sections)	×	
consumables		×	seismic force resisting system, perform on a random, daily basis per AISC 341-14 Section J5.1.	Reduced beam section repair		-
Cracked tack welds		×	Verify welding does not occur over cracked tack welds. For components of seismic force resisting system, perform on a random, daily basis per AISC 341-14 Section J5.1.		X	
Environmental conditions		×	Verify wind speed within limits, precipitation and temperature. For components of seismic force resisting system, perform on a random, daily basis per AISC 341-14 Section J5.1.	Weld tab removal sites		
MPS followed			Verify settings on welding equipment, travel speed, welding materials, shielding gas type/flow rate, preheat applied, interpass		×	
		×	temperature maintained, and proper position. For components of seismic force resisting system, perform on a random, daily basis per AISC 341-14 Section J5.1.			
Welding techniques		×	Verify interpass and final cleaning, each pass within profile limitations, and quality of each pass. For components of seismic	OTHER STEEL INSPE	CTIONS (	(5
			force resisting system, perform on a random, daily basis per AISC 341-14 Section J5.1.	Verification & Inspection	Continuous	,
AFTER WELDING	(TABLE N Continuous	N <b>5.4-3</b> , A Periodic	AISC 360-16; TABLE J6.3, AISC 314-16)	Structural steel details (fabricated steel or steel frames)	a	
Welds cleaned		×	Verify welds properly cleaned. For components of seismic force resisting system, perform on a random, daily basis per AISC			
Size, length, and location of	×		341-14 Section J5.1.	Anchor rods and other embedments supporting structural		
welds Welds meet visual acceptance criteria	×		Verify crack prohibition, weld/base metal fusion, crater cross section, weld profiles, weld size, undercut, and porosity meet	steel		
Arc strikes	×		visual acceptance criteria.	Reduced beam sections (RBS)	×	
k-area Backing & weld tabs removed	×			Protected zones	×	
and finished, and fillet welds added (if required) Repair activities	× ×			H-piles	N/A	+
Document acceptance or rejection of welded	×			WELDING OF	REINFOR	⊥ ≷∢
joint/member Placement of reinforcing or	×		Only required in components of seismic force resisting system.	Verification & Inspection Verification of weldability	Continuous	7
contouring fillet welds <b>PRIOF</b>	R TO BOI	LTING (1	ABLE N5.6-1, AISC 360-16)	Inspect single pass fillet welds,		+
Verification & Inspection Manufacturer's certifications	Continuous X	Periodic	Detailed Instructions Verify certifications available for fastener materials.	max 5/16" Inspect all other welds	×	+
Fasteners marked		×	Verify marked in accordance with ASTM requirements. For components of seismic force resisting system, perform on a random, daily basis per AISC 341-14 Section J5.1.			
Fastener selection		×	Verify proper selection for joint detail including grade, type, and bolt length if threads excluded from shear plane. For components of seismic force resisting system, perform on a random, daily basis per AISC 341-14 Section J5.1.			
Bolting procedure		×	Verify proper bolting procedure selected for joint detail. For components of seismic force resisting system, perform on a			
Connecting surfaces			random, daily basis per AISC 341-14 Section J5.1. Verify connecting elements, including the appropriate faying surface condition and hole preparation, if specified, meet			
		×	surface condition and hole preparation, if specified, meet applicable requirements. For components of seismic force resisting system, perform on a random, daily basis per AISC 341-14 Section J5.1.			
Pre-installation verification testing by installation personnel	×		Observe and document for fastener assemblies and methods used.			
Fastener storage		×	Verify proper storage provided for bolts, nuts, washers, and other fastener components. For components of seismic force resisting system, perform on a random, daily basis per AISC			
מו ורז		FING (TA	341-14 Section J5.1. BLE N5.6-2, AISC 360-16)			
Verification # Inspection	Continuous	Periodic	Detailed Instructions			
Position of fasteners		×	Verify fastener assemblies, of suitable condition, are placed in all holes and washers, if required, are positioned as required. For components of seismic force resisting system, perform on a random, daily basis per AISC 341-14 Section J5.1.			
Joint brought into snug-tight condition prior to the pretensioning operation		х	For components of seismic force resisting system, perform on a random, daily basis per AISC 341-14 Section J5.1.			
Fastener components not turned by the wrench are prevented from rotating		×	For components of seismic force resisting system, perform on a random, daily basis per AISC 341-14 Section J5.1.			
Pretensioning of fasteners		×	Fasteners are pretensioned in accordance with the RCSC specification, progressing systematically from the most rigid point toward the free edges. For components of seismic force resisting			
		ING (TA	system, perform on a random, daily basis per AISC 341-14 Section J5.1. BLE N5.6-3, AISC 360-16)			
			Detailed Instructions			
Verification & Inspection Document acceptance or	COntinuous					

© cì ∂

5			STEEL (CONT.)	Co	ONCR	ETE C	ONSTRUCTION			
	(IBC 170	5.2.1, 17	105.12.1 \$ 1705.13.1)	(IBC	1705.3;	TABLES	J9.2 & J9.3, AISC 341-16)			
			N N5.5, AISC 360-16; SECTION J6, AISC	Verification & Inspection	Continuous	Periodic	Detailed Instructions			
			4-16)	Reinforcing steel, including			Verify, prior to placing concrete, reinforcing is of specified			
	•			prestressing tendons			type, grade and size; free of oil, dirt and rust; located and spaced properly; hooks, bends, ties, stirrups and supplemental			
	Continuous		Detailed Instructions Ultrasonic testing shall be performed on 10% of CJP groove welds			×	reinforcement placed correctly; lap lengths, stagger and offsets			
			in butt, T- and corner joints subject to transversely applied				provided; and all mechanical connections installed per the			
		×	tension loading in materials 5/16-inch thick or greater. Testing				manufacturer's instructions and/or evaluation report.			
		~	rate must be increased if >5% of welds tested have unacceptable	Cast-in anchors		×	Verify anchor installation complies with ACI 318: 17.8.2. All post-installed anchors shall be specially inspected as required			
			defects. See AISC 360-14 Section N5.5f for increase requirements.	Post-installed anchors			by the approved ICC-ES report. Anchors installed horizontally or			
			Ultrasonic testing shall be performed on all CJP groove welds			×	in upwardly inclined orientations to resist tension loads require			
14)			subject to transversely applied tension loading in butt, T- and				continuous inspection per ACI 318:17.8.2.4. Verify all other			
	×		corner joints, in materials 5/16-inch thick or greater. See AISC				mechanical and adhesive anchors comply with ACI 318: 17.8.2.			
			360-14 Section N5.5e for reduction in rate of ultrasonic testing.	Use of required mix design		×	Verify mixes comply with the approved construction documents; ACI 318: Ch. 19, 26.4.3, 26.4.4 and IBC 1904.1, 1904.2, 1908.2,			
or	~						ACI 518: CH. 19, 28.4.5, 28.4.4 and 18C 1904.1, 1904.2, 1908.2, 1908.3			
	×		Verify no cracks present per AISC 360-14 Section N5.5c.	Concrete sampling for strength			Verify sampling in accordance with ASTM C172 and ASTM C31.			
atigue	×			tests, slump, air content, and	×		See ACI 318: 26.12 for evaluation and acceptance of concrete.			
ve	~		Verify record indicates basis of rejection and location of defect	temperature	~		See ACI 318: 26.5 for mixing requirements of concrete. See IBC			
	×		for all rejected welds.	Concrete & shotcrete placement			1908.10 for shotcrete. Verify proper application techniques. See ACI 318: 26.5.2. See			
			For components of seismic force resisting system: Perform	Concrete & shotcrete placement	х		IBC 1908.6-8 for shotcrete rebound, joint, and damage			
			magnetic particle testing for cracks where welding of doubler plates, continuity plates, or stiffeners has been performed in the				requirements.			
	×		k-area. Testing area shall include the k-area base metal within 3	Curing temperature and techniques			Verify concrete surface temperature (other than			
			inches of weld. Inspection shall be performed no sooner than 48				high-early-strength) is kept >50°F in moist condition for at least			
			hours following completion of welding.				7 days after placement unless accelerated curing is used.			
			Ultrasonic testing shall be performed on 100% of CJP groove			×	High-early-strength concrete shall be kept >50°F in moist condition for at least 3 days unless accelerated curing is used.			
rce			welds in materials 5/16-inch thick or greater. Magnetic particle				See IBC 1908.9 for curing of shotcrete requirements. Verify			
	×		testing shall be performed on 25% of all beam-to-column CJP groove welds. See AMS D1.1/D1.1M Table 6.2 for				compliance with cold weather requirements in ACI 318: 26.5.4 or			
	~		acceptance/rejection criteria. See Sections J6-2g and J6-2h in				hot weather requirements in ACI 318: 26.5.5, whichever is			
			AISC 341-14 for potential reduction in the rate of magnetic	Pre-stressed concrete			applicable. Verify application of prestressing force and grouting of bonded			
			particle and ultrasonic testing.	Fre-scressed concrele	N/A	N/A	prestressing tendons in accordance with ACI 318: 26.10.			
			For components of seismic force resisting system: Ultrasonic testing for discontinuities shall be performed, after joint	Erection of precast concrete			Verify all precast elements are lifted, assembled and braced in			
			completion, behind and adjacent to fusion line of CJP groove		N/A	N/A	accordance with the approved construction documents. See ACI			
	×		welds where base metal (>1 1/2") is loaded in tension in				318: 26.9.			
			through-thickness direction in T- and corner joints and the connection material is >3/4" thick. See AWS D1.1/D1.1M Table 6.2	Strength verification		×	Verify adequate strength has been achieved prior to the removal of shores and forms or the stressing of post-tensioned tendons.			
			for acceptance/ rejection criteria.				See ACI 318: 26.11.2.			
oles				Formwork			Verify forms are placed plumb and conform to the shapes, lines,			
napes,	×		For components of seismic force resisting system: Magnetic			×	and dimensions of the members as required by the approved			
puilt-up			particle testing or penetrant testing shall be performed.	Limits on water added at the truck			construction documents. See ACI 318: 26.11.1.2.			
pair			For components of seismic force resisting sustem: Magnetic	cimits on water added at the truck			Verify during concrete placement. Applicable to composite construction in seismic force resisting system components.			
			particle testing shall be performed on any weld and adjacent area	- · · · · · · · · · · · · · · · · · · ·		×	Perform on a random daily basis per AISC 341-14 Section J5.1.			
	×		of the reduced beam section cut surface that has been repaired				See Table J9-2, AISC 341-14.			
			by welding, or on the base metal of the reduced beam section cut	Proper placement techniques to			Verify during concrete placement. Applicable to composite			
			surface if sharp notch has been removed by grinding.	limit segregation		×	construction in seismic force resisting system components. Perform on a random daily basis per AISC 341-14 Section J5.1.			
			For components of seismic force resisting system: Magnetic particle testing shall be performed on same beam-to-column joints				See Table 19.2. AISC 341-14.			
			receiving ultrasonic testing under the CJP groove welds for							
	×		components of seismic force resisting system listed in this table.							
			See Section J6-2f and Section J6-2b of AISC 341-14 for reference. See Sections J6-2g and J6-2h in AISC 341-14 for	SOILS CONSTRUCTION						
			potential reduction in the rate of magnetic particle and ultrasonic			(IBC 1705.6)				
			testing.	Verification & Inspection	<b>6</b>		Detailed Instructions			
NSPE	CTIONS (	SECTION	N5.8, AISC 360-16; TABLES J8.1 & J10.1,	Verification & inspection Verify subgrade is adequate to	Continuous	Periodic				
	- · · - · ·		341-16)	achieve design bearing capacity		×	Prior to placement of concrete; per Geotechnical Report.			
	Continuous	Periodic	Detailed Instructions	Verify excavations extend to		x	Prior to placement of compacted fill or concrete; per			
bricated	Continuous		Verify compliance with the details in construction documents in	proper depth and material		^	Geotechnial Report			
			items including: braces, stiffeners, member locations, and proper	Verify subgrade has been		×	Prior to placement of compacted fill; per Geotechnical Report			
		×	application of joint details at each connection. For components of	appropriately prepared prior to placing compacted fill		×	Prior to placement of compacted fill; per Geolechnical Report			
			seismic force resisting system, perform on a random, daily basis per AISC 341-14 Section J5.1.	Perform classification and testing			All materials shall be checked at each lift for proper			
			Verify compliance with construction documents. Verify diameter,	of compacted fill materials		×	classifications and gradations not less than once for each			
ructural			arade, type, length of anchor rod or embedded item, and extent				10,000 sqft. of surface area unless otherwise noted; per			
		×	or depth of embedment prior to placement of concrete. For				Geotechnical Report			
			components of seismic force resisting system, perform on a	∨erify proper materials, densities and lift thicknesses	×		During placement and compaction on compacted fill; per Geotechnical Report			
			random, daily basis per AISC 341-14 Section J5.1.	and the linchiesses			Geotechnical Report			
RBS)	×		For seismic force resisting system components: Verify contour and finish as well as dimensional tolerances.							
			For seismic force resisting system components: Verify that no	I INSt		ON Of	= FABRICATORS			
	×		holes or unapproved attachments are made within the protected				1704 0)			
			zone.			•	1704.2)			
			For seismic force resisting system components: Verify that no	Verification & Inspection	Continuous	Periodic	Detailed Instructions			
	N/A	N/A	holes or unapproved attachments occur within the protected zones of piling.	Verify fabricator maintains		~				
				detailed fabrication and quality control procedures		×	See IBC 1704.2.5.1.			
7 U F	i	i	EEL (IBC 1705.3.1, TABLE 1705.3)	Submittal of certificate of		1	Where work is done on premises of "Approved" fabricator.			
	Continuous	Periodic	Detailed Instructions	compliance		×	Fabricator shall submit a Certificate of Compliance to the building			
		×	Verify weldability of reinforcing steel other than ASTM A706 in accordance with ANS D1.4.				official stating work was performed in accordance with the			
elds,							approved construction documents. See IBC 1704.2.5.1.			
		×	Verify weld meets acceptance criteria of AWS D1.4.							
	×		Verify weld meets acceptance criteria of AWS D1.4.							





#### CONSTRUCTION SAFETY GENERAL NOTE

THE STRUCTURAL ENGINEER SHALL NOT BE RESPONSIBLE FOR CONSTRUCTION MEANS, METHODS, TECHNIQUES, SEQUENCES OR PROCEDURES, OR FOR SAFETY PRECAUTIONS AND PROGRAMS, SINCE THESE ARE SOLELY THE CONTRACTOR'S RESPONSIBILITY.

#### Concrete General Notes

3100.1 All detailing, fabrication and placing of reinforcing steel shall conform to the ACI Standard "Details and Detailing of Concrete Reinforcement" (ACI 315).

#### 3100.2.

All concrete for building \$ VIC foundations shall develop a 28-day minimum compressive strength of 3,000 psi \$ have a 5" maximum slump. All concrete for slabs shall develop a 28-day minimum compressive strength of 3,500 psi & have a 5" maximum Slump. See Arch. and specifications for mix design requirements.

3100.3. All reinforcing steel shall be deformed bars conforming to ASTM A615, Grade 60.

#### 3100.4.

Reinforcing bar splices shall be 44 bar diameters for #6 and smaller diameter bars. Splices for #7 and larger diameter bars shall be 48 bar diameters.

#### 3100.5.

All reinforcing bar hooks shall be ACI standard 90 degree hook, unless noted otherwise.

#### 3100.6.

Provide corner bars in footings & turn-down slab same size & spacing as longitudinal reinforcing.

#### 3100.7.

Provide (1) #4 hoop with 8" lap in slab around floor drains and slab penetrations greater than 3" in diameter. Also install around electrical conduit groupings 3" in diameter or greater. CONDUIT SHALL NOT BE RUN UNDERNEATH COLUMN FOOTINGS OR SPREAD FOOTINGS.

#### 3100.8.

 ${f O}$  Welded wire fabric shall conform to ASTM A1064. Provide mesh in flat sheets.

#### 3100.9.

Wire fabric reinforcing shall lap 6" and be securely wired at each side and end.

#### 3100.10

Bar supports at footings & slab-on-grade shall be factory made wire bar supports. Bearing plates may be required under bar supports to maintain reinf. position during concrete placement.

#### 3100.11

Smooth dowels shall be steel conforming to ASTM A36.

#### 3100.12

All slots, sleeves and other embedded items shall be set before concrete is placed. See architectural, electrical, mechanical, and vendor's drawings for size & locations.

#### 3100.13.

The top of all concrete pedestals shall be square, level, and smooth to support the metal building base plates.

#### 3100.14

Plate dowel system shall be Diamond Dowel System by PNA Construction Technologies, the Spread Plate System by Greenstreak Group, Inc., or approved equal. Install plate dowels at slab construction joints @ 18" o.c.

#### 3100.15.

Provide two #4 x 4'-O" long diagonal bars in top face at all re-entrant corners in slab and at any other locations denoted on the plans.

#### 3100.16

No site-specific geotechnical report including foundation recommendations was available at the time of original issue. In accordance with Section 1806.2 of the 2018 International Building Code a presumed maximum allowable bearing pressure for shallow foundations of 1,500 psf has been utilized. Presumed bearing material per Table 1806.2 are clay, sandy clay, silty clay, clayey silt, silt and sandy silt (DL, ML, MH, and CH). Foundations may also bear on engineered fill of type and placement method approved by a registered Geotechnical Engineer licensed in the state of South Carolina. Slab-on-grade design considers a minimum modulus of subgrade reaction (k-value) of 100 psi/in. will be provided.

#### 3100.17

Use of compacted free-draining pea gravel, crushed stone, or coarse sand having no more than 50% passing the No. 50 sieve and no more than 5% passing the No. 200 sieve is recommended by TSWE, Inc. Consult Geotechnical Engineer regarding potential substitution of these materials with approved subgrade. Slabs-on-ground have been designed for a modulus of subgrade reaction (k-value) of 100 psi/in.

A.R.

Δ

EXPANSIVE CLAYS, LOW-STRENGTH SOILS, SOFT SOILS AND SOILS WITH ORGANIC MATERIAL ARE NOT SUITABLE FOR SUPPORTING THE SLAB AND FOUNDATIONS. IF CONTRACTOR DISCOVERS UNSTABLE MATERIAL DURING EARTHWORK, A GEOTECHNICAL ENGINEER SHALL BE CONSULTED TO ARRIVE AT SOLUTION WHICH WILL NOT COMPROMISE THE STRUCTURAL INTEGRITY OF THE SLAB AND FOUNDATIONS.

#### Pre-Engineered Building General Notes

#### 13100.1 The design fabrication and erection of the pre-engineered building shall conform to the requirements of AISC Specifications for the Design, Fabrication and Erection of Structural Steel for Buildings and the Metal Building Manufacturer Design Practices Manual.

13100.2. Structural steel for primary framing shall conform to ASTM A572, Grade 50 or ASTM A36.

#### 13100.3. strength.

13100.4. Structural system for metal building shall be a clear-span gabled rigid frame with no interior columns. Bay spacing, roof slope, and eave heights shall be as shown on the architectural drawings.

#### 13100.5. Lateral stability along the sidewalls for the metal building shall be provided by the use of a cable or rod x-bracing. Coordinate type & locations of bracing with the Architect.

13100.6. All columns except those at the VIC building shall be designed as pinned ends that transmit no moment to the foundations. Columns at the VIC building are designed as cantilevered columns fixed at the base and free at the top.

#### 13100.7 Coordinate actual finish floor elevation with Civil.

13100.8. Provide rod or cable x-bracing in roof as required to resist wind and seismic loads.

13100.9.

Purlins shall be designed for a maximum live load deflection of L/150, where "L" is the purlin span in inches. Purlin deflection shall be limited to L/ 180 for wind and snow loads. 13100.10.

#### Girts shall be designed for a maximum live load deflection of L/90, where "L" is the girt span in inches. Girts at Nichiha deflection of L/240.

13100.11. Limit lateral deflection of all columns in any direction to limits shown in the following table, where "H" is the column height in inches.

WALL	COLUMN TYPE			
CONSTRUCTION	MAIN FRAME	END WALL		
METAL WALL PANEL	H/60	H/90		
FACE BRICK, MASONRY, NICHIHA	H/100	H/240		

13100.12.

All rigid frame beams shall be designed for a maximum live load deflection of L/180, where "L" is the beam span in inches. 13100.13.

The General Contractor shall purchase and install pre-engineered building anchor rods based on the Anchor Rod Setting Plan provided by the pre-engineered building manufacturer. See the Anchor Rod Schedule on this sheet for rod lengths required based on the rod diameter called for by the pre-engineered Metal Building Manufacturer.

13100.14 The Metal Building Manufacturer shall certify that the building has been designed for the loads shown on this drawing. Certification must state that the building has been designed for all roof loads, wind & seismic, as well as deflection tolerances noted in the pre-engineered building general notes & design loads. The Metal Building Manufacturer is to provide governing combined reactions (uplift, bearing, & thrust) for each column base location. The Metal Building Manufacturer is to prepare complete fabrication & erection drawings, fully engineered & sealed by a Professional Engineer licensed in the state of South Carolina.

#### 13100.15

Metal Building Manufacturer shall design purlins & rigid frames for the mechanical equipment loads in addition to the uniform dead & live loads. Coordinate equipment weight, size, and locations with the Mechanical Contractor & the manufacturer.

13100.16 Metal Building Manufacturer shall provide miscellaneous steel as required to support the mechanical equipment

13100.17. No individual anchor rod shall be set a distance less than 3" from its centerline to the edge of slab, in order to comply with ACI 318-14 requirements.

13100.18. The Metal Building Manufacturer is responsible for all header design at wall openings.

#### Pre-Engineered Building Design Loads

- 1. Roof Dead Load:
- 2. Roof Collateral Load:
- 3. Roof Live Load:
- 4. Snow Load:
- Ground Snow Load:
- Flat-roof Snow Load (P<sub>f</sub>) = 7 psf Sloped-roof Snow Load (Ps) = 7 psf
- Snow Exposure Factor  $(C_e) = 1.0$ Snow Load Importance Factor (I₅) = 1.0
- Thermal Factor ( $C_t$ ) = 1.0 @ Main Building
- Thermal Factor ( $C_t$ ) = 1.2 @ VIC Building
- 5. Wind Load: Ultimate Wind Speed, Vult, Nominal Design Wind Speed, Vasd • Wind Importance Factor  $(I_w) = 1.0$
- Building Category II
- Wind Exposure C
- 6. Seismic: Risk Category II
- Seismic Importance Factor  $(I_e) = 1.0$
- 55 = 0.342 S1 = 0.111
- 5ds = 0.348
- 5d1 = 0.176 Site Class D (presumed per ASCE 7-16 Sect. 11.4.3)
- Seismic Design Category C
- Basic Structural System . Response Modification Coefficient (R) -
- Deflection Amplification Factor  $(C_d)$  -Analysis Procedure -
- Load Combinations:
- 8. Building Code • 2018 International Building Code
- ASCE 7-16

TYPICAL STRUCTURAL ABBREVIATIONS

ACI	AMERICAN CONCRETE INSTITUTE
AISC	AMERICAN INSTITUTE OF STEEL CONSTRUCTION
ARCH	ARCHITECT
ASTM	AMERICAN SOCIETY FOR TESTING AND MATERIALS
BLDG	BUILDING
BM	BEAM
BOTT	BOTTOM
BRG	BEARING
CLR	CLEAR
COL.	COLUMN
CONC	CONCRETE
CONN	CONNECTION
CONT	CONTINUOUS
DIA, or $\Phi$	DIAMETER
DIM	DIMENSION
DN	DOWN
do	DITTO
DTL	DETAIL
DWG	DRAWING
E.F.	EACH FACE
E.M.	EACH WAY
EA	EACH
EL	ELEVATION
EQ	EQUAL
EXIST	EXISTING
EXP	EXPANSION
F.S.	FAR SIDE

FOUNDATION

ANCHOR ROD

FIN	FINISH	PSF
FLR	FLOOR	PSI
FTG	FOOTING	R
GA	GAUGE	REI
GALV	GALVANIZED	REC
H.S.A.	HEADED STUD ANCHOR	RTL
НK	HOOK	S.0
HORIZ	HORIZONTAL	SCH
J.B.E.	JOIST BEARING ELEVATION	SEC
JST	JOIST	SEC
TL	JOINT	
L	ANGLE	SIM
LG	LONG	SJI
LLH	LONG LEG HORIZONTAL	SPA
LLV	LONG LEG VERTICAL	SPE
LONG	LONGITUDINAL	STE
MAX	MAXIMUM	STI
MBM	METAL BUILDING	STL
	MANUFACTURER	TOC
MECH	MECHANICAL	TOF
MFR	MANUFACTURER	TOS
MIN	MINIMUM	TOP
MISC	MISCELLANEOUS	TR/
MTL	METAL	TYF
N.S.	NEAR SIDE	U.N.
0.C.	ON CENTER	VEF
0.F.	OUTSIDE FACE	M
OPNG	OPENING	MP
PED	PEDESTAL	NM
PLF	POUNDS PER FOOT	Ł
PROJ	PROJECTION	₽ с

4 I C	NS
SF	POUNDS PER SQUARE FOO
5I	POUNDS PER SQUARE INCH
	RADIUS
EINF	REINFORCEMENT
EQ'D	REQUIRED
TU	ROOF TOP UNIT
.O.G.	SLAB ON GRADE
CHED	SCHEDULE
ECT	SECTION
EOR	STRUCTURAL ENGINEER OF RECORD
IM	SIMILAR
L	STEEL JOIST INSTITUTE
PA	SPACING
PECS	SPECIFICATIONS
TD	STANDARD
TIFF	STIFFENER
TL	STEEL
00	TOP OF CONCRETE
OF	TOP OF FOOTING
05	TOP OF STEEL
OM	TOP OF WALL
RANS	TRANSVERSE
YP	TYPICAL
N.O.	UNLESS NOTED OTHERWISE
ERT	VERTICAL
V	MITH
P	WORK POINT
IMF	WELDED WIRE FABRIC
	CENTER LINE
or PL	PLATE

Purlins & girts shall be cold-formed structural steel sections with stiffened flanges and have a minimum 55,000 psi yield

Bottom of base plate elevation for all pre-engineered building columns shall be at elevation 100'-0", unless otherwise noted.

panel, clay brick veneer, concrete masonry, or other brittle materials shall be designed for a maximum wind load horizontal

Per MBM

3 psf


20 psf


10 psf

114 mph 88.3 mph

Per MBM Per MBM Per MBM Per MBM

Per MBM






З

NOT TO SCALE

METAL	METAL BLDG. ANCHOR ROD SCHEDULE						
R <i>OD</i> DIAMETER	EMBEDMENT LENGTH "E"	THREAD PROJ. "B"	REMARKS				
1 1/4"	2'-0"	4"					
1"	1'-6"	4"					
7/8"	1'-6"	З"					
3/4"	1'-4"	З"					
5/8"	1'-4"	З"					
1/2"	1'-8"	2"					




NOTE


1/8" x 1 1/2" DEEP ---FACTORY MADE WIRE BAR SUPPORTS -----

AT JOINT -

10 MIL POLYETHYLENE-



Δ S




		P	EDESTA			
MARK	PEDEST	AL SIZE	VERTICAL			
MARK	MIDTH	LENGTH	DOWELS			
<b>P</b> 1	1'-4"	2-0"	(8) #5 DOWELS			
P2	2'-0"	2-0"	(10) #5 DOWELS			
PEDESTAL SCHEDULE NOTES: 1. SEE FOUNDATION PLAN FOR LOCATION AND ORIE						

FOOTING S							
MARK	F	FOOTING SIZE					
	В	L	t				
F1	4'-0"	4'-0"	1'-4"				
F2	5'-0"	5'-0"	1'-4"				
F3	7'-0"	7'-0"	2'-0"				

- REVISIONS MAY BE REQUIRED FOLLOWING RECEIPT AND REVIEW OF FINAL SEALED MBM FOUNDATION REACTIONS.


FOUNDATION DESIGN HEREIN IS BASED UPON ANTICIPATED METAL BUILDING REACTIONS AS DEVELOPED BY TATUM SMITH WELCHER ENGINEERS, INC. IN CONSIDERATION OF THE PLANNED BUILDING TYPE (GABLED, CLEAR SPAN & "POLE BARN"), BAY SPACING AND SPAN. THE GENERAL CONTRACTOR SHALL FURNISH FOUNDATION REACTIONS SEALED BY A STRUCTURAL ENGINEER LICENSED IN THE STATE OF SOUTH CAROLINA TO TATUM SMITH WELCHER ENGINEERS, INC. FOR REVIEW. CONTRACTOR SHALL ALLOW FOR A MINIMUM REVIEW TIME OF TEN (10) BUSINESS DAYS IN THEIR CONSTRUCTION SCHEDULE

SPREAD FOUNDATION SIZES SHOWN ARE FOR BIDDING PURPOSES ONLY.







TSW #: 20052 PM: BCC DE: TPG













OPTIONAL CONST. JT.












GINAL SHEET SIZE 36 x 24 / DO NOT SCALE DRAWING

2020 THE HILL FIRM - ARCHITECT, ALL RIGHTS RESERVED



© 2020 THE HILL FIRM - ARCHITECT.



Greg Anderson, Engineer

9 WEST 26th CIRCLE Fayetteville, AR 72701 PHONE: 479-601-3331 EMAIL: ga@gaengr.com PROJECT # 20006

#### **DRAIN PLAN KEYED NOTES** ① COORDINATE CONDENSATE DRAIN REQUIREMENTS WITH HVAC CONTRACTOR. 2 RIPE NEW F&R RELIER TO JAN SINK. 3 3 4" DRAIN LINE TO SEPTIC SYSTEM. SEE CIVIL SITE UTILITY PLAN. 4 2" HUB DRAIN ABOVE CEILING FOR COOLING AND HEATING CONDENSATE DRAINS. COORDINATE WITH CIVIL ENGINEER, MC, AND AHJ. (5) 2" CONDENSATE DRAIN SYSTEM BELOW SLAB. RUN OUT TO STORM DRAIN INLET. COORDINATE WITH CIVIL ENGINEER, MC, AND AHJ. PLUMBING LEGEND NEW BUILDING DRAIN COLD / DOMESTIC WATER SUPPLY (CW) BUILDING SEWER HOT WATER SUPPLY VENT (HW) VENT THRU ROOF (VTR) FIRE LINE ----FL----FIRE DEPARTMENT PRESSURE REDUCING <---FDC---CONNECTION LINE VALVE (PRV) $-\bowtie$ CLEANOUT TO GRADE (COTG)/ TEMPERATURE & PRESSURE (T&P) RELIEF VALVE TWO WAY CLEANOUT $\bigcirc$ (TWCO/ FLOOR CLEANOUT FROST PROOF HOSE BIBB (FPHB) (FCO) FLOOR DRAIN (FD) WALL CLEANOUT FLOOR SINK (FS) $\bigcirc$ (WCO)/ SAFE WASTE DRÁIN STACK CLEANOUT (SWD) 1 (SCO)/ ÈND OF STRAIGHT UTILITY BOX (UB) LINE CLEANOUT (CO) SUPPLY BOX (SB) UNION PIPE TURNING DOWN ——) LINE CAP \_\_\_\_\_ TEE UP -0-GATE VALVE TEE DOWN $\mathbf{r}$ "Y" STRAINER —)— DROP AND RUN REDUCE PRESSURE PRINCIPLE BACKFLOW DR DRAIN PREVENTER (RPZ) TEE OFF BOTTOM R REGULATOR DROP AND TURN TEE OFF TOP PIPE TURNING UP ———

## SUPPLY PLAN KEYED NOTES

- 1 -1/4" CW SERVICE TO BUILDING FROM CITY MAIN.
- 2 3/4" CW, 3/4" HW PIPING DOWN TO CONNECTION AT WATER HEATER.
- (3) ACCESSIBLE SHUT OFF VALVE.
- (4) 3/4" CW TO HOSE BIBB. PROVIDE ACCESSIBLE SHUT OFF VALVE ABOVE CEILING.
- (5) 1" MPG TO METER. COORD WITH CIVIL ENGINEER AND GAS COMPANY.
- 6 3/4" DW TO RUN AND DRIVE BUILDING HOSE BIBBS.
- PROPANE GAS SERVICE TO STORAGE TANK. COORDINATE CONNECTION LOCATION, TANK LOCATION AND PIPE SIZE WITH CIVIL ENGINEER AND GAS PROVIDER.

Image: Solution       Pare       Comments         Image: Solution       Solution       Image: Solution       Solution       Image: Solution       Solution         Image: Solution       Image: Solution       Image: Solution       Image: Solution       Solution       Solution       Solution         Image: Solution       Image: Solution       Image: Solution       Image: Solution       Solution       Solution       Solution         Image: Solution       Image: Solution       Image: Solution       Image: Solution       Image: Solution       Image: Solution       Image: Solution         Image: Solution       Image: Solution       Image: Solution       Image: Solution       Image: Solution       Image: Solution       Image: Solution         Image: Solution       Image: Solution       Image: Solution       Image: Solution       Image: Solution       Image: Solution         Image: Solution       Image: Solution       Image: Solution       Image: Solution       Image: Solution       Image: Solution         Image: Solution       Image: Solution       Image: Solution       Image: Solution       Image: Solution       Image: Solution         Image: Solution       Image: Solution       Image: Solution       Image: Solution       Image: Solution       Image: Solution         Image: Solution							5003 OLD GREENWOOD RD, SUITE D - FT SMITH, AR 72903 DH: 479 494 1808 - WWW HILL FIRM NET	
Insurance Auto Auction, Inc.       #         TBD       TBD         TBD       TBD         Lexington, South Carolina 29073       3         FEMIT - CONSTRUCTION DOCUMENTS       1	COMMENTS	CIVIL AND PLAN MODIFICA	ADD SECURITY CAMERAS					
Insurance Auto Auction, Inc. TBD Lexington, South Carolina 29073 FEMIT - CONSTRUCTION DOCUMENTS		08/11/20	09/02/20	11/04/20				
Insurance Auto Auc TBD Lexington, South Carolina 2 ERMIT - CONSTRUCTION							C	2
(A) $(AD a'')/(A)$	-			D	n Carolina 29073			JULION DOCUMEN
		Solution Incurance Auto				1///// PO		
PLUMBING PLANS           DATE:         JOB NO.           05/13/20         2020-09						NS BNO		

## GENERAL PLUMBING NOTES

\*GENERAL PLUMBING NOTES PERTAIN TO ALL PLUMBING SHEETS.

1. ALL WORK SHALL COMPLY WITH APPLICABLE PLUMBING CODES. REQUIREMENTS OF THE STATE HEALTH DEPARTMENT AND LOCAL ORDIN

2. PLUMBING SUPPLY AND DRAIN PLANS ARE DIAGRAMMATICAL IN NATURE. REGARDLESS OF HOW SHOWN ON THE PLANS, CONTRACTOR SH ALL PIPING IN A CONCEALED LOCATION UNLESS OTHERWISE DIRECTED. THE FINAL LAYOUT SHALL BE GOVERNED BY ACTUAL FIELD COND MEASUREMENTS VERIFIED AT THE SITE AND COORDINATED WITH OTHER TRADES. DURING CONSTRUCTION, ANY CONFLICT BETWEEN ARCHITECTS AND THE CONTRACTORS INTERPRETATION OF PLUMBING PLANS SHALL BE RESOLVED SO AS TO MAINTAIN THE ARCHITECTS AESTHETIC EXPECTATION PROJECT.

3. INSTALL WATER HAMMER ARRESTOR AT END OF EACH BRANCH ON HOT AND COLD WATER PIPING, EACH BATTERY OF WATER CLOSETS, AT HEATER, AND AT OTHER PLACES AS PER MANUFACTURER'S SIZING GUIDE.

4. WHETHER SHOWN OR NOT ON THESE PLANS, INSTALL ISOLATION VALVES IN EVERY SUPPLY FIXTURE BANK OR GROUP AND AT ALL HOT BRANCHES. PROVIDE ACCESS PANEL EQUAL TO ACCUDOR MODEL FW5050 WHERE REQUIRED TO ALLOW ADEQUATE ACCESS TO VALVES. SHALL NOT INSTALL ANY MAINTENANCE ITEMS ABOVE HARD CEILINGS UNLESS ACCESS IS PROVIDED. THIS SHALL INCLUDE VALVES, TRAP VALVES AND ANY OTHER ITEMS THAT REQUIRE ACCESS AFTER CONSTRUCTION IS COMPLETED.

5. AT FREEZE PROOF HOSE BIBBS, PIPING TO AND AROUND VALVE PORTION OF HOSE BIBBS SHALL BE INSIDE THE INSULATION. SEAL AIR SHEATHING PENETRATION.

6. FOR HANDICAPPED WATER CLOSETS, FLUSH CONTROLS SHALL BE MOUNTED ON THE OPEN SIDE OF TOILET AREAS. CENTERLINE OF HANDI CLOSET SHALL BE 18" FROM NEAREST FINISHED WALL OR PARTITION.

7. ALL PIPING SHALL BE ANCHORED AND SUPPORTED PER STANDARD INDUSTRY PRACTICE AND PER MANUFACTURER'S RECOMMENDATIONS.

8. FLOOR DRAINS ON THIS PROJECT ARE THE SAME SIZE AS THE DRAIN LINE TO WHICH THEY ARE CONNECTED UNLESS OTHERWISE NOTED LINES ARE NOT MARKED, THE MINIMUM SIZE PER SPECIFICATION IS 2". ALSO THE SMALLEST DRAIN LINE THAT IS ALLOWED BY COD BELOW SLAB IS 2". FOR INDIVIDUAL DRAIN LINES NOT SIZED ON PLANS, REFER TO PLUMBING ROUGH-IN MOUNTING HEIGHT SCHEDULE. A 4" AS INDICATED ON PLANS, SHALL BE PROVIDED AT ALL RPZ'S 3" AND BELOW. A 6" DRAIN SHALL BE PROVIDED AT ALL RPZ'S OVER 3".

9. VENT THROUGH ROOF (VTR) SHALL NOT BE LOCATED WITHIN 10' OF A FRESH AIR INTAKE OR IN LOW SPOTS OF VALLEYS. COMBINE AS POSSIBLE TO MINIMIZE THE QUANTITY OF VTR'S. LOCATE VTR'S ON THE BACK SIDE OF THE BUILDING WHERE POSSIBLE. CONTRACTOR AS REQUIRED TO MEET THESE REQUIREMENTS.

10. OUTSIDE OF FOOTING, MAINTAIN 10' BETWEEN SEWER AND DOMESTIC WATER LINES UNLESS WRITTEN PERMISSION IS OBTAINED FROM LOCA ADMINISTRATIVE AUTHORITY.

11. CONTRACTOR TO REVIEW ALL PLAN SHEETS FOR FIXTURE TAGS. MOST FIXTURE TAGS ARE LOCATED ON THE FIRST PLAN SHEET. FIXTURES APPEAR ON THE FIRST SHEET WILL BE TAGGED ON OTHER SHEETS.


12. ALL ABOVE GROUND WATER LINES SHALL BE COPPER OR PEX. ALL UNDERGROUND SANITARY SEWER SERVICE PIPING SHALL BE SCHEDUL ABOVE GROUND INDOOR PIPING SHALL BE PVC OR CELL CORE.

- 13. THIS NOTE DELETED
- 14. INSULATE TUB AND WATER CLOSET WASTE LINES FROM 2nd FLOOR WITH R-38 BATT INSULATION. TYP.
- 15. COORDINATE LOCATION OF SANITARY STACKS WITH STRUCTURE. NO OFFSETS SHALL BE INSTALLED IN THE SANITARY STACK VENTS.
- 16. MIRROR PLUMBING PLAN FOR OTHER SIDE OF BUILDING.

17. INSTALL APPROVED TRAP GUARD THAT CONFORMS TO NSF-14, CSA, B602-94 AND CSA B79-94. INSTALL IN ALL FLOOR DRAINS, HUB FLOOR SINKS.

18. PROVIDE FIRE RATED COVER AT CLEANOUTS THAT OCCUR IN FIRE RATED WALLS.

19. PROVIDE FIRE RATED UB-1 AND SB-1 WHEN INSTALLED IN A FIRE RATED WALL.




 $\square$ 20 0

L INSTALL IONS WITH ALL	MARK	DESCRIPTION	MFGR/	TRIM	COMMENTS	ELECTRICAL	
INTENT OF THE	HWC-1	HANDICAPPED WATER CLOSET FLUSH TANK	CADET IV 17"HIGH	D ELONGATED RIM, ROUGH-IN PER MFG.'S SPECIFICATIONS.	VITREOUS CHINA. PROVIDE COMMERCIAL SEAT INSTALL FLUSH	REQUIREMENTS	
CH WATER		FLOOR MNTD. FLOOR OUT	1.6 GAL. FLUSH		HANDLE TO THE OPEN AREA OF THE ROOM.		
ER RETURN TRACTOR PRIMER	WC-1	WATER CLOSET FLUSH TANK FLOOR MNTD. FLOOR OUT	AMERICAN STANDARE CADET IV STD HEIGHT 1.6 GAL. FLUSH	) ELONGATED RIM, ROUGH-IN PER MFG.'S SPECIFICATIONS. 3517C BOWL 4188 TANK	VITREOUS CHINA. PROVIDE COMMERCIAL SEAT		
IT AT	HL-1	HANDICAP LAVATORY COUNTER MOUNTED 19"x15" 4" HOLES O.C.	AMERICAN STANDARD OVAL LAV.	64920 1–1/4" O.D. TAILPIECE,	804–1180 CAST BRASS 1–1/4 x 1–1/4 ADJUSTABLE "P" TRAP W/ CLEANOUT & SLIP		
PPED WATER		VITREOUS CHINA		802–0950 3/8" ANGLE STOP I.P.S CONNECTION.	JOINT INLET.		
F DRAIN TO BE RAIN,	HL-2	LAVATORY WALL MTD 20 1/2x18 1/4 VITREOUS CHINA ADA	AMERICAN STD LUCERNE 0355.012	AMERICAN STANDARD RELIANT 3, 7385.004 SINGLE LEVER FAUCET HANDLE LESS DRAIN & POPUP. McGUIRE 155WC OFFSET CHROME PLATED CAST BRASS GRID DRAIN. SEAMLESS BRASS TAILPIECE W/	JR SMITH 0700 INSULATION EQUAL TO TRUEBRO LAV—GUARD PVC TYPE INSULATION		AE
IS AS MUCH TO OFFSET	HUR-1	FLUSH VALVE WALL MNT'D VITREOUS CHINA		CAST BRASS LOCKNUT. INTEGRAL FLUSHING RIM, 3/4" TOP SPUD 2" FEMALE FLANGED OUTLET CONNECTION. PROVIDE SLOAN 186-1.	PROVIDE J. R. SMITH 637 W/ HANGER PLATE AND LOWER BEARING PLATE		1U )
IAT DO NOT IO PVC.	EWH-1		LOCHINVAR JRC010DS	TROVIDE SECAN TOO-T.	PROVIDE CATCH PAN	120V, 1650W SINGLE PHASE	
	ET-1	EXPANSION TANK,	AMTROL AST–5	BACKFLOW PREVENTER	MOUNT ON WALL ALLOW AMPLE ROOM FOR MAINTENANCE.		1U ИI 1U
RAINS, AND	CP-1	CIRCULATING PUMP 120°F,1/12HP,24LBS	AMTROL CIRCULATING PUMP RBW2		TEMP CONTROL KIT 120–ATC. 3/4" SIZE	120V, 1/12 HP PROVIDE CORD AND PLUG.	SE IN OI
	SB-1	SUPPLY BOX	GUY – GRAY BIM– 875	1/2" FIP SUPPLY			SI
	S-1	SELF RIMMING SINGLE COMP. STAINLESS STEEL SINK.	ELKAY LUSTERTONE LR-1720	SINGLE LEVER W/ GOOSE NECK SWIVEL FAUCET LK-4122, 3-1/2" OPENING DRAIN. McGUIRE 151M	PROVIDE TWO FAUCET HOLES ON DECK.		S <sup>-</sup>
		OVERALL 17x20 INSIDE COMP. 14x14x7-1/2		HEAVY DUTY BRASS BASKET & STRAINER, 1 1/2", CHROME PLATED TAILPIECE. McGUIRE 8912 1 1/2" x 1 1/2" HEAVY DUTY CHROME PLATED CAST BRASS P-TRAP W/ CLEANOUST PLUG.	McGUIRE 170LK CHROME PLA SOLID BRASS ANGLE STOPS W/ 5" CHROME PLATED COPPER EXTENSION TUBE & LOOSE KEYS. FLEXIBLE CHROME PLATED COPPER RISERS		ST UI
	JS-1	FLOOR MNT'D	FIAT PRECAST TER– RAZZO FLOOR SINK TSB–200	ELJER 749–1450 SINK FAUCET W/ 8–7/16" SPOUT, 5' RUBBER HOSE, ZINC LEVER HANDLES,	W/ VACUUM BREAKER, INTEGRAL STOPS. PROVIDE TILING FLANGE WHERE REQUIRED PROVIDE CHECK VALVES ON HOT AND COLD WATER.		PL
	RPZ-1		WATTS LF909	1" RPZ W/ WATTS BALL VALVES, "Y" STRAINER	PROVIDE 4" DRAIN FOR 3" AND SMALLER AND 6" DRAIN FOR LARGER THAN 3".		F
	PRV-1		WATTS 223	1" ALL BRONZE FOR POTABLE WATER TO			(F
	FD-1		J. R. SMITH	70 PSIG SETTING	SEE PLANS AND/OR GENERAL		(F
			2005	GUARD INSERT. PROVIDES SEAL TO PREVENT TRAP FROM DRYING OUT.	PLUMBING NOTES FOR SIZES		LA SM JA
	HEWC-1	STANDARD HEIGHT. ELECT. WATER COOLER. CIRCULAR, STAINLESS STEEL, LEAD FREE. BI-LEVEL, WALL SURFACE MTD		HEAVY-GAUGE GALVANIZED STEEL WALL MOUNTING FRAME. 8 GALLONS PER HOUR. FLEXIBLE SAFETY BUBBLER LIGHT GRAY GRANITE VINYL C STEEL.		1PH, 380 WATTS. 1/5 HP, 4.5 FLA.,	
<u> </u>	HB-1	COOLING UNIT. HOSE BIBB. MILD CLIMATE SILLCOCH WHEEL HANDLE 3/4" HOSE. STAINLESS STEEL BOX W/ 180° COVER OPENING.		PUSHBARS FRONT AND SIDES WALL HYDRANT W/ INTEGRAL VACUUM BREAKER, ACCESSIBLE SHUT OFF VALVE AT TOP OF WALL	S PROVIDE W/ KEYED LOCK ON DOOR AND RECESSED BOX.		BA SH VA
	FPHB-1			WALL HYDRANT W/ INTEGRAL VACUUM BREAKER, STAINLESS STEEL BOX W/ KEYED LOCK AND KEYED VALVE	PROVIDE W/ KEYED LOCK ON DOOR AND KEYED VALVE. PROVIDE ACCESSIBLE ISOLATION VALVE ON SUPPLY PIPE.		
	FCO-1	FLOOR CLEAN OUT FOR CONCRETE	SMITH 4100	CAST IRON ADJUSTABLE CLEAN OUT W/ SATIN BRONZE COVER	SEE PLAN FOR SIZES.		
	TWCO-7	1 TWO WAY CLEANOUT TO GRADE SET IN CONCRETE SPEEDI SET DESIGN. NON TILT TRACTOR COVER	J. R. SMITH 4237	W/ SATIN BRONZE COVER DUCO CAST IRON BODY, ROUND ADJUSTABLE SCORIATED CAST IRON TOP. TAPERED THREAD BRONZE PLUG.	SEE PLAN FOR SIZES.		DC GF
		THERMOSTATIC MIXING					W





**Greg Anderson, Engineer** 9 WEST 26th CIRCLE


PIPING	MATERIAL	S SCHEDULE		F	
SERVICE		MATERIAL			
ABOVE GROUND DOMESTIC WATER	BY CODE. TYPE L HARD (	SS LINKED POLYETHYLENE (PEX) W COPPER WITH WROUGHT COPPER F EE SOLDER ONLY WHERE REQUIRE	TITTINGS AND	δ	
UNDERGROUND WATER OUTSIDE	IN 4" PVC SCH 1" AND SMALLE OR FITTINGS UI MAKE CONNECT FITTINGS AND L	SS LINKED POLYETHYLENE (PEX) S IED 40 PIPE WHERE ALLOWED BY ER: ASTM B88 TYPE L SOFT COPP NDER SLAB. IONS ABOVE SLAB WITH WROUGHT EAD FREE SOLDER . ARGER: ASTM B88 TYPE L HARD ( SS MAKE JOINTS WITH SIL—FOS (15)	CODE. ER NO JOINTS COPPER	DESCRIPTION	
UNDERGROUND WATER INSIDE	IN 4" PVC SCH	SS LINKED POLYETHYLENE (PEX) S HED 40 PIPE. TED PEX EQUAL TO FOSTAPEX WH		DATE	
UNDERGROUND SANITARY SEWER AND VENT PIPING INSIDE BLDG AND OUTSIDE BLDG	PVC SCHEDULE	40 PIPE AND FITTINGS.		+ -	
ABOVE GROUND SANITARY SEWER AND VENT	AREAS.	40 PIPE AND FITTINGS EXCEPT IN E WHERE ALLOWED.	N PLENUM RETURN	J U	VTS
STORM DRAIN PIPING, ROOF DRAIN PIPING ABOVE GROUND	STANDARD WEIG AND JOINTS OF COUPLINGS.	HT CAST IRON "NO-HUB" PIPE AN STANDARD WEIGHT STAINLESS STE	ND FITTINGS, EEL / NEOPRENE	Ē	2003 DOCUMENTS
STORM DRAIN PIPING UNDER GROUND		PVC PIPE AND FITTINGS		) Ľ	29073
PLUMBINGROUFIXTUREWASTEWATER CLOSETS (FLUSH TANK)3"URINALS (FLUSH VALVE)2"LAVATORIES & SMALL SINKS1-1/2"JANITOR'S SINKS3"HOSE BIBBUTILITY BOX2"SUPPLY BOXHUB DRAIN1-1/2"	- VENT COLD	MOUNTING H HOT INSTALLATION WATER HEIGHT STANDARD 15" TO TOF HANDICAPPED 17" TO STANDARD 22" TO TOF HANDICAPPED 17" TO 44" MAX. TO FLUSH L 1/2" STANDARD 31" TO TOF HANDICAPPED 34" TO 1/2" 18" ABOVE GRADE OUTSIDE 1/2" 42" TO BOTTOM OF BE 42" TO BOTTOM OF BE	ON OF SEAT TOP OF SEAT OF RIM TOP OF RIM EVER OF RIM TOP OF RIM E, 18" A.F.F. INSIDE OX.	Insurance Auto Au	ERMIT - CONSTRUCTIO
FIXTUREWASTEWATER CLOSETS (FLUSH TANK)3"URINALS (FLUSH VALVE)2"LAVATORIES & SMALL SINKS1-1/2"JANITOR'S SINKS3"HOSE BIBBUTILITY BOX2"SUPPLY BOXHUB DRAIN1-1/2"BATHTUB2"	VENTCOLD WATER $2"$ $1/2"$ $1-1/2"$ $3/4"$ $1-1/4"$ $1/2"$ $1-1/2"$ $1/2"$ $1-1/2"$ $1/2"$ $1-1/2"$ $1/2"$ $1-1/2"$ $1/2"$ $1-1/2"$ $1/2"$ $1-1/4"$ $$ $2"$ $1/2"$	HOT INSTALLATION WATER HEIGHT STANDARD 15" TO TOF HANDICAPPED 17" TO 44" MAX. TO FLUSH L 1/2" STANDARD 31" TO TOF HANDICAPPED 34" TO 1/2" 18" ABOVE GRADE OUTSIDE 1/2" 42" TO BOTTOM OF BE 42" TO BOTTOM OF BE 	ON OF SEAT TOP OF SEAT OF RIM TOP OF RIM EVER OF RIM TOP OF RIM E, 18" A.F.F. INSIDE OX. OX.	Insurance Au	PERMIT - CONSTRUC
FIXTUREWASTEWATER CLOSETS3"(FLUSH TANK)2"URINALS2"(FLUSH VALVE)1-1/2"LAVATORIES &1-1/2"SMALL SINKS3"HOSE BIBBUTILITY BOX2"SUPPLY BOXHUB DRAIN1-1/2"BATHTUB2"SHOWER MIXING	VENT       COLD WATER         2" $1/2$ " $1-1/2$ " $3/4$ " $1-1/4$ " $1/2$ " $1-1/2$ " $1/2$ " $1-1/2$ " $1/2$ " $1-1/2$ " $1/2$ " $1-1/2$ " $1/2$ " $$ $3/4$ " $1-1/2$ " $1/2$ " $$ $1/2$ " $1-1/2$ " $1/2$ " $$ $1/2$ " $1-1/4$ " $$	HOT INSTALLATION WATER HEIGHT STANDARD 15" TO TOP HANDICAPPED 17" TO STANDARD 22" TO TOP HANDICAPPED 17" TO 44" MAX. TO FLUSH L 1/2" STANDARD 31" TO TOP HANDICAPPED 34" TO 1/2" 18" ABOVE GRADE OUTSIDE 1/2" 42" TO BOTTOM OF BE 42" TO BOTTOM OF BE	ON OF SEAT TOP OF SEAT OF RIM TOP OF RIM EVER OF RIM TOP OF RIM E, 18" A.F.F. INSIDE OX. OX. OX. ENTERLINE OF HEAD	Insurance Au	PERMIT - CONSTRUC
FIXTUREWASTEWATER CLOSETS3"(FLUSH TANK)2"URINALS2"(FLUSH VALVE)2"	VENT       COLD WATER         2" $1/2$ " $1-1/2$ " $3/4$ " $1-1/4$ " $1/2$ " $1-1/2$ " $1/2$ " $1-1/2$ " $1/2$ " $1-1/2$ " $1/2$ " $1-1/2$ " $1/2$ " $1-1/2$ " $1/2$ " $1-1/2$ " $1/2$ " $1-1/4$ " $$ $2$ " $1/2$ " $1-1/4$ " $$ $2$ " $1/2$ " $1-1/2$ " $1/2$ " $1-1/2$ " $1/2$ "	HOT INSTALLATION WATER HEIGHT STANDARD 15" TO TOP HANDICAPPED 17" TO STANDARD 22" TO TOP HANDICAPPED 17" TO 44" MAX. TO FLUSH L 1/2" STANDARD 31" TO TOP HANDICAPPED 34" TO 1/2" 18" ABOVE GRADE OUTSIDE 1/2" 42" TO BOTTOM OF BE 42" TO BOTTOM OF BE 1/2" 1/2" SHOWER HEAD 72" TO CE MIXING VALVE HANDLE	ON OF SEAT TOP OF SEAT OF RIM TOP OF RIM EVER OF RIM TOP OF RIM E, 18" A.F.F. INSIDE OX. OX. OX. ENTERLINE OF HEAD AT 48" A.F.F.	Insurance Au	Lexington, South C PERMIT - CONSTRUC
FIXTURE       WASTE         WATER CLOSETS       3"         (FLUSH TANK)       2"         URINALS       2"         (FLUSH VALVE)       2"         LAVATORIES &       1-1/2"         MALL SINKS       3"         HOSE BIBB          UTILITY BOX       2"         SUPPLY BOX          HUB DRAIN       1-1/2"         BATHTUB       2"         SHOWER MIXING          NOTES:       VENT SIZES SHOWN ARE N         SIZES SHOWN FOR WASTE       BE 2" OR LARGER.         PLUMBING          DESCRIPTION       DESCRIPTION         DOMESTIC COLD AND HOT WATER PIF       DESCRIPTION	VENT       COLD WATER         2"       1/2"         1-1/2"       3/4"         1-1/2"       1/2"         1       1/2"         1	HOT INSTALLATION WATER HEIGHT STANDARD 15" TO TOF HANDICAPPED 17" TO 44" MAX. TO FLUSH L 1/2" STANDARD 31" TO TOF HANDICAPPED 34" TO 1/2" 18" ABOVE GRADE OUTSIDE 1/2" 42" TO BOTTOM OF BE 42" TO BOTTOM OF BE 12" 1/2" 1/2" SHOWER HEAD 72" TO CE MIXING VALVE HANDLE (STANDARD AND ADA) LARGER ON RISER DIAGRAMS. ALL DRAIN AND VENT LINES BEL INSULATION TYPE ELASTOMERIC	ON OF SEAT TOP OF SEAT OF RIM TOP OF RIM EVER OF RIM TOP OF RIM E, 18" A.F.F. INSIDE OX. OX. OX. ENTERLINE OF HEAD AT 48" A.F.F. LOW SLAB SHALL	PLUMBING	C A ROL South C 2/13/50 C AND C AND
FIXTURE       WASTE         WATER CLOSETS (FLUSH TANK)       3"         URINALS (FLUSH VALVE)       2"         LAVATORIES & MALL SINKS       1-1/2"         JANITOR'S SINKS       3"         HOSE BIBB          UTILITY BOX       2"         SUPPLY BOX          HUB DRAIN       1-1/2"         BATHTUB       2"         SHOWER MIXING          NOTES:       VENT SIZES SHOWN ARE N SIZES SHOWN FOR WASTE BE 2" OR LARGER.         PLUMBINC	VENT       COLD WATER         2"       1/2"         1-1/2"       3/4"         1-1/4"       1/2"         1-1/2"       1/2"         1       -1/2"         1       -1/2"         1       -1/2"         1       -1/2"         1       -1/2"         1       -1/2"         1       -1/2"         1       -1/2"	HOTINSTALLATIOWATERHEIGHTSTANDARD 15" TO TOF HANDICAPPED 17" TO 44" MAX. TO FLUSH L1/2"STANDARD 22" TO TOF HANDICAPPED 17" TO 44" MAX. TO FLUSH L1/2"STANDARD 31" TO TOF HANDICAPPED 34" TO1/2"1/2"42" TO BOTTOM OF BU 9000000000000000000000000000000000000	ON OF SEAT TOP OF SEAT OF RIM TOP OF RIM EVER OF RIM TOP OF RIM E, 18" A.F.F. INSIDE OX. OX. OX. ENTERLINE OF HEAD AT 48" A.F.F. OW SLAB SHALL 	PLUMBING	C A RO S AND DETAIL C A RO S AND S TABS S AND DETAIL JOB NO.



















Greg Anderson, Engineer


9 WEST 26th CIRCLE Fayetteville, AR 72701 PHONE: 479-601-3331 EMAIL: ga@gaengr.com PROJECT # 20006

4 ľ

SHEET:

**P2.2** 

 $\circ$ 





Greg Anderson, Engineer


9 WEST 26th CIRCLE Fayetteville, AR 72701 PHONE: 479-601-3331 EMAIL: ga@gaengr.com PROJECT # 20006

						5003 OLD GREENWOOD RD, SUITE D - FT SMITH, AR 72903 PH: 479 494 1808 - WWW HILL FIRM NET	
COMMENTS	CIVIL AND PLAN MODIFICATIONS	ADD SECURITY CAMERAS ON SITE	PLUMBING COORDINATION	PLAN MODIFICATIONS			
DATE	08/11/20	09/02/20	11/04/20	02/05/21			
#	~	2	М	4			
	Insurance Auto Auction Inc		TBD	Eckington, South Carolina 29073	<b>D</b>		FERMIL - CONSTRUCTION DOCUMENTS
			G //////	<u>    </u>	AN!		
DAT C SHE	)5/1	3/2	20		B NC 2020		


## **KEYED NOTES**


- (1) EXHAUST DUCT OUT THRU WALL. PROVIDE FAN MFGR'S WALL CAP TO MATCH WALL TYPE.
- (2) ROUTE REFRIG PIPING FROM MAC TO ASSOCIATED MCU. PIPE COND DRAIN OUTSIDE TO GRASSY AREA AND TURN DOWN.
- $\odot$  provide fan MFGR'S wall vent to match wall type.
- (4) UNDERCUT DOOR 1" TO ALLOW RA FLOW WHEN CLOSED.
- 5 ROUTE CONDENSATE DRAIN TO JANITOR SINK OR NEARBY HUB DRAIN ABOVE CEILING IF ALLOWED BY AHJ. COORDINATE HUB DRAIN LOCATIONS WITH PLUMBING CONTRACTOR. IF CONDENSATE DRAINS ARE NOT ALLOWED TO GO TO SANITARY SEWER RUN DRAINS OUT TO GRASSY AREA AND TURN DOWN.
- 6 1 HOUR FIRE RATED UPPER CEILING. PROVIDE 1 HR FIRE DAMPER IN SLEEVE AT UPPER CEILING FIRE RATED ASSEMBLY PER AHJ REQUIREMENTS. SEE DETAIL B/M 2.01

MECHA	NICA	L LEGENE	)
DUCT (1ST FIGURE, SIDE SHOWN: 2ND FIGURE, SIDE NOT	20×12	VOLUME DAMPER MANUAL OPERATION	
SHOWN)		TURNING VANES	
DUCT RISER 1ST DIMENSION SIDE POINTED TO	_30×20	COOLING CONDENSATE DRAIN	— C —
MECHANICAL EQUIPMENT		TRANSITION FROM SQUARE TO ROUND	
CEILING DIFFUSER	MARK CFM	THERMOSTAT MOUNT AT 48" AFF	T
RETURN GRILLE	MARK CFM	NEW	
EXHAUST GRILLE	MARK CFM	DOWNWARD SLOPE	
DUCT SECTION (SUPPLY)	$\square$	DUCT MOUNTED SMOKE DETECTOR	Ô
DUCT SECTION (RETURN)		AIR FLOW ARROW	_/
DUCT SECTION (EXHAUST)	$\square$	1 HOUR FIRE DAMPER	1FD











DRAIN PAN TRAP NTS








Greg Anderson, Engineer 9 WEST 26th CIRCLE Fayetteville, AR 72701 PHONE: 479-601-3331 EMAIL: ga@gaengr.com PROJECT # 20006

## GENERAL NOTES

- 1. SUBMISSION OF PROPOSAL IN CONNECTION WITH THIS WORK SHALL IMPLY THAT THE BIDDER HAS EXAMINED THE JOB SITE UNDER WHICH HE WILL BE OBLIGATED TO OPERATE SHOULD HE BE AWARDED THE WORK UNDER THIS CONTRACT. NO EXTRA CHARGE WILL BE ALLOWED FOR FAILURE OF ANY BIDDER TO EXAMINE THE SITE PRIOR TO BID.
- ALL WORK SHALL CONFORM TO STATE AND LOCAL CODES, RULES, REGULATIONS, AND ORDINANCES, ANY AND ALL OF WHICH SHALL TAKE PRECEDENCE OVER THE PLANS IF CONFLICTS EXIST BETWEEN THEM. COORDINATE ALL WORK WITH THE OWNER AND ALL - 3. OTHER CONTRACTORS. CONTRACTOR SHALL BE
- RESPONSIBLE FOR ALL RIGGING, HANDLING, AND PROTECTION OF MATERIALS. PROVIDE LABOR TO RECEIVE, UNLOAD, STORE, PROTECT AND TRANSFER TO POINT OF INSTALLATION OF ANY FURNISHED ITEMS.
- IN CASES OF EQUIPMENT SUBSTITUTION, CONTRACTOR IS RESPONSIBLE FOR VERIFYING THAT ALL SYSTEMS AND COMPONENTS WILL FIT PROPERLY PRIOR TO FABRICATION OR ORDERING. INSTALLED DUCTS MAY BE RESIZED BY THE CONTRACTOR TO FIT FIELD CONDITIONS. INSTALLED DUCTS SHALL HAVE EQUAL FRICTION LOSS TO THOSE SHOWN. RECTANGULAR DUCTS SHALL NOT BE CHANGED TO ROUND DUCTS. PROVIDE COMPLETE SHEET METAL SHOP DRAWINGS TO ENGINEER SHOWING ACTUAL DUCT SIZES, ARRANGEMENTS, AND UNIT LOCATIONS TO BE INSTALLED. THIS SHALL BE DONE PRIOR TO FABRICATION OR INSTALLATION.
- ALL DUCT SIZES SHOWN ARE THE METAL DIMENSIONS. ALLOWANCES HAVE BEEN MADE FOR THE LINER WHERE APPLICABLE IN THE RECTANGULAR DUCTS. AT DUAL WALL DUCTS, THE DIMENSION SHOWN IS THE OUTSIDE METAL DUCT SIZE.
- ALL DIMENSIONS AND SIZES IN INCHES UNLESS OTHERWISE NOTED.
- THE DRAWINGS INDICATE THE GENERAL LAYOUT 7. REQUIREMENTS FOR EQUIPMENT, FIXTURES, PIPING, DUCTWORK, ETC. FINAL LAYOUT SHALL BE GOVERNED BY ACTUAL FIELD CONDITIONS WITH ALL MEASUREMENTS VERIFIED AT THE SITE.
- THE CONTRACTOR SHALL PROVIDE A COMPLETE AND 8. OPERATING MECHANICAL SYSTEM, INCLUDING ALL INCIDENTAL ITEMS AND CONNECTIONS NECESSARY FOR PROPER OPERATION OR CUSTOMARILY INCLUDED, EVEN THOUGH EACH AND EVERY ITEM MAY NOT BE INDICATED.
- THE MECHANICAL INSTALLATION SHALL BE SAFE. RELIABLE, ENERGY EFFICIENT AND EASILY MAINTAINED WITH ADEQUATE PROVISIONS ALLOWED FOR ACCESS TO EQUIPMENT.
- 10. THE MECHANICAL SYSTEM SHALL OPERATE QUIETLY WITH NOISE LEVELS BELOW THE CRITERIA RECOMMENDED FOR THE APPLICATION BY ASHRAE. PROVIDE CORRECTIVE ACTION AS REQUIRED TO REDUCE OBJECTIONABLE NOISE OR VIBRATION.
- <sup>11.</sup> INSTALL REFRIGERANT PIPING FROM CONDENSING UNITS TO ASSOCIATED AIR HANDLERS. SIZE PER MANUFACTURER'S RECOMMENDATION.
- 12 USE ELBOW TAKE-OFF FITTINGS AT ALL ROUND SUPPLY BRANCH TAKE-OFFS.
- 13. USE FLEX DUCTS FROM TAKEOFF TO SUPPLY OUTLET AND LIMIT LENGTHS IF REQUIRED BY LOCAL CODE OR ORDINANCE
- 14. PROVIDE FIRE DAMPERS AT ALL FIRE-RATED WALLS AND FLOOR PENETRATIONS. REFER TO ARCHITECTURAL DRAWINGS FOR FIRE BARRIER LOCATIONS.
- 15. UNDERCUT DOORS 3/4 INCH WHERE NO RETURN IS PROVIDED IN AN ENCLOSED SPACE, EXCEPT AT FIREDOORS.
- 16. PROVIDE AN INSULATED BACK ON ALL THERMOSTATS. 17. COORDINATE ALL AIR DEVICES WITH CEILINGS AND
- CEILING ITEMS. 18. ROUTE DUCTWORK AS HIGH AS POSSIBLE IN CEILING
- SPACE. COORDINATE DUCTWORK WITH LIGHTS AND STRUCTURE. 19. CONTRACTOR SHALL NOT INSTALL ANY MAINTENANCE
- ITEMS ABOVE HARD CEILINGS. THIS SHALL INCLUDE VALVES, DAMPERS, OR ANY OTHER ITEMS THAT REQUIRE ACCESS AFTER CONSTRUCTION IS COMPLETED. IF INSTALLATION OF THESE ITEMS ABOVE A HARD CEILING CANNOT BE AVOIDED, THEN PROVIDE CEILING ACCESS DOORS EQUAL TO ACUDOR MODEL 5000 WHERE REQUIRED TO GAIN ACCESS TO EQUIPMENT, DAMPERS VALVES, CONTROL COMPONENTS, OR ANY OTHER DEVICE WHICH MAY REQUIRE ACCESS AFTER CONSTRUCTION IS COMPLETE. AT FIRE RATED WALLS, USE ACUDOR MODEL FW5050. MINIMUM SIZE SHALL BE 12"x12". USE
- 18"x18" WHEN PERSONNEL ACCESS IS REQUIRED. COORDINATE ALL DUCTWORK AND AIR DEVICES WITH 20. FIRE SPRINKLER CONTRACTOR PRIOR TO FABRICATION, PURCHASE, OR INSTALLATION.
- 21. AT ALL ABOVE CEILING FAN COIL UNITS, PROVIDE FLOAT SWITCH TO DE-ENGERGIZE SYSTEM IN THE EVENT OF CONDENSATE BACKUP. PROVIDE 3/4" PVC CONDENSATE DRAIN FROM FAN COIL UNITS TO HUB DRAIN AT WATER HEATER CLOSETS. CONFIRM WITH LOCAL AUTHORITY THAT DISCHARGE OF CONDENSATE DRAIN INTO SEWER SYSTEM IS ACCEPTABLE. IF NOT, DISCHARGE ALL CONDENSATE DRAINS INTO STORM DRAIN SYSTEM.
- PROVIDE LINT TRAPS AT ALL DRYERS.



- -ROOF STRUCTURE
- SMOKE DETECTOR (WHERE REQUIRED)-
  - -SUPPLY AIR DUCT PROVIDE SUPPORT AS REQUIRED COOLING COIL -GAS PIPE AS
  - REQUIRED - PRIMARY
  - CONDENSATE DRAIN

### VOLUME DAMPER MANUAL OPERATION TURNING VANES COOLING CONDENSATE TRANSITION FROM SQUARE TO ROUND (T)MOUNT AT 48" AFF DOWNWARD SLOPE $\longrightarrow$ DUCT MOUNTED $\bigcirc$ SMOKE DETECTOR AIR FLOW ARROW -√\--► HOUR FIRE DAMPER

	GAS INFRA F	RED H	HEATER S	SCHEI	DULE				ŀ	AIR D	EVICE S	SCH	EDULE		MECHANICAL INS	JLATION SCHEDL	JLE
MARK	DESCRIPTION MFGR/MODEL HEATING OUTPUT EFF		ECTRICAL PS MOCP V/A PHAS	CONTROL SE TYPE	ACCESSORIE	S		MARK	DESCRIPTION	MFGR., MODEL	SIZE	NECK*	MATERIAL, FINISH	COMMENTS	SERVICE	INSULATION TYPE	THICKNESS
IRH-1	INFRARED HEATER AMBI-RAD 80 MBH - MBH 80%			SHIELDED T-STAT	[	NIC IGNITION, F DRAFTER		CD-1	CEILING DIFFUSER LOUVER FACE	TITUS TDC	22x22 FACE 24x24 FRAME	6"	STEEL, WHITE	LAY-IN; UP TO 110 CFM	RESTROOM EXHAUST DUCTS, 1ST 10' FROM EXHAUST GRILLE	ACOUSTIC LINER	1"
	SEALED COMB. PROPANE				45 DEGREE 50' STAINLESS S	DISCHARGE AND STEEL HEAT EXC		CD-2	CEILING DIFFUSER LOUVER FACE	TITUS TDC	22x22 FACE 24x24 FRAME	8"	STEEL, WHITE	LAY-IN; UP TO 220 CFM	SINGLE WALL ROUND OR OVAL SUPPLY AIR DUCTS – LOW AND MEDIUM PRESSURE	DUCT WRAP	2"
								CD-3	CEILING DIFFUSER	TITUS TDCA	22x22 FACE 24x24 FRAME	10"	STEEL, WHITE	LAY-IN; UP TO 400 CFM	COPPER COOLING CONDENSATE DRAIN	ELASTOMERIC	3/8"
									LOUVER FACE ADJUSTABLE	TDCA	Z4XZ4 FRAME		WHILE	ADJUST TO FULL	RECTANGULAR SUPPLY AIR DUCTS	ACOUSTIC LINER	1 "
				1										VERTICAL THROW.	RECTANGULAR RETURN AIR DUCTS	ACOUSTIC LINER	1"
				1	VENTI	LAIIUI	N	RCD-1	CEILING DIFFUSER SQ CONE ROUND	TITUS TMR–AA	11 FACE	6"	ALUM, WHITE	DUCT MOUNTED UP TO 100 CFM	ALL OUTSIDE AIR DUCTS WITHIN BUILDING	DUCT WRAP	2"
					SCHE	EDULE									COMBUSTION SUPPLY AIR DUCTS ABOVE CEILING	DUCT WRAP	2"
				UNIT S	SUPPLY CFM	O.A. CFM	OA DUCT SIZE	WL-1	LOUVER WEATHER PROOF 4" FIXED BLADE DRAINABLE	RUSKIN ELF375DX	12x12 FACE 14x14 FRAME		ALUMINUM, COORD. W/ ARCH	SIDEWALL MOUNTED WITH INTEGRAL FRAME AND INSECT SCREEN UP TO 200 CFM	GREASE DUCT	THERMAL CERAMICS FIREMASTER DUCT FIRE PROTECTION SYSTEM. UL CLASSIFIED FOR 0" CLEARANCE FROM COMBUSTIBLES.	3"
				FU-1	1200	120	6	RG-1	RETURN GRILLE EGG CRATE	TITUS 50F	22x22 FACE 24x24 FRAME	22x22	ALUMINUM, WHITE	LAY-IN; UP TO 1600 CFM	CONDENSER WATER PIPE, BELOW GRADE	NO INSULATION	N/A
				FU-2	1200	120	6								CONDENSER WATER PIPE, ABOVE GRADE	ELASTOMERIC	1/2"
				FU-3	1600	160 200	8		RUNOUT DUCT SHALL					JRING AIR BALANCE.	ALL SUPPLY CEILING DIFFUSERS AND GRILLES	DUCT WRAP	2"
					2000	200											

				_								
CHE	DULE				/	AIR D	EVICE S	SCHE	EDULE		MECHANICAL INSULATION SCHEDU	JLE
ONTROL TYPE	ACCESSORIES			MARK	DESCRIPTION	MFGR., MODEL	SIZE	NECK*	MATERIAL, FINISH	COMMENTS	SERVICE INSULATION TYPE	THICKNESS
HIELDED T-STAT	D	IIC IGNITION, P RAFTER		CD-1	CEILING DIFFUSER LOUVER FACE	TITUS TDC	22x22 FACE 24x24 FRAME	6"	STEEL, WHITE	LAY-IN; UP TO 110 CFM	RESTROOM EXHAUST DUCTS, 1ST 10' FROM EXHAUST ACOUSTIC LINER GRILLE	1"
	45 DEGREE [ 50' STAINLESS ST	DISCHARGE AND TEEL HEAT EXC		CD-2	CEILING DIFFUSER LOUVER FACE	TITUS TDC	22x22 FACE 24x24 FRAME	8"	STEEL, WHITE	LAY-IN; UP TO 220 CFM	SINGLE WALL ROUND OR OVAL SUPPLY AIR DUCTS – DUCT WRAP LOW AND MEDIUM PRESSURE	2"
				CD-3	CEILING DIFFUSER LOUVER FACE	TITUS TDCA	22x22 FACE 24x24 FRAME	10"	STEEL, WHITE	LAY-IN; UP TO 400 CFM	COPPER COOLING CONDENSATE DRAIN ELASTOMERIC	3/8"
					ADJUSTABLE	IDCA	ZTXZT I MAML		<b>VV</b> 1111	ADJUST TO FULL VERTICAL THROW.	RECTANGULAR SUPPLY AIR DUCTS ACOUSTIC LINER	1"
			.1								RECTANGULAR RETURN AIR DUCTS ACOUSTIC LINER	1 "
	VENTIL			RCD-1	CEILING DIFFUSER SQ CONE ROUND	TITUS TMR-AA	11 FACE	6"	ALUM, WHITE	DUCT MOUNTED UP TO 100 CFM	ALL OUTSIDE AIR DUCTS WITHIN BUILDING DUCT WRAP	2"
	SCHE	DULE									COMBUSTION SUPPLY AIR DUCTS ABOVE CEILING DUCT WRAP	2"
UNIT NO.	SUPPLY CFM	O.A. CFM	OA DUCT SIZE	WL-1	LOUVER WEATHER PROOF 4" FIXED BLADE DRAINABLE	RUSKIN ELF375DX	12x12 FACE 14x14 FRAME		ALUMINUM, COORD. W/ ARCH	SIDEWALL MOUNTED WITH INTEGRAL FRAME AND INSECT SCREEN UP TO 200 CFM	GREASE DUCT GREASE DUCT FIRE PROTECTION SYSTEM. UL CLASSIFIED FOR 0" CLEARANCE FROM COMBUSTIBLES.	Г З"
FU-1	1200	120	6	RG-1	RETURN GRILLE EGG CRATE	TITUS 50F	22x22 FACE 24x24 FRAME	22x22	ALUMINUM, WHITE	LAY-IN; UP TO 1600 CFM	CONDENSER WATER PIPE, BELOW GRADE NO INSULATION	N/A
-U-2	1200	120	6								CONDENSER WATER PIPE, ABOVE GRADE ELASTOMERIC	1/2"
-U−3	1600	160	8		RUNOUT DUCT SHALL OORDINATE AIR DEVICE						ALL SUPPLY CEILING DIFFUSERS AND GRILLES DUCT WRAP	2"
-U-4	2000	200	8						LE ENGINEER DO			

	MINI	SPLI	ΤH	EAT	P	JMP	U	NITS
MARK	DESCRIPTION	MFGR., MODEL	CFM/ SEER	COOL CAP.	HEAT CAP.	PHASE		COMMENTS
MAC-1	MINIATURE SPLIT SYSTEM AIR CONDITIONERS, INDOOR UNIT WALL MOUNTED	MISTSUBISHI PKA A18HA4	425 15.3	18 MBH	19 MBH	120 1	20A	MAC & MCU COMPRISE A SINGLE AIR CONDITIONING SPLIT SYSTEM AND INCLUDE MICROPROCESSOR CONTROLS, PROVIDE WALL MOUNT MHK1 WIRELESS REMOTE, ON/OFF 24-HOUR TIMER, AND WASHABLE AIR FILTER
MCU-1	MINIATURE SPLIT SYSTEM AIR CONDITIONERS, OUTDOOR HP UNIT	MISTSUBISHI PUZ A18NHA4				208 1	12.4 13 20	FULL COOLING CAP TO 0 DEG WITH WIND BAFFLE

 $\square$ Ñ 0

FAN SCHEDULE													
MARK	DESCRIPTION	MFGR., MODEL		AREA	CFM,		HP/W,		SONES	CONTROL TYPE	REMARKS		
EF-1	CEILING CABINET SPA-125 PLANS .25 1100 1PH PLANS												
EF-2       EXHAUST FAN CEILING CABINET       GREENHECK SPA-200       DIRECT       SEE PLANS       200 .25       -       55 W       120V/ 1PH       2.5       SEE PLANS       a, c, e, j													
EF-3EXHAUST FAN CEILING CABINETGREENHECK DIRECT SPA-390SEE PLANS300 .25 1350135 W120V/ 1PH4.5SEE PLANSa, c, e, j													
											a,d,e,g,h,n		
GENERAL REQUIREMENTS - ALL FANS													
	/IDE PREWIRED FA /IDE PREWIRED VA							IA 3R F	OR EXTER	RIOR).			
				FAN ACC	ESSOR	IES LEG	END						
a. FACTORY-MOUNTED DISCONNECT SWITCH       f. ROOF CURB TO MATCH ROOF TYPE AND SLOPE         b. NEMA 3R DISCONNECT SWITCH       g. WALL SLEEVE         c. BACKDRAFT DAMPER       h. WIRE GUARD         d. BIRD SCREEN       i. WEATHER HOOD         e. VARIABLE SPEED CONTROLLER       j. MANUFACTURER'S WALL CAP													
	e. VARIABLE SPEED CONTROLLER j. MANUFACTURER'S WALL CAP k. INTAKE EXTENSION I. MANUFACTURER'S WHITE ALUMINUM GRILLE m. MOTOR-OPERATED DAMPER W/ 120 V ACTUATOR AND FAN START TIME DELAY CONTROLS.												

n. PREFINISHED WEATHERPROOF LOUVERS o. PROVIDE METAL LOCKING COVERS OVER FAN SWITCHES.


1					CON	DEN	SING	UNI	ΤS	CHE	DU	LE	
1	MARK	DESCRIPTION	MFGR., MODEL	AREA SERVED	NOM. TONS	SEER	VOLTS/ PHASE	FLA	МСА	MOCP	WT. LBS	ACCESSORIES	REMARKS
	CU-1,2	CONDENSING UNIT	DAIKIN DX14SA	SEE PLANS	3	14	208/1	15	18.6	30	162	COIL GUARD, TXV, CRANKCASE HEATER ANTI RECYCLE TIMER, LOW AMBIENT CONTROL	
	CU-3	CONDENSING UNIT	DAIKIN DX14SA	SEE PLANS	4	14	208/1	19.9	26.4	45	201	COIL GUARD, TXV, CRANKCASE HEATER ANTI RECYCLE TIMER, LOW AMBIENT CONTROL	
	CU-4	CONDENSING UNIT	DAIKIN DX14SA	SEE PLANS	5	14	208/1	26.3	32.6	50	260	COIL GUARD, TXV, CRANKCASE HEATER ANTI RECYCLE TIMER, LOW AMBIENT CONTROL	


					GA	S—FIF	RED	FL	JRN	ACE	U	VIT	SCI	HED	ULE					
MARK	DESCRIPTION	MFGR., MODEL	DEPENDENT UNIT	AREA SERVED	NOM. TONS	DESIGN COOLING CFM	HEAT CFM	O/A CFM	E.S.P (IN.)		COOL EAT/ LAT	HEAT EAT/ LAT	HEAT MBH IN	HEAT MBH OUT	VOLTS/ PHASE	FAN HP	WT. LBS	CONTROL TYPE	ACCESSORIES	REMARKS
FU-1,2	FURNACE PROPANE-FIRED HORIZONTAL	DAIKIN DM92SS	CU-1	SEE PLANS	3	1200	1200	120	.5	_	80/55	70/95	60	55.3	120/1	1/3	140	T-STAT	CONCENTRIC VENT KIT	PROVIDE LABOR SAVER FILTER HOUSING. HORIZ CASED COIL
FU-3	FURNACE PROPANE-FIRED HORIZONTAL	DAIKIN DM92SS	CU-1	SEE PLANS	4	1600	1600	160	.5	_	80/55	70/95	80	73.7	115/1	1/2	140	T-STAT	CONCENTRIC VENT KIT	PROVIDE LABOR SAVER FILTER HOUSING. PROVIDE VERTICAL CASED COIL.
FU-4	FURNACE PROPANE-FIRED HORIZONTAL	DAIKIN DM92SS	CU-1	SEE PLANS	5	2000	2000	200	.5	_	80/55	70/95	100	92.1	120/1	3/4	140	T-STAT	CONCENTRIC VENT KIT	PROVIDE LABOR SAVER FILTER HOUSING. HORIZ CASED COIL



Greg Anderson, Engineer 9 WEST 26th CIRCLE Fayetteville, AR 72701 PHONE: 479-601-3331 EMAIL: ga@gaengr.com PROJECT # 20006

MECHANICAL P	IPING SCHEDULE		Ш.
SERVICE	PIPING TYPE		
EQUIPMENT DRAINS, OVERFLOWS	TYPE "L" HARD COPPER		
			<u>  </u>  '
MECHANICAL DUC	CTWORK SCHEDU	LE	
SERVICE	DUCT TYPE		
RESTROOM EXHAUST DUCTS, 1ST 10' FROM EXHAUST GRILLE	RECTANGULAR W/ ACOUSTIC LINER		
RESTROOM EXHAUST DUCTS, BEYOND 10' FROM EXHAUST GRILLE	ROUND WRAPPED, OR RECTANGULAR L AS INDICATED ON THE PLANS	INED,	
ALL LOW PRESSURE SUPPLY AND RETURN AIR RECTANGULAR DUCTS.	RECTANGULAR W/ ACOUSTIC LINER		
ALL ROUND RUNOUTS TO SUPPLY DIFFUSERS AND RETURN GRILLES CONCEALED ABOVE CEILINGS.	ROUND DUCT WITH INSULATION WRAP SCHEDULE. PROVIDE 6–8' FLEX DUC CONNECTIONS PER DETAILS AND NOTE	T AT OUTLET	COMMENTS
COMMERCIAL KITCHEN EXHAUST DUCTS.	GREASE DUCT- 16 GAUGE, CARBON AIR TIGHT AT ALL JOINTS AND SEAMS. FASTENERS SHALL NOT PENETRATE DU	MECHANICAL	CRIPTION
COMBUSTION AIR SUPPLY DUCTS	ROUND OR RECTANGULAR WITH INSULA	ATION WRAP.	DESCF
NOTE: 1. PROVIDE SPIRAL OVAL DUCTS IN PLACE OF ROUND TO LIMITED SPACE.	SPIRAL WHERE SHOWN ON PLANS OR AS	REQUIRED DUE	
			DATE ATE
MECHANICAL INSU	JIATION SCHEDU	IJЕ	DATE
SERVICE	INSULATION TYPE	THICKNESS	# -
RESTROOM EXHAUST DUCTS, 1ST 10' FROM EXHAUST	ACOUSTIC LINER	1"	
GRILLE SINGLE WALL ROUND OR OVAL SUPPLY AIR DUCTS -	DUCT WRAP	2"	l c
LOW AND MEDIUM PRESSURE COPPER COOLING CONDENSATE DRAIN	ELASTOMERIC	3/8"	
RECTANGULAR SUPPLY AIR DUCTS	ACOUSTIC LINER	1"	






2020 THE HILL FIRM - ARCHITECT. ALL RIGHTS RESERV




Greg Anderson, Engineer


9 WEST 26th CIRCLE Fayetteville, AR 72701 PHONE: 479—601—3331 EMAIL: ga@gaengr.com PROJECT # 20006




## KEYED NOTES

- (1) PROVIDE 120V 20 AMP CIRCUIT TO EACH POLE. EACH CIRCUIT SHALL SERVE 1 POLE. MAX 3 CIRCUITS PER CONDUIT. ADD MORE CONDUITS AS REQUIRED. WIRE SIZE SHALL BE AS SHOWN ON THE SCHEDULE ON THIS SHEET. CONFIRM VOLTAGE DROP AND ADJUST WIRE SIZE AS REQUIRED. LOAD IS 7 AMPS AT 120V PER CAMERA. PROVIDE 3 SEPARATE 3" CONDUITS FOR POWER, FIBER, AND SPARE TO EACH POLE. BURY CONDUITS 3' AND BACKFILL. PROVIDE 17x30x24 PULL BOXES AT ALL CHANGE OF DIRECTION OF CONDUIT ON SITE. ROUTE ALL CONDUITS TO IT ROOM IN BUYERS OFFICE BUILDING. FEED POWER CIRCUITS FROM PANEL S.
- (2) CAMERA POLES SHALL BE 30' CLASS 4 UTILITY POLE SUNK 6' INTO THE GROUND. ON EACH POLE PROVIDE BREAKER BOX. POWER SHALL BE PROVIDED TO CAMERA EQUIPMENT AT 90-120V. PROVIDE 12x12 SPLICE BOX, 24x24 NEMA 4 CCTV BOX WITH BACK BOARD AND QUAD RECEPTACLE IN BOX. PROVIDE PVC PIPE FROM CCTV BOX UP TO CANTEX BOX AT THE TOP OF EACH POLE. PROVIDE WATER PROOF FLEX CONNECTION FROM CONDUIT TO NEMA BOX. PROVIDE ALL ITEMS AS SHOWN IN THE DETAILS AT EACH POLE. BOLLARDS TO BE PROVIDE BY GENERAL CONTRACTOR.
- (3) GAS PIPE EASEMENT SHOULD ONLY BE CROSSED WHERE APPROVED. SEE CIVIL PLANS.





SINAL SHEET SIZE 36 x 24 / DO NOT SCALE DRAWING



© 2020 THE HILL FIRM - ARCHITECT. ALL RIGHTS RESERVEI



Greg Anderson, Engineer 9 WEST 26th CIRCLE Fayetteville, AR 72701 PHONE: 479-601-3331 EMAIL: ga@gaengr.com PROJECT # 20006

# GENERAL POWER PLAN NOTES

- 1.) <u>OUTLET ROUGH-IN COORDINATION</u>: COORDINATE EXACT LOCATIONS OF ALL OUTLETS IN AREAS WITH MILLWORK WITH ARCHITECTS MILLWORK ELEVATIONS PRIOR TO ROUGH-IN.
- 2.) <u>TELEPHONE/ COMMUNICATIONS OUTLETS:</u> PROVIDE 3/4" CONDUIT, 2x4" JUNCTION BOX WITH DOUBLE GANG DEVICE RING FOR ALL TELEPHONE AND COMMUNICATIONS OUTLETS INDICATED ON THE ELECTRICAL DRAWINGS. ROUTE CONDUIT FROM BOX UP WALL AND TURN OUT TO ACCESSIBLE CEILING CAVITY. PROVIDE PLASTIC BUSHINGS ON CONDUIT ENDS. PROVIDE PULL STRING IN ALL EMPTY CONDUIT SYSTEMS. PROVIDE 1" CONDUIT WHERE REQUIRED BY COM CONTRACTOR.
- 4.) <u>ELECTRIC WATER HEATERS:</u> MAKE CONNECTIONS AS REQUIRED. VERIFY REQUIREMENTS AND LOCATION WITH MECHANICAL CONTRACTOR PRIOR TO INSTALLATION. PROVIDE CORD AND PLUG AS REQUIRED.
- 5.) <u>CONDUIT SIZING:</u> ALL CONDUITS FOR BRANCH CIRCUITING CONTAINING UP TO 10 #12 CONDUCTORS TO BE 3/4 INCH UNLESS LABELED OTHERWISE OR OTHERWISE REQUIRED BY NEC.
- 6.) <u>EXISTING EQUIPMENT:</u> FIELD VERIFY LOCATIONS OF EXISTING ELECTRICAL EQUIPMENT, INCLUDING POWER POLES, TELEPHONE PEDESTALS, OVERHEAD AND UNDERGROUND FEEDERS, METERS, PANELS, DEVICES, ETC. PROVIDE FOR COORDINATION WITH EXISTING EQUIPMENT.
- 7.) <u>THERMOSTAT CONDUITS:</u> PROVIDE 3/4" CONDUIT, AND 2x4" BOX WITH SINGLE GANG DEVICE RING FOR ALL THERMOSTAT LOCATIONS INDICATED ON THE MECHANICAL DRAWINGS. ROUTE CONDUIT FROM BOX TO ACCESSIBLE CEILING CAVITY. PROVIDE PLASTIC BUSHINGS ON EXPOSED CONDUIT ENDS. PROVIDE PULL STRING IN ALL EMPTY CONDUIT SYSTEMS. COORDINATE EXACT LOCATIONS AND MOUNTING HEIGHTS WITH MECHANICAL CONTRACTOR PRIOR TO ROUGH-IN.
- 8.) <u>MECHANICAL EQUIPMENT CONNECTIONS:</u> COORDINATE MECHANICAL EQUIPMENT CONNECTION REQUIREMENTS WITH MECHANICAL CONTRACTOR PRIOR TO ROUGH-IN. LOCATE FEEDERS, DISCONNECTS AND MAINTENANCE RECEPTACLES SO THAT THEY WILL NOT INTERFERE WITH OPERATION OR MAINTENANCE OF MECHANICAL EQUIPMENT.

# **KEYED NOTES**


- (1) COORDINATE ELECTRIC METER LOCATION AND SIZE WITH POWER COMPANY.
- (2) EXTERIOR POWER SERVICE DISCONNECT
- (3) 3/4" PLYWOOD PHONE BOARD WITH GROUND BAR. PROVIDE 2-2" CONDUITS TO LOCATIONS SPECIFIED BY IT COORDINATOR.
- (4) POWER AND DATA OUTLETS MOUNTED IN MILLWORK. COORDINATE WITH
- ARCHITECT AND G.C. (5) EXTERIOR LIGHTING CONTROL CONTACTORS.
- 6 NOT USED.
- (7) MOUNT WALL PACKS WITH BOTTOM AT 14' AFF.
- (8) PROVIDE CONNECTION FOR PORTABLE GENERATOR. COORDINATE WITH OWNER.
- (9) COORDINATE PRINTER LOCATION AND POWER REQUIREMENTS WITH OWNER.
- PROVIDE CONDUIT TO 14 POLE MTD SECURITY CAMERAS AT PARKING LOTS. COORDINATE REQUIREMENTS WITH OWNER.
- PROVIDE SEPARATE 208V/1PH CIRCUIT TO EACH OF 2 GUARD SHACKS. SEE SITE PLAN. COORDINATE REQUIREMENTS WITH OWNER.
- (2) PROVIDE ISOLATED GROUND AT ALL OUTLETS IN THE IT ROOM.

# GENERAL LIGHTING PLAN NOTES

- 30.) <u>EXIT LIGHTS:</u> CONNECT EXIT LIGHTS TO UNSWITCHED PORTION OF ADJACENT LIGHTING CIRCUIT. DO NOT SWITCH.
- 31.) INDOOR FIXTURE LOCATIONS ARE SCHEMATIC IN NATURE: LOCATION ADJUSTMENTS PRIOR TO INSTALLATION SHALL BE MADE AT NO COST TO OWNER. COORDINATE EXACT LOCATIONS WITH ARCHITECTURAL REFLECTED CEILING PLAN. VERIFY IN FIELD.
- 32.) <u>EMERGENCY LIGHTS:</u> EMERGENCY LIGHTS ARE SHOWN ON THE PLAN. PROVIDE EMERGENCY BALLAST. PROVIDE "HOT" WIRE TO EMERGENCY LIGHT FROM NEARBY LIGHTING CIRCUIT. DO NOT SWITCH EMERGENCY LIGHT FIXTURE.
- 33.) <u>NOT USED</u>
- 34.) <u>CEILING COORDINATION:</u> COORDINATE ALL CEILING MOUNTED ELECTRICAL ITEMS WITH OTHER DISCIPLINES AND WITH CEILING GRID & BAR JOIST. REFER TO ARCHITECTURAL REFLECTED CEILING PLAN.
- 35.) <u>FIRE RATED CEILING:</u> WHERE RECESSED LIGHTING FIXTURES ARE INDICATED IN A FIRE RATED CEILING, PROVIDE A ONE HOUR RATED "TENT" AS DETAILED ON ARCHITECTURAL DRAWINGS.


Initial Contribution       Initial Date       Initial Date							5003 OLD GREENWOOD RD, SUITE D - FT SMITH, AR 72903 DH: 470 404 1808 - WWW HILLERM NET	
Insurance Auto Auction, Inc.       #         TBD       TBD         TBD       Jabb         Lexington, South Carolina 29073       4         PERMIT - CONSTRUCTION DOCUMENTS       4	COMMENTS		ADD SECURITY CAMERAS ON :					
Insurance Auto Auction, Inc. TBD Lexington, South Carolina 29073 PERMT - CONSTRUCTION DOCUMENTS	DATE	08/11/20	09/02/20	11/04/20	02/05/21			
Insura Permit -	#	-	2	Ю	4			
	•							, UIMEN I
				10. 5 G	The second south Carolina 290			<b>FERMIN</b>
05/13/20 2020-09 SHEET:					ا ا ا ا ا ا ا ا ا ا ا ا ا ا ا ا ا ا ا	IIII POX 5 120 ANIIII AN		

												Ú	
			LIC	GHTI	NG FIX	XTU	RE S	SCHEE	DULE				
						LAMPS				FIXT	URE		
MARK	DESCRIPTION	MFGR.	MODEL		ESCRIPTION	COLOR TEMP.K	LUMENS	WATTS QTY	BALLAST	LUMENS	WATTS	VOLTS	REMARKS
LS	LED STRIP 4 FT LENSED WRAP AROUND	WILLIAMS	39-L30/835	WHITE	LED	3500	3000	25 1	LED	3000	25	120	SURFACE MTD
SYMBOL	DESCRIPTION	MFGR. M	SWITC ODEL VOLTAGE RATING	AMPS	SCHED MOUNTIN HEIGHT AFF	IG		REMAF	RKS				
		ATT DT TOPPER	-355 120V	20	RECESSED I CEILING			OGY INFRA RE R, LINE VOLTA		ASONIC			
		RECE	PTACLE	SC	HEDU	LE							
SYMBOL	DESCRIPTION	MFGR.	MODEL	NEMA	MOUNTING HEIGHT AFF	REM	IARKS						
⊗=	DUPLEX GFCI W/ BACK & SIDE WIRE, TEST & RESET BUTTON	HUBBELL	GFRST20 5	5–20R 1	'-6" TO TOP		TRIP POINT AULT CURR						



Scale: 1/8" = 1'-0"





2 0

F			EDS			P	OLTS: HASE: WRE:	3					AIC RA MOUNT LOCAT	ING:	22000 RECESSED VIC BACK WALL		
	LOAD	DESCRIPTION	WRE		CCT.			KV	4			CCT.		WRE	LOAD DESC	RIPTION	1
LTS	REC	OTHER	AWG.	BRKR	NO.	Α		В		С		NO.	BRKR	AWG.	OTHER	REC	LTS
	7	REC VIC R	12	20/1	1	1.3	0.5					2	20/1	12	SPARE		
6		LTS VIC	12	20/1	3			0.2	0.5			4	20/1	12	SPARE		
	7	REC VIC F	12	20/1	5		20			1.3	0.5	6	20/1	12	SPARE		
		SPARE	12	20/1	7	0.5	0.5					8	20/1	12	SPARE		
		SPARE	12	20/1	9			0.5	0.5			10	20/1	12	SPARE		
								TOTA	LS						1		
					Γ	1.8	1.0	0.7	1.0	1.3	0.5	1					
						2.8	B	1.7	/	1.8		-					
												1					
				TOTAL	CONN	ECTED	KVA	6.2	2								
				MAX	ONNE		MPS	23.	0								
				NEC D	EMAN	D AMPS	5	17.	2								





 $\cup$ 



- STEEL.



1.) <u>OUTLET ROUGH-IN COORDINATION</u>: COORDINATE EXACT LOCATIONS OF ALL OUTLETS WITH ARCHITECTS ELEVATIONS PRIOR TO ROUGH-IN.



Greg Anderson, Enginee 9 WEST 26th CIRCLE Fayetteville, AR 72701 PHONE: 479-601-3331 EMAIL: ga@gaengr.com PROJECT # 20006

# GENERAL ELECTRICAL NOTES

1 PROVIDE A COMPLETE AND OPERATING ELECTRICAL SYSTEM INCLUDING ALL INCIDENTAL ITEMS AND CONNECTIONS NECESSARY FOR PROPER OPERATION.

2 FINAL LAYOUT SHALL BE GOVERNED BY ACTUAL FIELD CONDITIONS WITH ALL MEASUREMENTS VERIFIED AT THE SITE AND COORDINATED WITH OTHER TRADES.

3 PROVIDE CIRCUITS AND MAKE FINAL CONNECTIONS TO ALL MECHANICAL EQUIPMENT, APPLIANCES, AND OTHER DEVICES REQUIRING ELECTRICAL POWER THAT ARE INDICATED ON ANY OF THE DRAWINGS OR SPECIFICATIONS CONTAINED HEREIN.

4 ALL WORK SHALL COMPLY WITH THE NATIONAL ELECTRICAL CODE (NEC) CURRENT EDITION AND ALL PRODUCTS SHALL BE NEW AND LISTED AND LABELED BY UNDERWRITERS LABORATORIES (UL). COMPLY WITH ALL APPLICABLE REGULATIONS AND LAWS.

5 WIRING AND CABLES SHALL BE SINGLE CONDUCTOR COPPER WITH 600 VOLT CODE TYPE THW OR THHN INSULATION. MINIMUM WIRE SIZE IS #12 AWG. INSTALL ALL POWER WIRING IN CONDUIT.

6 UNDERGROUND OR OUTSIDE CONDUIT SHALL BE SCHEDULE 40 PVC CONDUIT AND FITTINGS.

7 ABOVE GROUND CONDUIT INSIDE BUILDING SHALL BE EMT WITH SET SCREW OR COMPRESSION FITTINGS.

8 JUNCTION AND OUTLET BOXES SHALL BE OF CODE GAUGE GALVANIZED

9 RIGIDLY SUPPORT CONDUIT AND BOXES FROM THE BUILDING STRUCTURE PER THE NEC PRIOR TO PULLING IN THE CONDUCTORS. 10 LEAVE PULL WIRE IN EMPTY CONDUIT WITH IDENTIFYING LABELS FOR FUTURE WIRE INSTALLATION.

11 IDENTIFY ELECTRICAL EQUIPMENT, SUCH AS PANELS, STARTERS, AND SPECIAL SWITCHES WITH PLASTIC NAMEPLATES. FILL OUT CIRCUIT DIRECTORIES COMPLETELY IN EACH PANEL.

# GENERAL POWER PLAN NOTES

# **KEYED NOTES**


PROVIDE 100A/10 CCT/ 1PH PANEL FED FROM PANEL R IN RUN AND DRIVE BUILDING.

Insurance Auto Auction, Inc.       # Date Date Comments         TBD       TBD         TBD       Lexington, South Carolina 29073         PERMIT - CONSTRUCTION DOCUMENTS       PERMIT - CONSTRUCTION DOCUMENTS
#       TBD       TBD         TBD       TBD         Lexington, South Carolina 29073       1         PERMIT - CONSTRUCTION DOCUMENTS       1
Insurance Auto Auction, Inc. TBD Lexington, South Carolina 29073 PERMIT - CONSTRUCTION DOCUMENTS
Insurance Auto Auction TBD TBD Lexington, South Carolina 290 PERMIT - CONSTRUCTION DC
WITH CARO


# GENERAL ELECTRICAL NOTES

- 1 PROVIDE A COMPLETE AND OPERATING ELECTRICAL SYSTEM INCLUDING ALL INCIDENTAL ITEMS AND CONNECTIONS NECESSARY FOR PROPER OPERATION.
- 2 FINAL LAYOUT SHALL BE GOVERNED BY ACTUAL FIELD CONDITIONS WITH ALL MEASUREMENTS VERIFIED AT THE SITE AND COORDINATED WITH OTHER TRADES.
- 3 PROVIDE CIRCUITS AND MAKE FINAL CONNECTIONS TO ALL MECHANICAL EQUIPMENT, APPLIANCES, AND OTHER DEVICES REQUIRING ELECTRICAL POWER THAT ARE INDICATED ON ANY OF THE DRAWINGS OR SPECIFICATIONS CONTAINED HEREIN.
- 4 ALL WORK SHALL COMPLY WITH THE NATIONAL ELECTRICAL CODE (NEC) CURRENT EDITION AND ALL PRODUCTS SHALL BE NEW AND LISTED AND LABELED BY UNDERWRITERS LABORATORIES (UL). COMPLY WITH ALL APPLICABLE REGULATIONS AND LAWS.
- 5 WIRING AND CABLES SHALL BE SINGLE CONDUCTOR COPPER WITH 600 VOLT CODE TYPE THW OR THHN INSULATION. MINIMUM WIRE SIZE IS #12 AWG. INSTALL ALL POWER WIRING IN CONDUIT.
- 6 UNDERGROUND OR OUTSIDE CONDUIT SHALL BE SCHEDULE 40 PVC CONDUIT AND FITTINGS.
- 7 ABOVE GROUND CONDUIT INSIDE BUILDING SHALL BE EMT WITH SET SCREW OR COMPRESSION FITTINGS.
- 8 MAKE FINAL CONNECTIONS TO MOTORS, PUMPS, OR OTHER VIBRATING EQUIPMENT WITH "SEALTIGHT" FLEXIBLE CONDUIT.
- <sup>9</sup> JUNCTION AND OUTLET BOXES SHALL BE OF CODE GAUGE GALVANIZED STEEL.
- <sup>10</sup> RIGIDLY SUPPORT CONDUIT AND BOXES FROM THE BUILDING STRUCTURE PER THE NEC PRIOR TO PULLING IN THE CONDUCTORS.
- 11 SAFETY DISCONNECT SWITCHES SHALL BE HEAVY DUTY "HD" TYPE IN NEMA 1 ENCLOSURE OF RATINGS AS SHOWN ON THE DRAWINGS OR REQUIRED BY EQUIPMENT SERVED. FUSED DISCONNECT SWITCHES SHALL BE COMPLETE WITH CURRENT LIMITING FUSES.
- 12 LEAVE PULL WIRE IN EMPTY CONDUIT WITH IDENTIFYING LABELS FOR FUTURE WIRE INSTALLATION.
- 13 IDENTIFY ELECTRICAL EQUIPMENT, SUCH AS PANELS, STARTERS, AND SPECIAL SWITCHES WITH PLASTIC NAMEPLATES. FILL OUT CIRCUIT DIRECTORIES COMPLETELY IN EACH PANEL.
- 14 PAY ALL PERMITS AND INSPECTION FEES REQUIRED.
- 15 PROVIDE CONTROL WIRING, AS WELL AS POWER WIRING FOR HVAC EQUIPMENT.

		RECE	EPTACL	E S	CHEDUL	E				<u></u>		COLLED	
SYMBOL	DESCRIPTION	MFGR.	MODEL	NEMA	MOUNTING	REMARKS		SCON	NECI	5 W I	ICH	SCHED	EDULE
					HEIGHT AFF		MARK/ SYMBOLS	LOAD SERVED	VOLTS, POLE,	SWITCH AMPS	FUSES	NEMA ENCLOSURE	NOTES
<del>C</del>	DUPLEX W/ BACK & SIDE WIRE	COOPER	TR270	5–15R	1'-6" TO BOTTOM	_	S1	EWH	WIRES 120/208V 1P	30A	NF	3R	NOTE a.
GFI ⊗=	DUPLEX GFCI W/ BACK & SIDE WIRE, TEST & RESET BUTTON	COOPER	?	5–15R	1'-6" TO BOTTOM	SET TRIP POINT AT 5 MA FAULT CURRENT.	<sup>1</sup> 		208V	30A	NF	3R	NOTE a.
GFI	ABOVE COUNTER GFCI DUPLEX W/	COOPER	?	5-15R	8" ABOVE COUNTERTOP.	SET TRIP POINT AT 5 MA FAULT CURRENT.		MCU	3P 4W				
⊨⊗=	BACK & SIDE WIRE, TEST & RESET BUTTON				COUNTERTOP.		S3 ℃	AC UNITS	208V 3P 4W	60A	NF	ЗR	NOTE a.
ŧ	SPECIAL	COOPER	SPECIFICATION GRADE OR BETTER	REF. DRAWING	8" ABOVE COUNTERTOP.	PROVIDE NEMA TYPE COMPATIBLE W/ PLUG CONFIGURATION OF APPLIANCE OR EQUIPMENT.	SAFETY SWITC a. HEAVY DU	TY TYPE.					
NOTE:	2. COORDINATE CO	1. PROVIDE COVER PLATE AND ANY ACCESSORIES NEEDED FOR COMPLETE INSTALLATION OF RECEPTACLE. 2. COORDINATE COLOR OF ALL DEVICE AND COVER PLATES WITH ARCHITECT. 3. COORDINATE ALL MOUNTING HEIGHTS WITH ARCHITECT					<ul> <li>b. SWITCH SHALL BE "SERVICE ENTRANCE" LABELED AND LISTED.</li> <li>c. PROVIDE AUXILIARY CONTACTS IN DISC SWITCH FOR ELEVATOR AUTOMATIC LOWERING CUTC</li> <li>d. VERIFY FUSE SIZE WITH EQUIPMENT MANUFACTURER'S NAMEPLATE DATA.</li> </ul>						ERING CUTOF




	FEEDER SCHEDULE								
MARK	AMPACITY/ PHASE/ WIRES	LOAD Served	CONDUIT AND WIRE (COPPER)						
1	400A 3PH 4W	PANEL B	<u>3.5"C, 4-#500 1-#3 GND</u>						
2	200A 3PH 4W	PNL R	<u>2"C, 4-#3/0 1-#6 GND</u>						
3	100A 3PH 4W	VIC PANEL V	<u>1-1 1/4"C. 4-#2.</u> <u>1#8 GND</u>						






Greg Anderson, Engineer 9 WEST 26th CIRCLE Fayetteville, AR 72701 PHONE: 479-601-3331 EMAIL: ga@gaengr.com PROJECT # 20006


ELECT	RICA	L LEGEND	
DIMENSIONS SHOWN BE CENTER LINE OF DEVIC		STANDARD MOUNTING HEIG OTHERWISE SPECIFIED.	HTS TO
HOME RUN PANEL AND CIRCUIT NOTED	◄	CIRCUIT CONDUCTORS; INSULATED GROUND, NEUTRAL AND HOT, RESPECTIVELY	x I
DUPLEX RECEPTACLE (1'6"AFF)	ŧ	TV DUPLEX RECEPTACLE (7'6"AFF)	⊜ <sup>TV</sup>
GFCI DUPLEX RECEPTACLE (1'6"AFF)	₿	CT INDICATES COUNTER TOP HEIGHT DEVICE. COORDINATE ELEVATION	
QUADRUPLEX RECEPTACLE (1'6"AFF)	<b></b>	WITH COUNTER HEIGHT AND BACKSPLASH. LOCATE WHERE SHOWN ON ARCH ELEVATIONS.	СТ
SIMPLEX RECEPTACLE (1'6"AFF)	-0	RECESSED FLOOR BOX WITH	
SPECIAL RECEPTACLE(1'6"AFF)	•	DEVICES AS INDICATED	
LOWER CASE LETTERS INDICATE SWITCHING CONFIGURATION. TWO LETTERS ON SAME	a, b, c	20A, 120/277V (4'0" AFF TO TOP) THREE WAY SWITCH 20A, 120/277V (4'0"	\$\$
FIXTURE INDICATES INBOARD – OUTBOARD SWITCHING.		AFF TO TOP)	
EXIT LIGHT: PROVIDE DIRECTIONAL INDICATION AS REQUIRED PER CODE. DO NOT SWITCH.	×	AFF TO TOP) EMERGENCY LIGHT WITH BATTERY BACKUP, LETTER INDICATES TYPE.	\$ <sub>D</sub>
NON-FUSED DISCONNECT SWITCH (4'0"AFF TO TOP)	L)	EMERGENCY LIGHT	
TV CABLE OUTLET (7'6" AFF)	T∨	MOTOR	N
DUCT MOUNTED SMOKE DETECTOR	DD	JUNCTION BOX	J
EMERGENCY	(E)	TO EQUIPMENT	
WEATHER PROOF	WP	COMMUNICATIONS OUTLET (1'6"AFF)	©
GROUND FAULT CIRCUIT INTERRUPTER	GFCI	EXISTING TO REMAIN	ETR
ISOLATED GROUND	IG	ELECTRICAL CONTRACTOR	EC
ABOVE FINISHED FLOOR	AFF	UNDER GROUND	U/G



Ο









# OCCUPANCY SENSOR WIRING DIAGRAM

	BLUE	
	CEILING MOUNTED OCCUPANCY SENSOR	
 LIGHTING LOAD a		
 LIGHTING LOAD b		

/	-24V POWER PACK
	RED BLUE BLUE
	CEILING MOUNTED OCCUPANCY SENSOR
NG a	
NG b	

				GHI	ING FI	XIUł	ΥĿ ζ	SCH	EL	)ULE				
											FIXT	URE		
MARK	DESCRIPTION	MFGR.	MODEL	FINISH	DESCRIPTION	I TEMP,K	LUMENS	WATTS	QTY	BALLAST	LUMENS	WATTS	VOLTS	REMARKS
C1	6" DISK LIGHT SURFACE MTD WHITE TRIM LED	C&F LIGHTING	LED022WH	WHITE	LED	3000K	1000	15	1	LED	1000	15	120	DIMMABLE MOUNT ON FIRE RATED JE WHERE REQUIF WET LOCATIO
E5	EMERGENCY LIGHT ULTRA COMPACT LED	BARRON EXITRONIX	LED 52 WH G2	WHITE	LED	6000	_	2	2	2	250	5	120	90 MINUTE EM BATTERY 1FC @ 40' O
H1	HIGH BAY SUSPENDED LED CLEAR ACRYLIC REFLECTOR. MILKY LENS	GE ALBEO	ABV2-1-1-E-48 D-V-23-A-B-W	WHITE	LED DIMMABLE	4000K	18,200	122	1	LED	18,200	122	120	3/4" PIPE PENDANT MOUNT.
L4	2x4 LAY IN PANEL LED CCT SELECT DIMMABLE	VENTURE	DLC-P124-48 ANR-C	WHITE	LED	3500K 4000K 5000K	4660 4740 5030	44	1	LED	4660 4740 5030	44	120	80+ CRI DAMP LOC IC RATED
LS	LED STRIP 4 FT LENSED WRAP AROUND	WILLIAMS	39-L30/835	WHITE	LED	3500	3000	25	1	LED	3000	25	120	SURFACE MTE
W1E	WALL MTD COMPACT EGRESS LIGHT, LED TEARDROP	BARRON EXITRONIX	TRL ACEM	BZ AL WH	LED	5000	1080	11	_	LED	1080	11	120	90 MINUTE EM BATTERY 1FC © 30' OC WET LOCATION
W2	WALL PACK LOW PROFILE CAST ALUM LED	WILLIAMS	VWPH-L60/740 T4-DBZ-120V	BRONZE	LED	4000	6000	70	-	LED	6000	70	120	_
W2 LTERNATE	SECURITY WALL PACK CAST ALUM LED	CREE SECURITY EDGE	SEC-EDG 4M WM 12 E UL BZ 40K	BRONZE	LED	4000	13000	130	_	LED	13000	130	120	_
XE	EXIT AND LED BAR EMERGENCY LIGHT	BARRON LED	CLED-U-WH	WHITE	LED	_	_	4.5	1	LED	_	4.5	120	90 MINUTE EM BATTERY 1FC @ 12'x6'

NOTES: - ALL FIXTURES SHALL BE PROVIDED WITH ALL ACCESSORIES FOR A COMPLETE INSTALLATION, INCLUDING MOUNTING HARDWARE. - CONTRACTOR SHALL VERIFY FIXTURE MOUNTING TYPE IS COMPATIBLE WITH CEILING TYPE AND PROVIDE 0 DEGREES F RATED BALLAST AT OUTDOOR INSTALLATIONS OF FIXTURES.
 PROVIDE SAFETY CABLES AND WIRE GUARDS WHERE REQUIRED. STRUCTURAL CONDITIONS. FINISHES SHALL BE COORDINATED WITH ARCHITECT OR OWNER BEFORE ORDERIN
 PROVIDE BALLAST EQUAL TO BODINE B50, BATTERIES AND CHARGER AT EMERGE


			S	WITC	H S	CHEDUL	_E		
SYMBOL	DESCRIPTION	MFGR.	MODEL	VOLTAGE RATING	AMPS	MOUNTING HEIGHT AFF	REMARKS		
\$	SINGLE POLE	HUBBELL	HBL122	120-277V	20	4'-0" TO TOP AFF	PROVIDE HIGH CAPACITY SILVER ALLOY SWITCH CONTACTS		
\$ 3	THREE-WAY	HUBBELL		120-277V	20	4'-0" TO TOP AFF	PROVIDE HIGH CAPACITY SILVER ALLOY SWITCH CONTACTS		
\$ <sub>os</sub>	\$ 0CCUPANCY SENSOR WALL SWITCH       LEVITON       0SSMT       120-277V       20       4'-0" TO TOP AFF       PROVIDE HIGH CAPACITY SILVER ALLOY SWITCH								
D <sup>\$</sup> os	OCCUPANCY SENSOR WALL SWITCH WITH DIMMER	LUTRON MAESTRO	MS-Z101 -XX	120–277V	20	4'-0" TO TOP AFF	PROVIDE HIGH CAPACITY SILVER ALLOY SWITCH CONTACTS, 0-10V DIMMING FOR LED LIGHT FIXTURES.		
ß	OCCUPANCY SENSOR	WATT STOPPER	DT-355	120V	20	RECESSED IN CEILING	DUAL TECHNOLOGY INFRA RED AND ULTRASONIC MOTION SENSOR, LINE VOLTAGE		
2. 3. SI	COORDINATE COL PROVIDE OCCUP	_OR OF DE\ ANCY SENS OR 120 VO	VICE AND O ORS WITH	OVER PLATES POWER PACK	S WITH AR S AS REQU	CHITECT. JIRED IN RESTROO	DN OF SWITCHING DEVICE. MS, CORRIDORS & CLASSROOMS. POWER PACKS POWER TO POWER PACKS FROM NEAREST 277V		



**Greg Anderson, Engineer** 9 WEST 26th CIRCLE Fayetteville, AR 72701 PHONE: 479–601–3331 EMAIL: ga@gaengr.com PROJECT # 20006

ING.	
GENCY	FIXTURES.

LIGHTING CONTACTOR SCHEDULE												
MARK	LOAD SERVED	MANUF., MODEL NO.	NUMBER OF POLES	COIL VOLTAGE, CONTACTING RATING	NEMA ENCLOSURE	NOTES						
LTC1	EXTERIOR LIGHTS	SQUARE D #LX	4	120V 20A	1	NORMALLY OPEN NOTE a.						
	LIGHTING CONTRACTOR SCHEDULE NOTES: a. PROVIDE HAND/OFF/AUTO SWITCH PER SPECIFICATIONS. b. PROVIDE TWO-WIRE CONTROL RELAY FOR COIL CLEARING.											



0

				D/		RO	APD	SC	HEDU	IF						/		
	S-SECURITY			F /	영양하는 영양 전 전 전 전 전 전 전 전 전 전 전 전 전 전 전 전 전 전	LTS: 1	S. 1998 (1998)	50			AIC RA		22000					
	200 A MLO					ASE:	3				MOUNT		SURFACE					
	PANEL B				W	/IRE:	4				LOCATI	ION:	WALL					
	D TYPE: NQO			Carlos - No. ( Sec. 13)												$\langle$		
LOAD	O DESCRIPTION OTHER	WIRE		CCT. NO.	A		KVA B		С	CCT. NO.	BRKR	WRE AWG.	LOAD DESCRIF OTHER	REC		)		
IS REC	CAMERA POLE 1	12	20/1	1	0.8	0.8	В		<u> </u>	2	20/1		CAMERA POLE 2	REC	LIJ	$\langle$		
	CAMERA POLE 3	00000	20/1	3			0.8	0.8		4	20/1	12	CAMERA POLE 4			)		
	CAMERA POLE 5	12	20/1	5		L			0.8 0.	B 6	20/1	12	CAMERA POLE 6			<		
	CAMERA POLE 7	12	20/1	7	0.8	0.8			1	8	20/1	12	CAMERA POLE 8			)		
	CAMERA POLE 9	12	20/1	9			0.8	0.8		10	20/1	12	CAMERA POLE 10			2		
	CAMERA MC	12	20/1	11		-	1		0.8 0.	8 12	20/1	12	CAMERA VIC					
	SPARE	12	20/1	13	0.5	0.5			16	14	20/1	12	SPARE					
	SPARE	12	20/1	15			0.5	0.5		16	20/1	12	SPARE			$\sum$		
	SPARE	12	20/1	17					0.5 0.	5 18	20/1	12	SPARE			)		
	SPARE	12	20/1	19	0.5	0.5				20	20/1	12	SPARE			$\langle$		
	SPARE	12	20/1	21			0.5	0.5		22	20/1	12	SPARE			)		
	SPACE			23					0.5 0.	-			SPACE			$\langle  $		
	SPACE			25	0.0	0.0		12121		26			SPACE					
	SPACE			27			0.0	0.0		28			SPACE					B-BUYERS OFFICE
	SPACE			29	0.0	0.0			0.0 0.				SPACE					: 400 A MCB : METER
	SPACE			31	0.0	0.0	0.0	0.0		32			SPACE			. / . '		
	SPACE			33			0.0	0.0	0.0	34			SPACE				ARE	D TYPE: NQO
	SPACE		100/2	35	0.0	0.0			0.0 0.		-		SPACE			)	100	
	SPD		100/3	37 39	0.0	0.0	0.0	0.0		38 40			SPACE SPACE			< 1 Te	LOA	D DESCRIPTION OTHER
				39 41			0.0	0.0	0.0 0.				SPACE			42		LTS NORTH
							ΤΟΤΑΙ	S	0.0 0.				JIAVE			24		LTS SOUTH
				Ĩ	2.7	2.7	2.7	2.7	2.7 2.1	2						14		LTS EXT
				-	5.4		5.4		4.9	-								SPARE
				L												$\langle  $	4	<b>REC 105 NE</b>
			TOTAL	CONI		KVA	15.6										4	REC 105 NE
			MAY O			IDS	44.7									$\langle  $	2	<b>REC 105 PRN 2</b>
			MAX C	UNNE	CILD AN	11 3												DEC 405 CW
					D AMPS		50.2										4	<b>REC 105 SW</b>
							01/24200										4	REC 105 SW REC 105 NW
							01/24200									$\langle  $	4	REC 105 NW REC IT/EXT
							01/24200										4 2 1	REC 105 NW REC IT/EXT REC FACP
							01/24200		~						2	}	4 2 1 2	REC 105 NW REC IT/EXT REC FACP REC 104 TOW
					D AMPS		50.2			<u> </u>		<u> </u>			2	3	4 2 1 2 3	REC 105 NW REC IT/EXT REC FACP REC 104 TOW REC CONF W
					D AMPS		50.2			_∕_ JLE	<u></u>	<u> </u>			2		4 2 1 2	REC 105 NW REC IT/EXT REC FACP REC 104 TOW REC CONF W REC CONF SE
	: R- RUN AND DRIVE	<u> </u>				BO	50.2 ARC 120/208		CHEDU	<u> </u>		ATING:	22000		2		4 2 1 2 3 3	REC 105 NW REC IT/EXT REC FACP REC 104 TOW REC CONF W REC CONF SE REC EWH-1
MAIN	: 200 A MCB	<u> </u>					50.2 DARC 120/208 3		A A CHEDL	<u> </u>	MOUN	TING:	SURFACE		2		4 2 1 2 3 3 3 4	REC 105 NW REC IT/EXT REC FACP REC 104 TOW REC CONF W REC CONF SE REC EWH-1 REC 106 BM
MAIN		<u> </u>				BO	50.2 ARC 120/208		CHEDU	JLE		TING:			2		4 2 1 2 3 3 3 4 4	REC 105 NW REC IT/EXT REC FACP REC 104 TOW REC CONF W REC CONF SE REC EWH-1 REC 106 BM REC BRK WALLS
MAIN FEED	: 200 A MCB	<u> </u>					50.2 DARC 120/208 3		CHEDL	<u>م</u> الد	MOUN	TING:	SURFACE		2		4 2 1 2 3 3 3 4 4 4 1	REC 105 NW REC IT/EXT REC FACP REC 104 TOW REC CONF W REC CONF SE REC EWH-1 REC 106 BM
MAIN FEED QUARE	E 200 A MCB METER D TYPE: NQO	AREA					50.2 <b>ARC</b> 120/208 3 4	) S(	CHEDU			TING: FION:	SURFACE WALL		2		4 2 1 2 3 3 3 4 4	REC 105 NW REC IT/EXT REC FACP REC 104 TOW REC CONF W REC CONF SE REC EWH-1 REC 106 BM REC BRK WALLS REC BRK CTR S
MAIN FEED QUARE	D TYPE: NQO			EMAN P			50.2 DARC 120/208 3	) S(	CHEDU	CC1		TING: TION: WRE	SURFACE WALL		-		4 2 1 2 3 3 3 4 4 4 1 1	REC 105 NW REC IT/EXT REC FACP REC 104 TOW REC CONF W REC CONF SE REC EWH-1 REC 106 BM REC BRK WALLS REC BRK CTR S REC 100 E
MAIN FEED QUARE LOA TS REC	D TYPE: NQO	AREA		EMAN P			50.2 <b>DARC</b> 120/208 3 4 KV/	) S(				TING: TION: WRE	SURFACE WALL		LTS 5		4 2 1 2 3 3 3 4 4 4 1 1 3	REC 105 NW REC IT/EXT REC FACP REC 104 TOW REC CONF W REC CONF SE REC EWH-1 REC 106 BM REC BRK WALLS REC BRK CTR S REC 100 E REC RR S
MAIN FEED UARE LOA S REC	D TYPE: NQO D DESCRIPTION D OTHER	AREA WIRE AWG.				BO DLTS: IASE: MIRE:	50.2 <b>DARC</b> 120/208 3 4 KV/	) S(			MOUN LOCAT	TING: TION: WIRE AWG.	SURFACE WALL LOAD DESCRI OTHER		LTS		4 2 1 2 3 3 3 4 4 4 1 1 3 6	REC 105 NW REC IT/EXT REC FACP REC 104 TOW REC CONF W REC CONF SE REC EWH-1 REC 106 BM REC BRK WALLS REC BRK CTR S REC 100 E REC RR S REC LOBBY
MAIN FEED UARE LOA S REC	E 200 A MCB METER D TYPE: NQO D DESCRIPTION C OTHER LTS	AREA WIRE AWG. 12	BRKR 20/1	PA PA CCT. NO. 1 3		BO DLTS: IASE: MIRE:	50.2 <b>DARC</b> 120/208 3 4 <b>KV/</b> B	) S(	C		MOUN LOCAT	TING: TION: WIRE AWG. 12	SURFACE WALL LOAD DESCRI OTHER LTS		LTS 5		4 2 1 2 3 3 3 4 4 4 1 1 3 6 4	REC 105 NW REC IT/EXT REC FACP REC 104 TOW REC CONF W REC CONF SE REC EWH-1 REC 106 BM REC BRK WALLS REC BRK CTR S REC 100 E REC RR S REC LOBBY REC VIC 1
MAIN FEED UARE LOA S REC	E 200 A MCB METER D TYPE: NQO D DESCRIPTION C OTHER LTS LTS	AREA WIRE AWG. 12 12	BRKR 20/1 20/1	PA PA CCT. NO. 1 3		BO DLTS: IASE: MIRE:	50.2 <b>DARC</b> 120/208 3 4 <b>KV/</b> B	) S(	C	CC1 NO 2 4	MOUN LOCAT BRKR 20/1 20/1	TING: TION: WRE AWG. 12 12	SURFACE WALL LOAD DESCRI OTHER LTS LTS EXT		LTS 5		4 2 1 2 3 3 3 4 4 4 1 1 3 6 4 4 4 4 4	REC 105 NW REC IT/EXT REC FACP REC 104 TOW REC CONF W REC CONF SE REC EWH-1 REC 106 BM REC BRK WALLS REC BRK CTR S REC BRK CTR S REC 100 E REC RR S REC LOBBY REC VIC 1 REC VIC 2
MAIN FEED UARE LOA S REC	I: 200 A MCB I: METER D TYPE: NQO D DESCRIPTION C OTHER LTS LTS PANEL V	AREA AWIRE AWG. 12 12 3	BRKR 20/1 100/2	EMAN P. CCT. NO. 1 3 5	D AMPS	BC DLTS: HASE: WIRE: 0.5	50.2 <b>DARC</b> 120/208 3 4 <b>KV/</b> B	) S(	C	CC1 NO 2 4 .5 6	MOUN LOCAT BRKR 20/1 20/1 20/1 20/1	TING: TION: WRE AWG. 12 12 12	SURFACE WALL LOAD DESCRI OTHER LTS LTS EXT SPARE	REC	LTS 5		4 2 1 2 3 3 3 4 4 4 1 1 3 6 4 4 4 4 4 4	REC 105 NW REC IT/EXT REC FACP REC 104 TOW REC CONF W REC CONF SE REC EWH-1 REC 106 BM REC BRK WALLS REC BRK CTR S REC 100 E REC RR S REC LOBBY REC VIC 1 REC VIC 2 REC VIC 3
MAIN FEED QUARE LOA IS REC 0	I: 200 A MCB I: METER D TYPE: NQO D DESCRIPTION C OTHER LTS LTS PANEL V 	AREA WIRE AWG. 12 12 3 3 3	BRKR 20/1 100/2 	EMAN P. CCT. NO. 1 3 5 7	D AMPS	BC DLTS: HASE: WIRE: 0.5	50.2 <b>ARC</b> 120/208 3 4 <b>KV/</b> <b>B</b> 1.0	) S(	C 2.8 0	CCT NO 2 4 .5 6 8	MOUN LOCAT BRKR 20/1 20/1 20/1 20/1 20/1	TING: TION: WRE AWG. 12 12 12 12 12	SURFACE WALL LOAD DESCRI OTHER LTS LTS EXT SPARE REC N	REC	LTS 5		4 2 1 2 3 3 3 4 4 4 1 1 3 6 4 4 4 4 4 4	REC 105 NW REC IT/EXT REC FACP REC 104 TOW REC CONF W REC CONF SE REC EWH-1 REC 106 BM REC BRK WALLS REC BRK WALLS REC BRK CTR S REC 100 E REC RR S REC LOBBY REC LOBBY REC VIC 1 REC VIC 2 REC VIC 3 REC
MAIN FEED QUARE LOA TS REC 0 0 0	E 200 A MCB METER D TYPE: NQO D DESCRIPTION C OTHER LTS LTS PANEL V  REC S	AREA AWG. 12 12 3 3 12	BRKR 20/1 20/1 100/2  20/1	EMAN P. CCT. NO. 1 3 5 7 9	D AMPS	BC DLTS: HASE: WIRE: 0.5	50.2 <b>ARC</b> 120/208 3 4 <b>KV/</b> <b>B</b> 1.0	) S(	C 2.8 0	CC1 NO 2 4 .5 6 8 10	MOUN LOCAT BRKR 20/1 20/1 20/1 20/1 20/1 20/1 20/1	TING: TION: WIRE AWG. 12 12 12 12 12 12 12	SURFACE WALL LOAD DESCRI OTHER LTS LTS EXT SPARE REC N OH DOOR	REC	LTS 5		4 2 1 2 3 3 3 4 4 4 1 1 3 6 4 4 4 4 4 4	REC 105 NW REC IT/EXT REC FACP REC 104 TOW REC CONF W REC CONF SE REC EWH-1 REC 106 BM REC BRK WALLS REC BRK CTR S REC BRK CTR S REC 100 E REC RR S REC LOBBY REC VIC 1 REC VIC 2 REC VIC 3 REC VIC 3 REC FU-1
MAIN FEED UARE LOA S REC D D 5 0	E 200 A MCB METER D TYPE: NQO D DESCRIPTION C OTHER LTS LTS PANEL V  REC S SPARE SPARE	AREA WIRE AWG. 12 12 3 3 3 12 12 12	NEC DI BRKR 20/1 20/1 100/2  20/1 20/1	EMAN P. CCT. NO. 1 3 5 7 9 11	D AMPS	BC DLTS: IASE: WIRE: 0.5	50.2 <b>ARC</b> 120/208 3 4 <b>KV/</b> <b>B</b> 1.0	) S(	C 2.8 0	CCT NO 2 4 .5 6 8 10 .6 12	MOUN LOCAT BRKR 20/1 20/1 20/1 20/1 20/1 20/1 20/1	TING: TION: WRE AWG. 12 12 12 12 12 12 12 12	SURFACE WALL COAD DESCRI OTHER LTS LTS EXT SPARE REC N OH DOOR OH DOOR	REC	LTS 5		4 2 1 2 3 3 3 4 4 4 1 1 3 6 4 4 4 4 4 4	REC 105 NW REC IT/EXT REC FACP REC 104 TOW REC CONF W REC CONF SE REC EWH-1 REC 106 BM REC BRK WALLS REC BRK CTR S REC BRK CTR S REC 100 E REC RR S REC LOBBY REC VIC 1 REC VIC 1 REC VIC 2 REC VIC 3 REC VIC 3 REC FU-1 FU-2
MAIN FEED QUARE LOA S REC 0 0 0 5 0 0	E: 200 A MCB E: METER D TYPE: NQO D DESCRIPTION C OTHER LTS LTS PANEL V  REC S SPARE SPARE SPARE	AREA AWG. 12 12 3 3 12 12 12 12 12	NEC DI BRKR 20/1 20/1 100/2  20/1 20/1 20/1 20/1	EMAN P. CCT. NO. 1 3 5 7 9 11 13	D AMPS	BC DLTS: IASE: WIRE: 0.5	50.2 <b>DARC</b> 120/208 3 4 <b>KV/</b> <b>B</b> 1.0 0.9	) S( 0.3 1.6	C 2.8 0 0.5 1	CCT NO 2 4 .5 6 8 10 .6 12 14	MOUN LOCAT 20/1 20/1 20/1 20/1 20/1 20/1 20/1 20/1	TING: TION: WIRE AWG. 12 12 12 12 12 12 12 12 12 12	SURFACE WALL LOAD DESCRI OTHER LTS LTS EXT SPARE REC N OH DOOR OH DOOR SPARE	REC	LTS 5		4 2 1 2 3 3 3 4 4 4 1 1 3 6 4 4 4 4 4 4	REC 105 NW REC IT/EXT REC FACP REC 104 TOW REC CONF W REC CONF SE REC EWH-1 REC 106 BM REC BRK WALLS REC BRK CTR S REC BRK CTR S REC 100 E REC RR S REC LOBBY REC VIC 1 REC VIC 1 REC VIC 2 REC VIC 3 REC VIC 3 REC FU-1 FU-2 FU-3
MAIN FEED QUARE LOA S REC 0 0 5 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	E: 200 A MCB E: METER D TYPE: NQO D DESCRIPTION C OTHER LTS LTS PANEL V  REC S SPARE SPARE SPARE SPARE	AREA AWG. 12 12 12 3 3 12 12 12 12 12 12 12	NEC DI BRKR 20/1 20/1 100/2  20/1 20/1 20/1 20/1 20/1	EMAN P CCT. NO. 1 3 5 7 9 11 13 15	D AMPS	BC DLTS: IASE: WIRE: 0.5	50.2 <b>DARC</b> 120/208 3 4 <b>KV/</b> <b>B</b> 1.0 0.9	) S( 0.3 1.6	C 2.8 0 0.5 1	CCT NO 2 4 .5 6 8 10 .6 12 14 16	MOUN LOCAT BRKR 20/1 20/1 20/1 20/1 20/1 20/1 20/1 20/1	TING: TION: MRE AWG. 12 12 12 12 12 12 12 12 12 12 12	SURFACE WALL UOAD DESCRI OTHER LTS LTS EXT SPARE REC N OH DOOR OH DOOR SPARE OH DOOR	REC	LTS 5		4 2 1 2 3 3 3 4 4 4 1 1 3 6 4 4 4 4 4 4	REC 105 NW REC IT/EXT REC FACP REC 104 TOW REC CONF W REC CONF SE REC EWH-1 REC 106 BM REC BRK WALLS REC BRK WALLS REC BRK CTR S REC 100 E REC RR S REC 100 E REC RR S REC LOBBY REC VIC 1 REC VIC 2 REC VIC 3 REC VIC 3 REC VIC 3 FU-1 FU-2 FU-3 FU-4
MAIN FEED QUARE LOA S REC 0 0 0 5 5 0 0 0 0 0 0 0 0 0 0 0 0 0 0	E: 200 A MCB METER D TYPE: NQO D DESCRIPTION C OTHER LTS PANEL V  REC S SPARE SPARE SPARE SPARE SPARE	AREA AREA MIRE AWG. 12 12 12 3 3 12 12 12 12 12 12 12 12	NEC DI BRKR 20/1 20/1 100/2  20/1 20/1 20/1 20/1 20/1 20/1	EMAN P CCT. NO. 1 3 5 7 9 11 13 15 17	D AMPS	BO DLTS: HASE: MIRE: 0.5	50.2 <b>DARC</b> 120/208 3 4 <b>KV/</b> <b>B</b> 1.0 0.9	) S( 0.3 1.6	C 2.8 0 0.5 1	CCT NO 2 4 .5 6 8 10 .6 12 14 16 .6 18	MOUN LOCAT 20/1 20/1 20/1 20/1 20/1 20/1 20/1 20/1	TING: TION: MRE AWG. 12 12 12 12 12 12 12 12 12 12 12 12 12	SURFACE WALL UOAD DESCRI OTHER LTS LTS EXT SPARE REC N OH DOOR OH DOOR SPARE OH DOOR OH DOOR	REC	LTS 5		4 2 1 2 3 3 3 4 4 4 1 1 3 6 4 4 4 4 4 4	REC 105 NW REC IT/EXT REC FACP REC 104 TOW REC CONF W REC CONF SE REC EWH-1 REC 106 BM REC BRK WALLS REC BRK CTR S REC BRK CTR S REC 100 E REC RR S REC LOBBY REC VIC 1 REC VIC 2 REC VIC 3 REC VIC 3 REC VIC 3 REC VIC 3 FU-1 FU-2 FU-3 FU-4 PANEL R
MAIN FEED QUARE LOA TS REC 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	E: 200 A MCB METER D TYPE: NQO D DESCRIPTION C OTHER LTS LTS PANEL V  REC S SPARE SPARE SPARE SPARE SPARE	AREA AWG. 12 12 12 3 3 12 12 12 12 12 12 12 12 12 12 12	BRKR 20/1 20/1 20/1 20/1 20/1 20/1 20/1 20/1	EMAN P CCT. NO. 1 3 5 7 9 11 13 15 17 19	D AMPS	BC DLTS: HASE: WIRE: 0.5	50.2 <b>DARC</b> 120/208 3 4 <b>KV/</b> <b>B</b> 1.0 0.9 0.5	) S( ) 1.6	C 2.8 0 0.5 1 0.5 1	CCT NO 2 4 .5 6 10 .6 12 14 16 .6 18 20	MOUN LOCAT BRKR 20/1 20/1 20/1 20/1 20/1 20/1 20/1 20/1	TING: TION: TION: MRE AWG. 12 12 12 12 12 12 12 12 12 12 12 12 12	SURFACE WALL UOAD DESCRI OTHER LTS LTS EXT SPARE REC N OH DOOR OH DOOR SPARE OH DOOR OH DOOR OH DOOR SPARE	REC	LTS 5		4 2 1 2 3 3 3 4 4 4 1 1 3 6 4 4 4 4 4 4	REC 105 NW REC IT/EXT REC FACP REC 104 TOW REC CONF W REC CONF SE REC EWH-1 REC 106 BM REC BRK WALLS REC BRK WALLS REC BRK CTR S REC 100 E REC RR S REC 100 E REC RR S REC LOBBY REC VIC 1 REC VIC 2 REC VIC 3 REC VIC 3 REC VIC 3 FU-1 FU-2 FU-3 FU-4 PANEL R
MAIN FEED QUARE LOA TS REC 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	E 200 A MCB METER D TYPE: NQO D DESCRIPTION C OTHER LTS LTS PANEL V  REC S SPARE SPARE SPARE SPARE SPARE SPARE SPARE SPARE SPARE SPARE	AREA AWIRE AWG. 12 12 12 3 3 12 12 12 12 12 12 12 12 12 12 12 12 12	NEC DI BRKR 20/1 20/1 20/1 20/1 20/1 20/1 20/1 20/1	EMAN P CCT. NO. 1 3 5 7 9 11 13 15 17 19 21 23 25	D AMPS	BO DLTS: HASE: MIRE: 0.5	50.2 <b>ARC</b> 120/208 3 4 <b>KV/</b> B 1.0 0.9 0.5 0.5	) S( ) .3 1.6 1.6	C 2.8 0 0.5 1 0.5 1	CCT NO 2 4 .5 6 8 10 .6 12 14 16 .6 18 20 22 .5 24 26	MOUN LOCAT BRKR 20/1 20/1 20/1 20/1 20/1 20/1 20/1 20/1	TING: TION: TION: WIRE AWG. 12 12 12 12 12 12 12 12 12 12 12 12 12	SURFACE WALL UAD DESCRI OTHER LTS LTS EXT SPARE REC N OH DOOR OH DOOR OH DOOR SPARE OH DOOR OH DOOR SPARE SPARE SPARE WEF-1 WEF-2	6	LTS 5		4 2 3 3 3 4 4 4 1 1 3 6 4 4 4 4 4 4 4 4 4	REC 105 NW REC IT/EXT REC FACP REC 104 TOW REC CONF W REC CONF SE REC EWH-1 REC 106 BM REC BRK WALLS REC BRK WALLS REC BRK CTR S REC 106 BM REC BRK CTR S REC 100 E REC RR S REC LOBBY REC VIC 1 REC VIC 2 REC VIC 3 REC VIC 3 REC VIC 3 REC VIC 3 FU-1 FU-2 FU-3 FU-3 FU-4 PANEL R  REC 105 PRN 4 REC 105 PRN 5
MAIN FEED QUARE LOA S REC 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	E 200 A MCB METER D TYPE: NQO D DESCRIPTION C OTHER LTS LTS PANEL V  REC S SPARE	AREA AWG. 12 12 12 12 12 12 12 12 12 12 12 12 12	NEC DI BRKR 20/1 20/1 20/1 20/1 20/1 20/1 20/1 20/1	EMAN P P CCT. NO. 1 3 5 7 9 11 13 15 17 19 21 23 25 27	D AMPS	BC DLTS: HASE: WIRE: 0.5	50.2 <b>DARC</b> 120/208 3 4 <b>KV/</b> <b>B</b> 1.0 0.9 0.5	) S( ) 1.6	C 2.8 0 0.5 1 0.5 1 0.5 0	CCT NO 2 4 .5 6 8 10 .6 12 14 16 .6 18 20 22 .5 24 26 28	MOUN LOCAT BRKR 20/1 20/1 20/1 20/1 20/1 20/1 20/1 20/1	TING: TION: TION: WIRE AWG. 12 12 12 12 12 12 12 12 12 12 12 12 12	SURFACE WALL UOAD DESCRI OTHER LTS LTS EXT SPARE REC N OH DOOR OH DOOR OH DOOR SPARE OH DOOR OH DOOR SPARE SPARE SPARE SPARE WEF-1	6	LTS 5		4 2 1 2 3 3 4 4 4 1 1 3 6 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4	REC 105 NW REC IT/EXT REC FACP REC 104 TOW REC CONF W REC CONF SE REC EWH-1 REC 106 BM REC BRK WALLS REC BRK CTR S REC BRK CTR S REC 100 E REC RR S REC LOBBY REC VIC 1 REC VIC 2 REC VIC 3 REC VIC 3 REC VIC 3 REC VIC 3 REC VIC 3 FU-1 FU-2 FU-3 FU-3 FU-4 PANEL R  REC 105 PRN 4 REC 105 PRN 5 REC 105 PRN 6
MAIN FEED LOA S REC 0 0 5 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	E 200 A MCB METER D TYPE: NQO D DESCRIPTION C OTHER LTS LTS PANEL V  REC S SPARE SPARE SPARE SPARE SPARE SPARE SPARE SPARE SPARE SPARE SPARE SPARE SPARE SPARE SPARE SPARE SPARE	AREA AWIRE AWG. 12 12 12 3 3 12 12 12 12 12 12 12 12 12 12 12 12 12	NEC DI BRKR 20/1 20/1 20/1 20/1 20/1 20/1 20/1 20/1	EMAN P P CCT. NO. 1 3 5 7 9 11 13 5 7 9 11 13 15 17 19 21 23 25 27 29	D AMPS	BC DLTS: IASE: MIRE: 0.5 0.5	50.2 <b>ARC</b> 120/208 3 4 <b>KV/</b> B 1.0 0.9 0.5 0.5	) S( ) .3 1.6 1.6	C 2.8 0 0.5 1 0.5 1 0.5 0	CCT NO 2 4 .5 6 8 10 .6 12 14 16 .6 18 20 22 .5 24 26 28 .5 30	MOUN LOCAT 20/1 20/1 20/1 20/1 20/1 20/1 20/1 20/1	TING: TION: TION: WIRE AWG. 12 12 12 12 12 12 12 12 12 12 12 12 12	SURFACE WALL UAD DESCRI OTHER LTS LTS EXT SPARE REC N OH DOOR OH DOOR OH DOOR SPARE OH DOOR OH DOOR SPARE SPARE SPARE WEF-1 WEF-2 AIR COMPRESSO	6	LTS 5		4 2 3 3 3 4 4 4 1 1 3 6 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4	REC 105 NW REC IT/EXT REC FACP REC 104 TOW REC CONF W REC CONF SE REC EWH-1 REC 106 BM REC BRK WALLS REC BRK WALLS REC BRK CTR S REC 106 BM REC BRK CTR S REC 100 E REC RR S REC LOBBY REC VIC 1 REC VIC 2 REC VIC 3 REC VIC 3 REC VIC 3 REC VIC 3 REC VIC 3 FU-1 FU-2 FU-3 FU-3 FU-4 PANEL R  REC 105 PRN 4 REC 105 PRN 6 REC 105 PRN 6
MAIN FEED QUARE LOA IS REC 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	E 200 A MCB METER D TYPE: NQO D DESCRIPTION C OTHER LTS LTS PANEL V  REC S SPARE	AREA AWG. 12 12 12 12 12 12 12 12 12 12 12 12 12	NEC DI BRKR 20/1 20/1 20/1 20/1 20/1 20/1 20/1 20/1	EMAN P P CCT. NO. 1 3 5 7 9 11 13 5 7 9 11 13 15 17 19 21 23 25 27 29 31	D AMPS	BC DLTS: HASE: WIRE: 0.5	50.2 <b>ARC</b> 120/208 3 4 <b>KV/</b> <b>B</b> 1.0 0.9 0.5 0.5 1.0	) S( ) .3 1.6 1.5	C 2.8 0 0.5 1 0.5 1 0.5 0	CCT NO. 2 4 5 6 10 .6 12 14 16 .6 18 20 22 .5 24 26 28 .5 30 32	MOUN LOCAT 20/1 20/1 20/1 20/1 20/1 20/1 20/1 20/1	TING: TION: TION: WIRE AWG. 12 12 12 12 12 12 12 12 12 12 12 12 12	SURFACE WALL UALD UALD UTHER UTS UTS EXT SPARE REC N OH DOOR OH DOOR OH DOOR SPARE OH DOOR SPARE OH DOOR SPARE SPARE WEF-1 WEF-2 AIR COMPRESSO  SPARE	6	LTS 5		4 2 1 2 3 3 4 4 4 1 1 3 6 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4	REC 105 NW REC IT/EXT REC FACP REC 104 TOW REC CONF W REC CONF SE REC EWH-1 REC 106 BM REC BRK WALLS REC BRK CTR S REC BRK CTR S REC 100 E REC RR S REC LOBBY REC VIC 1 REC VIC 2 REC VIC 3 REC VIC 3 REC VIC 3 REC VIC 3 REC VIC 3 FU-1 FU-2 FU-3 FU-3 FU-4 PANEL R  REC 105 PRN 4 REC 105 PRN 5 REC 105 PRN 6
MAIN FEED QUARE LOA IS REC 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	E 200 A MCB METER D TYPE: NQO D DESCRIPTION C OTHER LTS LTS PANEL V  REC S SPARE SPARE SPARE SPARE SPARE SPARE SPARE SPARE SPARE SPARE SPARE SPARE SPARE SPARE SPARE SPARE SPARE	AREA WIRE AWG. 12 12 12 3 3 12 12 12 12 12 12 12 12 12 12 12 12 12	NEC DI BRKR 20/1 20/1 20/1 20/1 20/1 20/1 20/1 20/1	EMAN P CCT. NO. 1 3 5 7 9 11 13 5 7 9 11 13 15 17 19 21 23 25 27 29 31 33	D AMPS	BC DLTS: IASE: MIRE: 0.5 0.5	50.2 <b>ARC</b> 120/208 3 4 <b>KV/</b> B 1.0 0.9 0.5 0.5	) S( ) .3 1.6 1.6	C 2.8 0 0.5 1 0.5 1 0.5 1	CCT NO 2 4 .5 6 8 10 .6 12 14 16 .6 18 20 22 .5 24 26 28 .5 30 32 34	MOUN LOCAT 20/1 20/1 20/1 20/1 20/1 20/1 20/1 20/1	TING: TION: TION: WRE AWG. 12 12 12 12 12 12 12 12 12 12 12 12 12	SURFACE WALL UALD UALD UTHER UTS UTS EXT SPARE REC N OH DOOR OH DOOR OH DOOR OH DOOR SPARE OH DOOR OH DOOR SPARE SPARE WEF-1 WEF-2 AIR COMPRESSO  SPARE SPARE	6	LTS 5		4 2 1 2 3 3 4 4 4 1 1 3 6 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4	REC 105 NW REC IT/EXT REC FACP REC 104 TOW REC CONF W REC CONF SE REC EWH-1 REC 106 BM REC BRK WALLS REC BRK WALLS REC BRK CTR S REC 106 BM REC BRK CTR S REC 100 E REC RR S REC LOBBY REC VIC 1 REC VIC 2 REC VIC 3 REC VIC 3 REC VIC 3 REC VIC 3 REC VIC 3 FU-1 FU-2 FU-3 FU-3 FU-4 PANEL R  REC 105 PRN 4 REC 105 PRN 6 REC 105 PRN 6
MAIN FEED QUARE LOA TS REC 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	E 200 A MCB METER D TYPE: NQO D DESCRIPTION C OTHER LTS LTS PANEL V  REC S SPARE	AREA AWG. 12 12 12 12 12 12 12 12 12 12 12 12 12	NEC DI BRKR 20/1 20/1 20/1 20/1 20/1 20/1 20/1 20/1	EMAN P P CCT. NO. 1 3 5 7 9 11 13 5 7 9 11 13 15 17 19 21 23 25 27 29 31 33 35	D AMPS	BO DLTS: HASE: MRE: 0.5 0.5 0.5	50.2 <b>ARC</b> 120/208 3 4 <b>KV/</b> <b>B</b> 1.0 0.9 0.5 0.5 1.0	) S( ) .3 1.6 1.5	C 2.8 0 0.5 1 0.5 1 0.5 1	CCT NO 2 4 .5 6 8 10 .6 12 14 16 .6 18 20 22 .5 24 26 28 .5 30 32 34 .5 36	MOUN LOCAT 20/1 20/1 20/1 20/1 20/1 20/1 20/1 20/1	TING: TION: WIRE AWG. 12 12 12 12 12 12 12 12 12 12	SURFACE WALL UALD UALD UALD UALD UALD UALD UALD U	6	LTS 5		4 2 1 2 3 3 4 4 4 1 1 3 6 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4	REC 105 NW REC IT/EXT REC FACP REC 104 TOW REC CONF W REC CONF SE REC EWH-1 REC 106 BM REC BRK WALLS REC BRK WALLS REC BRK CTR S REC 100 E REC RR S REC 100 E REC VIC 1 REC VIC 2 REC VIC 2 REC VIC 3 REC VIC 3 REC VIC 3 REC VIC 3 REC VIC 3 FU-1 FU-2 FU-3 FU-3 FU-4 PANEL R  REC 105 PRN 4 REC 105 PRN 5 REC 105 PRN 6 REC 105 PRN 7 PANEL S 
MAIN FEED QUARE LOA IS REC 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	E 200 A MCB METER D TYPE: NQO D DESCRIPTION C OTHER LTS LTS PANEL V  REC S SPARE	AREA AWG. 12 12 12 12 12 12 12 12 12 12 12 12 12	NEC DI BRKR 20/1 20/1 20/1 20/1 20/1 20/1 20/1 20/1	EMAN P CCT. NO. 1 3 5 7 9 11 13 5 7 9 11 13 15 17 19 21 23 25 27 29 31 33 35 37	D AMPS	BC DLTS: IASE: MIRE: 0.5 0.5	50.2 <b>DARC</b> 120/208 3 4 <b>KV/</b> <b>B</b> 1.0 0.9 0.5 0.5 1.0 0.0	) S( ) .3 1.6 1.6 1.5 0.5	C 2.8 0 0.5 1 0.5 1 0.5 1	CCT NO 2 4 .5 6 8 10 .6 12 14 16 .6 18 20 22 .5 24 26 28 .5 30 32 34 .5 36 38	MOUN LOCAT 20/1 20/1 20/1 20/1 20/1 20/1 20/1 20/1	TING: TION: WRE AWG. 12 12 12 12 12 12 12 12 12 12	SURFACE WALL UALL UALD UTHER UTS UTS UTS EXT SPARE OH DOOR OH DOOR OH DOOR OH DOOR SPARE OH DOOR OH DOOR SPARE SPARE WEF-1 WEF-2 AIR COMPRESSO  SPARE SPARE SPARE SPARE SPARE SPARE SPARE	6	LTS 5		4 2 1 2 3 3 4 4 4 1 1 3 6 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4	REC 105 NW REC IT/EXT REC FACP REC 104 TOW REC CONF W REC CONF SE REC EWH-1 REC 106 BM REC BRK WALLS REC BRK WALLS REC BRK CTR S REC 100 E REC RR S REC 100 E REC VIC 1 REC VIC 2 REC VIC 2 REC VIC 3 REC VIC 3 REC VIC 3 REC VIC 3 FU-1 FU-2 FU-3 FU-3 FU-4 PANEL R  REC 105 PRN 4 REC 105 PRN 4 REC 105 PRN 5 REC 105 PRN 5 REC 105 PRN 7 PANEL S  GUARD SHACK
MAIN FEED UARE LOA S REC 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	E 200 A MCB METER D TYPE: NQO D DESCRIPTION C OTHER LTS LTS PANEL V  REC S SPARE	AREA WIRE AWG. 12 12 12 12 12 12 12 12 12 12	NEC DI BRKR 20/1 20/1 20/1 20/1 20/1 20/1 20/1 20/1	EMAN P CCT. NO. 1 3 5 7 9 11 13 5 7 9 11 13 15 17 19 21 23 25 27 29 31 33 35 37 39	D AMPS	BO DLTS: HASE: MRE: 0.5 0.5 0.5	50.2 <b>ARC</b> 120/208 3 4 <b>KV/</b> <b>B</b> 1.0 0.9 0.5 0.5 1.0	) S( ) .3 1.6 1.5	C 2.8 0 0.5 1 0.5 1 0.5 0 0.5 1 0.0 0	CCT NO. 2 4 .5 6 8 10 .6 12 14 16 .6 18 20 22 .5 24 26 28 .5 24 26 28 .5 30 32 34 .5 36 38 40	MOUN LOCAT 20/1 20/1 20/1 20/1 20/1 20/1 20/1 20/1	TING: TION: WRE AWG. 12 12 12 12 12 12 12 12 12 12	SURFACE WALL UALD SURFACE WALL UTS UTHER LTS LTS EXT SPARE OH DOOR OH DOOR OH DOOR OH DOOR OH DOOR SPARE OH DOOR OH DOOR SPARE SPARE SPARE SPARE SPARE SPARE SPARE SPARE SPARE SPARE SPARE SPARE SPARE SPARE SPARE	6	LTS 5		4 2 1 2 3 3 4 4 4 1 1 3 6 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4	REC 105 NW REC IT/EXT REC FACP REC 104 TOW REC CONF W REC CONF SE REC EWH-1 REC 106 BM REC BRK WALLS REC BRK WALLS REC BRK CTR S REC 100 E REC RR S REC 100 E REC VIC 1 REC VIC 2 REC VIC 2 REC VIC 3 REC VIC 3 REC VIC 3 REC VIC 3 FU-1 FU-2 FU-3 FU-3 FU-4 PANEL R  REC 105 PRN 4 REC 105 PRN 5 REC 105 PRN 5 REC 105 PRN 6 REC 105 PRN 7 PANEL S  GUARD SHACK
MAIN FEED UARE LOA S REC 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	E 200 A MCB METER D TYPE: NQO D DESCRIPTION C OTHER LTS LTS PANEL V  REC S SPARE	AREA AWG. 12 12 12 12 12 12 12 12 12 12 12 12 12	NEC DI BRKR 20/1 20/1 20/1 20/1 20/1 20/1 20/1 20/1	EMAN P CCT. NO. 1 3 5 7 9 11 13 5 7 9 11 13 15 17 19 21 23 25 27 29 31 33 35 37	D AMPS	BO DLTS: HASE: MRE: 0.5 0.5 0.5	50.2 <b>DARC</b> 120/208 3 4 <b>KV/</b> <b>B</b> 1.0 0.9 0.5 0.5 1.0 0.5	) S( ) ( ) ( ) ( ) ( ) ( ) ( ) ( ) ( ) ( )	C 2.8 0 0.5 1 0.5 1 0.5 0 0.5 1 0.0 0	CCT NO 2 4 .5 6 8 10 .6 12 14 16 .6 18 20 22 .5 24 26 28 .5 30 32 34 .5 36 38	MOUN LOCAT 20/1 20/1 20/1 20/1 20/1 20/1 20/1 20/1	TING: TION: WRE AWG. 12 12 12 12 12 12 12 12 12 12	SURFACE WALL UALL UALD UTHER UTS UTS UTS EXT SPARE OH DOOR OH DOOR OH DOOR OH DOOR SPARE OH DOOR OH DOOR SPARE SPARE WEF-1 WEF-2 AIR COMPRESSO  SPARE SPARE SPARE SPARE SPARE SPARE SPARE	6	LTS 5		4 2 1 2 3 3 4 4 4 1 1 3 6 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4	REC 105 NW REC IT/EXT REC FACP REC 104 TOW REC CONF W REC CONF SE REC EWH-1 REC 106 BM REC BRK WALLS REC BRK WALLS REC BRK CTR S REC 100 E REC RR S REC 100 E REC VIC 1 REC VIC 2 REC VIC 2 REC VIC 3 REC VIC 3 REC VIC 3 REC VIC 3 FU-1 FU-2 FU-3 FU-3 FU-4 PANEL R  REC 105 PRN 4 REC 105 PRN 4 REC 105 PRN 5 REC 105 PRN 5 REC 105 PRN 7 PANEL S  GUARD SHACK
MAIN FEED QUARE LOA TS REC 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	E 200 A MCB METER D TYPE: NQO D DESCRIPTION C OTHER LTS LTS PANEL V  REC S SPARE	AREA WIRE AWG. 12 12 12 12 12 12 12 12 12 12	NEC DI BRKR 20/1 20/1 20/1 20/1 20/1 20/1 20/1 20/1	EMAN P CCT. NO. 1 3 5 7 9 11 13 5 7 9 11 13 15 17 19 21 23 25 27 29 31 33 35 37 39	D AMPS	BC DLTS: HASE: MRE: 0.5 0.5 0.5 0.5 0.5	50.2 <b>DARC</b> 120/208 3 4 <b>KV/</b> <b>B</b> 1.0 0.9 0.5 0.5 1.0 0.0	) SC ) SC 1.5 0.5 1.5 0.5 LS 6.5	C 2.8 0 0.5 1 0.5 1 0.5 0 0.5 0 0.5 0	CCT NO. 2 4 .5 6 8 10 .6 12 14 16 .6 18 20 22 .5 24 26 28 .5 24 26 28 .5 30 32 34 .5 36 38 40	MOUN LOCAT 20/1 20/1 20/1 20/1 20/1 20/1 20/1 20/1	TING: TION: WRE AWG. 12 12 12 12 12 12 12 12 12 12	SURFACE WALL UALD SURFACE WALL UTS UTHER LTS LTS EXT SPARE OH DOOR OH DOOR OH DOOR OH DOOR OH DOOR SPARE OH DOOR OH DOOR SPARE SPARE SPARE SPARE SPARE SPARE SPARE SPARE SPARE SPARE SPARE SPARE SPARE SPARE SPARE	6	LTS 5		4 2 1 2 3 3 4 4 4 1 1 3 6 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4	REC 105 NW REC IT/EXT REC FACP REC 104 TOW REC CONF W REC CONF SE REC EWH-1 REC 106 BM REC BRK WALLS REC BRK WALLS REC BRK CTR S REC 100 E REC RR S REC 100 E REC VIC 1 REC VIC 2 REC VIC 2 REC VIC 3 REC VIC 3 REC VIC 3 REC VIC 3 FU-1 FU-2 FU-3 FU-3 FU-4 PANEL R  REC 105 PRN 4 REC 105 PRN 5 REC 105 PRN 5 REC 105 PRN 6 REC 105 PRN 7 PANEL S  GUARD SHACK
MAIN FEED QUARE LOA TS REC 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	E 200 A MCB METER D TYPE: NQO D DESCRIPTION C OTHER LTS LTS PANEL V  REC S SPARE	AREA WIRE AWG. 12 12 12 12 12 12 12 12 12 12 12 12 12	NEC DI BRKR 20/1 20/1 20/1 20/1 20/1 20/1 20/1 20/1	EMAN P CCT. NO. 1 3 5 7 9 11 13 5 7 9 11 13 15 17 19 21 23 25 27 29 31 33 35 37 39	D AMPS	BC DLTS: HASE: MRE: 0.5 0.5 0.5 0.5 0.5	50.2 DARC 120/208 3 4 KV/ B 1.0 0.9 0.5 0.5 1.0 0.5 1.0 0.5 1.0	) SC ) SC 1.5 0.5 1.5 0.5 LS 6.5	C 2.8 0 0.5 1 0.5 1 0.5 0 0.5 0 0.5 0 0.5 0	CCT NO. 2 4 .5 6 8 10 .6 12 14 16 .6 18 20 22 .5 24 26 28 .5 30 22 .5 24 26 28 .5 30 32 34 .5 36 38 40 .5 42	MOUN LOCAT 20/1 20/1 20/1 20/1 20/1 20/1 20/1 20/1	TING: TION: WRE AWG. 12 12 12 12 12 12 12 12 12 12	SURFACE WALL UALD SURFACE WALL UTS UTHER LTS LTS EXT SPARE OH DOOR OH DOOR OH DOOR OH DOOR OH DOOR SPARE OH DOOR OH DOOR SPARE SPARE SPARE SPARE SPARE SPARE SPARE SPARE SPARE SPARE SPARE SPARE SPARE SPARE SPARE	6	LTS 5		4 2 1 2 3 3 4 4 4 1 1 3 6 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4	REC 105 NW REC IT/EXT REC FACP REC 104 TOW REC CONF W REC CONF SE REC EWH-1 REC 106 BM REC BRK WALLS REC BRK WALLS REC BRK CTR S REC 100 E REC RR S REC 100 E REC VIC 1 REC VIC 2 REC VIC 2 REC VIC 3 REC VIC 3 REC VIC 3 REC VIC 3 FU-1 FU-2 FU-3 FU-3 FU-4 PANEL R  REC 105 PRN 4 REC 105 PRN 5 REC 105 PRN 5 REC 105 PRN 6 REC 105 PRN 7 PANEL S  GUARD SHACK
MAIN FEED QUARE LOA TS REC 10 10 10 10 10 10 10 10 10 10 10 10 10	E 200 A MCB METER D TYPE: NQO D DESCRIPTION C OTHER LTS LTS PANEL V  REC S SPARE	AREA WIRE AWG. 12 12 12 12 12 12 12 12 12 12 12 12 12	NEC DI BRKR 20/1 20/1 20/1 20/1 20/1 20/1 20/1 20/1	EMAN P P CCT. NO. 1 3 5 7 9 11 13 5 7 9 11 13 15 17 19 21 23 25 27 29 31 33 35 37 39 41	D AMPS	BC DLTS: HASE: MRE: 0.5 0.5 0.5 0.5 0.5	50.2 DARC 120/208 3 4 KV/ B 1.0 0.9 0.5 0.5 1.0 0.5 1.0 0.5 1.0	) S( ) S( ) 1.6 1.6 1.5 0.5 1.5 0.5	C 2.8 0 0.5 1 0.5 1 0.5 0 0.5 0 0.5 0 0.5 0	CCT NO. 2 4 .5 6 8 10 .6 12 14 16 .6 18 20 22 .5 24 26 28 .5 30 22 .5 24 26 28 .5 30 32 34 .5 36 38 40 .5 42	MOUN LOCAT 20/1 20/1 20/1 20/1 20/1 20/1 20/1 20/1	TING: TION: WRE AWG. 12 12 12 12 12 12 12 12 12 12	SURFACE WALL UALD SURFACE WALL UTS UTHER LTS LTS EXT SPARE OH DOOR OH DOOR OH DOOR OH DOOR OH DOOR SPARE OH DOOR OH DOOR SPARE SPARE SPARE SPARE SPARE SPARE SPARE SPARE SPARE SPARE SPARE SPARE SPARE SPARE SPARE	6	LTS 5		4 2 1 2 3 3 4 4 4 1 1 3 6 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4	REC 105 NW REC IT/EXT REC FACP REC 104 TOW REC CONF W REC CONF SE REC EWH-1 REC 106 BM REC BRK WALLS REC BRK WALLS REC BRK CTR S REC 100 E REC RR S REC 100 E REC VIC 1 REC VIC 2 REC VIC 2 REC VIC 3 REC VIC 3 REC VIC 3 REC VIC 3 FU-1 FU-2 FU-3 FU-3 FU-4 PANEL R  REC 105 PRN 4 REC 105 PRN 5 REC 105 PRN 5 REC 105 PRN 6 REC 105 PRN 7 PANEL S  GUARD SHACK
MAIN FEED QUARE LOA TS REC 10 10 10 10 10 10 10 10 10 10 10 10 10	E 200 A MCB METER D TYPE: NQO D DESCRIPTION C OTHER LTS LTS PANEL V  REC S SPARE	AREA WIRE AWG. 12 12 12 12 12 12 12 12 12 12 12 12 12	NEC DI BRKR 20/1 20/1 20/1 20/1 20/1 20/1 20/1 20/1	EMAN P P CCT. NO. 1 3 5 7 9 11 13 5 7 9 11 13 5 7 9 11 13 5 7 9 11 13 5 7 9 11 13 5 7 9 11 13 5 7 9 11 13 5 7 9 11 13 5 7 9 9 11 13 5 5 7 9 9 11 13 5 7 7 9 9 11 13 5 5 7 7 9 9 11 1 3 3 5 5 7 7 9 9 11 1 3 3 5 5 7 7 9 9 11 1 3 3 3 5 5 7 7 9 9 11 1 3 3 3 5 5 7 7 9 9 11 1 3 3 5 5 7 7 9 9 11 1 3 3 5 5 7 7 9 9 11 1 3 3 1 3 3 5 5 7 7 9 9 11 1 3 3 5 5 3 7 7 9 9 11 2 3 1 3 3 5 5 3 7 7 9 9 11 2 3 1 3 3 5 5 3 7 7 2 5 7 7 9 9 11 2 3 1 3 3 5 5 3 7 7 9 9 1 1 2 3 1 3 3 5 5 3 7 7 2 9 9 1 3 1 3 3 5 5 3 7 7 2 9 9 4 1 3 1 3 1 3 3 5 5 5 7 7 1 2 7 7 7 7 9 9 31 3 3 7 7 7 7 9 9 4 1 3 7 7 7 7 9 9 1 4 1 3 7 7 7 9 9 1 4 1 3 7 7 7 9 9 14 1 3 7 7 7 9 9 4 1 3 7 7 1 3 1 3 1 1 1 3 1 3 1 1 1 1 1 1	D AMPS	BC DLTS: JASE: MIRE: 0.5 0.5 0.5 0.5 0.5 0.5	50.2 <b>ARC</b> 120/208 3 4 KV/ B 1.0 0.9 0.5 0.5 1.0 0.5 1.0 0.5 TOTA 4.4 10.5	) SC ) SC 1.5 1.6 0.5 1.5 0.5 1.5 6.5 9	C 2.8 0 0.5 1 0.5 1 0.5 0 0.5 0 0.5 0 0.5 0	CCT NO. 2 4 .5 6 8 10 .6 12 14 16 .6 18 20 22 .5 24 26 28 .5 30 22 .5 24 26 28 .5 30 32 34 .5 36 38 40 .5 42	MOUN LOCAT 20/1 20/1 20/1 20/1 20/1 20/1 20/1 20/1	TING: TION: WRE AWG. 12 12 12 12 12 12 12 12 12 12	SURFACE WALL UALD SURFACE WALL UTS UTHER LTS LTS EXT SPARE OH DOOR OH DOOR OH DOOR OH DOOR OH DOOR SPARE OH DOOR OH DOOR SPARE SPARE SPARE SPARE SPARE SPARE SPARE SPARE SPARE SPARE SPARE SPARE SPARE SPARE SPARE	6	LTS 5		4 2 1 2 3 3 4 4 4 1 1 3 6 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4	REC 105 NW REC IT/EXT REC FACP REC 104 TOW REC CONF W REC CONF SE REC EWH-1 REC 106 BM REC BRK WALLS REC BRK WALLS REC BRK CTR S REC 100 E REC RR S REC 100 E REC VIC 1 REC VIC 2 REC VIC 2 REC VIC 3 REC VIC 3 REC VIC 3 REC VIC 3 FU-1 FU-2 FU-3 FU-3 FU-4 PANEL R  REC 105 PRN 4 REC 105 PRN 5 REC 105 PRN 5 REC 105 PRN 6 REC 105 PRN 7 PANEL S  GUARD SHACK



Greg Anderson, Engineer 9 WEST 26th CIRCLE Fayetteville, AR 72701 PHONE: 479-601-3331 EMAIL: ga@gaengr.com PROJECT # 20006

<b>er</b> 1 31 n							5003 OLD GREENWOOD RD, SUITE D - FT SMITH, AR 72903 DH: 476 404 1808 - WWW HILLEIDM NET	
	COMMENTS	CIVIL AN						
	DATE	08/11/20	09/02/20					
	#	-	7					
		Incurance Auto Auction Inc			Exington, South Carolina 29073			FERMIL - CONSTRUCTION DOCUMENTS
		Section 1		10. ( 10. ( 5) G	CA/ 55510 3788 /13/	POX 55 120 AIIII		
	P/ DAT	LEC ANE E: )5/1	LS	CH	EDU JO	B NO		
	SHE	ET:	E	. /	2.	3	3	

PA	NELBO	ARD SO	CHEDUL	Ε					
	VOLTS: 1	20/208			AIC RA	TING:	22000	•	
	PHASE:	3		MOUNTING:			SURFACE		
	WRE:	4			LOCAT	ION:	ELECT ROOM		
ССТ.		KVA		ССТ.		WIRE	LOAD DESCR		
NO.	Α	В		NO.	BRKR		OTHER	REC	
1	1.3 1.2			2	20/1	12	LTS CENTER		30

WIRE		CCT.			KV	A			CCT.		WIRE	LOAD DESCRIP	TION	1
AWG.	BRKR	NO.	A		E		С		NO.	BRKR	AWG.	OTHER	REC	
12	20/1	1	1.3	1.2					2	20/1	12	LTS CENTER		30
12	20/1	3			1.0	0.5			4	20/1	12	LTS SPARE		
12	20/1	5					1.0	0.5	6	20/1	12	SPARE		
12	20/1	7	0.5	0.7					8	20/1	12	<b>REC 105 E</b>	4	
12	20/1	9			0.7	0.7			10	20/1	12	<b>REC 105 NE</b>	4	
12	20/1	11					0.7	0.4	12	20/1	12	<b>REC 105 PRN 1</b>	2	
12	20/1	13	0.4	0.4					14	20/1	12	<b>REC 105 PRN 3</b>	2	
12	20/1	15			0.7	0.7			16	20/1	12	<b>REC 105 WC</b>	4	
12	20/1	17					0.7	0.9	18	20/1	12	<b>REC 105 E</b>	5	
12	20/1	19	0.4	0.4					20	20/1	12	REC IT N/W	2	
12	20/1	21			0.2	0.4			22	20/1	12	REC IT S/W	2	
12	20/1	23		L			0.4	1.1	24	20/1	12	REC 108 116	6	
12	20/1	25	0.5	0.5					26	20/1	12	REC CONF N	3	
12	20/1	27			0.5	0.5			28	20/1	12	REC CORR 108 W		
10	30/1	29			010	010	1.7	0.5	30	20/1	12	VENDING	•	
12	20/1	31	0.7	0.5		Ļ		0.5	32	20/1	12	VENDING		
100 A 4			0.7	0.5	0.7	0.2			Sector Ma	100-00-00-00			4	
12	20/1	33		L	0.7	0.2			34	20/1	12	REC BRK CTR N	1	
12	20/1	35				L	0.2	0.5	36	20/1	12	REC FRIDGE		
12	20/1	37	0.2	0.5					38	20/1	12	REC EWC		
12	20/1	39			0.5	0.7			40	20/1	12	REC YARD S	4	
12	20/1	41					1.1	1.1	42	20/1	12	REC YARD N	6	
12	20/1	43	0.7	0.5					44	20/1	12	SPARE		
12	20/1	45			0.7	0.5			46	20/1	12	SPARE		
12	20/1	47					0.7	1.8	48	30/3	10	CU-1		
12	20/1	49	0.7	1.8					50		10			
12	20/1	51			1.5	1.8			52		10			
12	20/1	53					1.5	1.8	54	30/3	10	CU-2		
12	20/1	55	1.5	1.8					56	· /	10			
12	20/1	57			1.5	1.8			58		10			
3/0	200/3	59					8.7	2.4	60	45/3	8	CU-3		
3/0		61	10.9	2.4					62		8			
3/0		63			12.0	2.4			64		8			
12	20/1	65		L			0.4	1.5	75755	20/2	12	MCU-1		-
12	20/1	67	0.4	1.5		L			68		12			
12	20/1	69			0.4	3.2			70	50/3	8	CU-4		<u> </u>
12	20/1	71			14		0.4	3.2	72		8			
3/0	200/3	73	5.4	3.2			~17	712	74		8			
3/0	200/3	75	514	512	5.4	0.0			76	100/3		SPD		
3/0		77		L	0.4	0.0	4.9	0.0						
	40/2	79	2.0	0.0		L	4.3	0.0						
6	40/2		2.0	0.0		0.5			80		40			
6		81			2.0	0.5			82	20/1	12	SPARE		
12	20/1	83					0.5	0.5	84	20/1	12	SPARE		
		Ē			TOT	202002 000								
		_	25.5	15.4		13.9	22.8	16.1						
			40.	9	41	.8	38.	9						
				F										
	TOTAL	CON	NECTED	KVA	121.6									
	MAX CONNECTED AMPS					8.0								
		NEC DEMAND AMPS												

CIVIL ENGINEERING ENVIRONMENTAL SURVEYING LANDSCAPE ARCHITECTURE GEOTECHNICAL

### ENVIRONMENTAL IMPACT STATEMENT

248 Stickles Pond Road Block 151 Lot 21 Andover Township, Sussex County,

New Jersey

Prepared For: BHT Properties Group 5081 SW 48<sup>th</sup> Street, 1023 Davie, Florida 33314

December 12, 2019 Revised January 26, 2021

Wayne Ingram, P.E., P.P., P.L.S New Jersey Professional Engineer License No. 24GB04258200



Headquarters 140 West Main Street | High Bridge, NJ 08829 T: 908.238.0544

Clinton | Asbury Park | Denville | Philadelphia



### TABLE OF CONTENTS

1.	Introduction	
2.	EXISTING ENVIRONMENTAL CONDITIONS	4
2.1	Phase I Environmental Site Assessment	4
2.2	Topography	4
2.3	Air Quality	
2.4	Noise Levels	
2.5	Water Supply And Water Quality	
2.6	Drainage	
2.7	Critical Impact Areas	
2.8	Sewer Systems And Utilities	
2.9	Geology	
2.10	Soils And Slope Stabilities	
2.11	Vegetation	
2.12	Land Use And Demography	
2.13	Aesthetics	
2.14	History	
3.	PROBABLE IMPACTS & MITIGATION	
3.1	Topography	
3.2	Air Quality	
3.3	Noise Levels	
3.4	Water Supply And Freshwater Wetlands Protection	
3.5	Drainage And Floodplain Protection	
3.6	Sewer Systems And Utilities	
3.7	Geology Stability	
3.8	Soil Stability And Erosion Control	
3.9	Vegetation	
3.10	Land Use And Demography	
3.11	Aesthetics	
3.12	History	
3.13	Displacement Of People And Businesses	
3.14	Marketability Of Proposed Use	
3.15	Disruption Of Desirable Community And Regional Growth	
3.16	Spill Protection Measures	
3.17	Police And Fire Protection And Emergency Health Services	10



3.1	8	Traffic	10
3.1	9	Solid Waste Generation and Disposal	10
3.2	20	Construction Impact	10
4.		ALTERNATIVES ANALYSIS	. 11
4.1	No	Build Option	. 11
4.2	2 Les	ss Intensive Option	. 11
4.3	s Mo	re Intensive Option	. 11
5.		LICENSES, PERMITS & APPROVALS	. 11
6.		DOCUMENTATION	. 11

### LIST OF APPENDICES

Appendix A: Preliminary & Final Site Plans (Attached Separately) Appendix B: Stormwater Management Report (Attached Separately)

### LIST OF FIGURES

Figure 1:USGS MapFigure 2:Zoning MapFigure 3:USDA Web Soil Survey MapFigure 4:NJDEP Wetlands Existing Conditions Plan



### 1. INTRODUCTION

Engineering & Land Planning Associates, Inc. has prepared this Environmental Impact Statement (EIS) on behalf of BHT Properties Group. This EIS has been prepared in accordance with the requirements of Section 131–13, the Environmental Impact Statement Ordinance. The EIS provides an inventory of existing natural resources, an assessment of the environmental impacts of the proposed project, environmental protective measures, and lists unavoidable adverse impacts should the project be implemented per the ordinance.

The proposed project consists of the construction of a construction office with construction equipment and material storage areas on the property located on 248 Stickles Pond Road, on Lot 151, Block 21 in Andover Township, Sussex County, New Jersey. The 100-acre subject property currently consists of a former airport. The proposed project consists of the demolition of hangars, paved drives, concrete pads, three dwellings, two garages, and three sheds. The existing 112,050 square foot asphalt runway is to remain. The proposed construction consists of a 12,860 square foot building, 2,883 square feet of concrete sidewalk and curbing, lighting and landscape improvements, 35,235 square feet to be paved with asphalt for parking and circulation and 1,822,812 square feet to be paved with asphalt millings and used as construction equipment and material storage area. The materials to be stored in site are stone, aggregate, precast concrete structures and other typical natural construction materials.

The significant findings of the EIS include the following:

- 1. The purpose of the project is to construct a construction office with construction equipment and material storage areas and parking spaces. This new facility is proposing an approved use of the Township Zoning Ordinance.
- 2. The potential for soil erosion during the construction process would be minimized through the implementation of a soil erosion and sediment control plan.
- 3. The proposed development includes a proposed stormwater management system that meets all of the quantity, quality, and recharge requirements outlined in Stormwater Management Rules of N.J.A.C. 7:8.
- 4. The increase in municipal services, including the anticipated water and wastewater demand will be accommodated by the installation of a well and septic system by the proposed building.

In summary, it is anticipated that the proposed site improvements can be implemented without creating any appreciable adverse environmental impacts. If environmental impacts are incurred, appropriate mitigation measures will be implemented.



# 2. EXISTING ENVIRONMENTAL CONDITIONS

#### 2.1 Phase I Environmental Site Assessment

The Phase I Environmental Site Assessment has revealed no evidence of Controlled Recognized Environmental Conditions (CRECs). The site did identify Historic Underground Storage Tanks (USTs), which is a Historical Recognized Environmental Condition (HRECs). The area assessed identified three Recognized Environmental Condition (RECs), Those are historic agricultural use and an unidentified Underground Storage Tank. The third Recognized Environmental Condition included two older Aboveground Storage Tanks (ASTs) but no signs of holes or release were reported and the tanks were empty and no longer in use.

#### 2.2 Topography

The topographic relief on the property ranges from 588 to 645 feet above MSL. The surface topography fluctuates from moderately flat land along Stickles Pond Road, the southern part of the property, to various steep sections scattered throughout the property.

#### 2.3 Air Quality

There is no air quality monitoring station in Sussex County. A 2019 Air Quality Index Report from the Passaic County monitoring station shows the average Air Quality Index to be at 40, which is in the range of "Good" quality. The Good Level of Health Concern considers the air quality to be satisfactory, with air pollution posing little or no risk. During Phase I Environmental Investigation, no noxious odors were detected.

#### 2.4 Noise Levels

The noise levels on the site are generally adequate to low due to the surrounding wooded areas and residential lots. The prior airport use would have generated higher noise levels from planes taking off and landing at the site.

#### 2.5 Water Supply and Water Quality

The property is bisected by a sub-watershed, Pequest River (above Brighton). Pequest River tributaries are located near the northwest and northern edges of the property, at least 35 feet from the northwestern corner of the property. The Pequest River flows into Stickle Pond, which is located east adjacent to the property.

The water quality on the site is generally adequate and no known contamination exists on the property. There is a 3.81-acre groundwater contamination area (CEA) approximately 800 feet away from the southwestern edge of the property.



#### 2.6 Drainage

Stormwater run-off follows the surface topography and flows across the site to either the Pequest River tributary or Stickle Pond, as well as draining into the wetlands on and off site. There are no existing stormwater conveyance on the site that collects the generated stormwater runoff.

#### 2.7 Critical Impact Areas

The township identifies areas of significant concern as stream corridors, streams, wetlands, slopes greater than 15%, highly acidic or erodible soils, areas of high-water table, mature strands of native vegetation, aquifer recharge and discharge areas.

NJDEP GeoWeb indicates a Total Maximum Load (TDML) Streamshed for Phosphorous to Address Four Impaired Assessment Units in the Pequest River Watershed, dated 2010 at Pequest River (above Brighton).

Five separate wetlands appear to be completely within the property lines with two other wetlands partially on the site, as seen on Figure 4: NJDEP Wetlands Ex. Conditions Plan. NJDEP GeoWeb lists a 1.4-acre Deciduous Wooded Wetlands is located in the western region on-site and a 0.70-acre Deciduous Scrub/Shrub Wetlands is located on-site at the eastern corner of the property. The wetlands found partially within the property boundary are listed as 4.36-acre Deciduous Wooded Wetlands and 5.81-acre Deciduous Scrub/Shrub Wetlands.

This property is part of the State Planning Area for Limited Growth identified as a Rural Environmentally Sensitive Planning Area, meaning environmental constraints affect development. As part of the NJ Wildlife Action Plan, this site is falls within the Skylands Landscape Region. The site is within a 1,336-acre Vernal Habitat Area with a Vernal Pool Location on site in the western region of the site, at the previously described Deciduous Wooded Wetlands.

Five separate groundwater recharge areas are found within the property boundaries. The Northwest Upper Delaware watershed recharge area found at the northern, eastern, and southwestern portions of the site has a "B" Groundwater Recharge Ranking. The Northwest Upper Delaware watershed recharge area found along the western and northeastern edges of the property has an "A" Groundwater Recharge Ranking. The Northwest Upper Delaware watershed found at the center of the site has a "D" Groundwater Recharge Ranking. The Northwest Upper Delaware watershed found at the center of the site has a "D" Groundwater Recharge Ranking. The Northwest Upper Delaware watershed recharge areas found at the locations of the wetlands have a "W" Groundwater Recharge Ranking, which is identified as wetlands, open water- no recharge calculated and an "L" Groundwater Recharge Ranking, which is identified as hydric soil-no recharge calculated.

NJDEP GeoWeb lists three bedrock aquifers within the boundaries of the site, Jacksonburg Limestone, Kittatinny Supergroup, and Hardyston Quartzite.



#### 2.8 Sewer Systems and Utilities

During Phase I Environmental Investigation, a septic system was identified onsite. According to documents provided by the Township of Andover, the sewage disposal system was installed in 2001, listed as a "Commercial/Institutional" Facility with waste types to be charged listed as "sanitary sewage".

During Phase I Environmental Investigation, a historic pumphouse was identified behind the 214 Stickles Pond residence and a jet pump was observed in the basement of the 210 Stickles Pond Road structure, which appeared to service a hot water heater. Therefore, there are potable wells on-site.

#### 2.9 Geology

The surficial geology beneath the site is Allentown Dolomite. The geology of the site consists of mainly sedimentary rock, specifically dolostone and shale. The dolomite is medium to very light gray color and fine to medium grained. The bedrock aquifers beneath the site are known as Jacksonburg Limestone, Kittatinny Supergroup, and Hardyston Quartzite, according to NJDEP GeoWeb.

#### 2.10 Soils and Slope Stabilities

The <u>USDA Soil Survey of Sussex County, New Jersey</u> as published by the NRCS Web Soil Survey (WSS 2009) indicates that the site is comprised of the following major soil series/phases, as referred to on Figure 3:

- FaxC- Farmington-Rock Outcrop Complex (0 to 15 percent slopes);
- HdxpAb Hazen-Paulins Kill Complex (0 to 3 percent slopes);
- USFARC Urban Land-Farmington-Rock Outcrop Complex (0 to 15 percent slopes)

<u>The USDA Soil Survey of Sussex County, New Jersey</u> indicates that the site primarily contains Hazen-Paulins Kill Complex. The site also contains Farmington-Rock Outcrop Complex and Urban Land-Farmington-Rock Outcrop Complex.

Farmington-Rock Outcrop Complex is referred to as FaxC as indicated on Figure 3. The Farmington-Rock Series consists of well-drained, somewhat excessively drained, loamy till soil derived from limestone and dolomite. They are nearly level to very steep soils on glaciated uplands. This soil complex is classified as high runoff class and Hydrologic Soil Group D.

Hazen-Paulins Kill Complex is referred to as HdxpAb. as indicated on Figure 3. The Hazen-Paulins Kill Series consists of very deep, well-drained, soils made up of gravelly loam, formed in Wisconsin glaciofluvial deposits derived from sandstone and shale. They are nearly level to very steep soils on outwash deltas and valleys associated with proglacial lake basins. This soil complex is classified as Hydrological Soil Group B, having high saturated hydraulic conductivity with surface runoff ranging from low to high.

Urban Land-Farmington-Rock Outcrop Complex is referred to as USFARC as indicated on Figure 3. The parent materials include buildings, pavement, and



other impervious surfaces over loamy till derived from limestone and dolomite. This soil complex is classified as Hydrologic Soil Group D.

#### 2.11 Vegetation

The property is a mixture of open grasslands and dense woods. Generally, the flatter areas are covered by the grasslands and the steeper areas to the west and north are wooded. The vegetated areas are identified as deciduous forest with greater than 50% Crown Closure and deciduous brush and shrubland with some of the clearing identified as cropland and pastureland for former agriculture use.

#### 2.12 Land Use and Demography

The property is located in the C/I Zone of Andover Township and currently consists of a former airport. The property is surrounded by farmlands to the northwest, more dense undeveloped woods and a religious center to the north, and light residential development and few businesses in all other directions. The demographics of the property and the surrounding area is consistent with the demographics of the Township as a whole. The land use is consistent with the Commercial/Industrial zone

#### 2.13 Aesthetics

The 100-acre property is mostly wooded but currently contains an unused 112,050 square foot runway from the former airport. At the eastern corner of the property are several unused buildings, including three unoccupied residences known as 210 Stickles Pond Road, 214 Stickles Pond Road, and 216 Stickles Pond Road. The other unnecessary structures remaining on the property consist of two garages and three sheds.

#### 2.14 History

The property does not contain any historic buildings or resources.



### **3. PROBABLE IMPACTS & MITIGATION**

#### 3.1 Topography

The proposed development includes a proposed grading plan. The proposed topography will provide stable slopes and conveyances for surface water runoff. Natural drainage patterns will be maintained to the extent possible.

#### 3.2 Air Quality

The proposed project will not substantially impact air quality on- or off-site. The sources for potential air pollutants are the construction materials to be stored, but it's not expected to cause a degradation of air quality.

#### 3.3 Noise Levels

The proposed development will not result in any sources of noise or vibration levels in excess of State standards.

#### 3.4 Water Supply and Freshwater Wetlands Protection

The well found during the Phase I Environmental Site Assessment will be removed and a new well is proposed near the proposed building at the south corner of the property, which will service the site.

For the seven areas of wetlands identified on the site, proposed disturbance is to maintain the buffer zones of 150' around the wetlands boundary. According to the proposed grading plan, grading will encroach on the buffer of the wetlands identified as Wetlands B and Wetlands E in Appendix A. The buffers of the wetlands identified as Wetlands A, B, D, E, and F have been previously disturbed for prior development on site.

#### 3.5 Drainage and Flood Protection

The project includes a stormwater management design that has been designed in accordance with NJDEP standards for a Major Stormwater Development Project. The property is within the FEMA Zone X, area of minimal flood hazard.

There is no existing stormwater conveyance along Stickles Pond Road or on the site. The increase in impervious surfaces from the proposed development may result in a degradation of the quality of the stormwater runoff and increased flows across the site. This is mitigated through the use of six above-ground infiltration basins designed to capture, treat, and infiltrate the stormwater runoff. The proposed locations of the referenced systems along with the proposed inlet and conveyances are shown on the "Grading and Drainage Plan" of Appendix A. For the full analysis of existing and proposed drainage on-site, see the Stormwater Management Report (Appendix B).

#### 3.6 Sewer Systems and Utilities

The proposed development will be serviced by the private proposed septic system and proposed well on-site at the southern edge of the property to the



east of the proposed building. The proposed septic system shall be constructed in compliance with the N.J.D.E.P. N.J.A.C. 7:9A, Standards for Individual Subsurface Sewage Disposal Systems and will consists of a septic tank, pump tank, and disposal field.

The project consists of a proposed electric service connection to the utility poles located along Stickles Pond Road, as shown inw Appendix A. A will-serve letter from Jersey Central Power and Light is being sought.

#### 3.7 Geology Stability

The proposed development will have minimal impact on site geology.

#### 3.8 Soil Stability and Erosion Control

There is the potential for short term unavoidable impacts to soil erosion at the site during construction activities. The project will follow all procedures set to minimize soil erosion on and surrounding the site.

Cut and fill of soil on the site is to remain as balanced as possible. The proposed limit of disturbance for the construction of the facility and the proposed grading is 59.79 acres (2,604,395 square feet) and will be kept at a minimum. Locations of proposed silt fencing, a proposed temporary soil stockpile, and recommended soil compaction testing are shown on Erosion & Sediment Control Plan in Appendix A.

#### **3.9 Vegetation**

The property contains densely wooded areas that will be altered as part of the development. This tree removal and tree protection will be mitigated in accordance with the Township tree removal ordinance of on-site tree replacement.

#### 3.10 Land Use and Demography

The proposed use of a construction office with construction equipment and material storage areas is an approved use of the commercial industrial zoning district. The property meets the Townships requirements for this zone: the facility will fall on a lot size greater than 3 acres and proposes less than 60% impervious surface coverage.

#### 3.11 Aesthetics

The proposed development has been designed to be aesthetically pleasing with adequate lighting. The development will include a Lighting and Landscaping Plan, as seen in Appendix A.

#### 3.12 History

No impacts are anticipated to any historic resources.



#### 3.13 Displacement of People and Businesses

The proposed project will have no effect on the displacement of people and businesses.

#### 3.14 Marketability of Proposed Use

The proposed project will result in an increase in employment since a business will be brought to an unused property. The implementation of the project will also create construction jobs.

#### 3.15 Disruption of Desirable Community and Regional Growth

The replacement of the unused airport and unoccupied dwellings with the construction of a construction office with construction equipment and material storage areas will not affect community growth.

#### 3.16 Spill Prevention Measures

The project will be constructed in conformance with all local, state and federal regulations. The proposed construction office with construction equipment and material storage areas do not involve the dismantling of the construction equipment. No parts are removed from the construction equipment and no maintenance is performed on site. No flammable or extra hazardous materials are to be stored on or included in the construction of the site.

In the unlikely event that spillage or leakage were to occur, trained operators have defined protocols to remediate the spillages, as stated in the Operational Manual included as Appendix C.

#### 3.17 Police and Fire Protection and Emergency Health Services

The proposed project does not entail the need for the implementation of increased police protection, emergency health services, or fire protection of the property. Stickles Pond is a natural fire protection resource existing adjacent to the site that is able to provide water for extinguishing any potential fires to occur during construction.

#### 3.18 Traffic

The traffic in the proposed area is expected to increase slightly.

#### 3.19 Solid Waste Generation and Disposal

Any solid waste generation will be picked up from the trash enclosure proposed on-site near the proposed staging and loading area, as seen on in Appendix A.

#### 3.20 Construction Impact

The construction impacts include an increase in noise levels associated with the heavy construction equipment required for site and grading improvements. Construction is to be performed during hours permitted by the



Township's ordinance. Appropriate measures will be taken in accordance to the approved Soil Erosion and Sediment Control to control potential erosion and dust generated during construction.

The construction activities and equipment are to be kept within the property boundaries so that impacts on the surrounding properties are avoided. The proposed grading for the development shall be completed in phases, so that the overall grading improvements within the proposed limits of disturbance are not taking place at once. The construction equipment will be relocated as necessary. Permanent covers will be installed to the areas disturbed before moving construction equipment onto the sequential phase of grading.

### 4. ALTERNATIVES ANALYSIS

#### 4.1 No Build Option

A no build option was considered as part of this alternatives analysis. This would not allow the property owner to realize the economic potential of the property. There would be no new impacts as a result of this option because there would be no changes to the property.

#### 4.2 Less Intensive Option

A less intensive development was considered for the property. This alternative includes less disturbance and less impervious cover. This alternative would result in a slightly reduced footprint of development. However, the property and its surroundings can support the larger development and the reduction in size impacts the economic viability of the project.

### 5. LICENSES, PERMITS & APPROVALS

- Sussex County Planning Board Approval
- NJDEP DLUR Freshwater Wetlands Permits
- NJDEP DLUR Flood Hazard Area Verification


### 6. DOCUMENTATION


The Township of Andover Ordinances were reviewed as part of the preparation of this report. GIS mapping as provided by the NJDEP through its GeoWeb service was consulted during the preparation of the report. United States Environmental Protection Agency Air Quality Data was consulted for 2019 Air Quality Index. Additionally, the applicant was consulted throughout the design process.

















### APPENDIX A: SITE PLANS (ATTACHED SEPARATELY)



APPENDIX B: STORMWATER MANAGEMENT REPORT (ATTACHED SEPARATELY)

